PS2342

Total Power	1000 Watts
Input Voltages	90-264 VAC
Outputs	48V

SPECIAL FEATURES

- Power density > 6W/ cu in.
- 90-264 VAC input with under voltage lockout
- UL, CSA, BABT Recognized, CE CB pending
- Remote on/off control
- Active PFC compliant to EN61000-3-2
- Low profile, fits 2U application
- Third Wire current share
- Hot pluggable
- Fully protected

ENVIRONMENTAL


Ambient Operating Temperature : 0 to +50°C, full rating.

Humidity: Up to 95% non-condensing

Temperature coefficient: \pm 0.01%/ °C

Storage Temperature: -20 to 85°C

Cooling: One 81 CFM fan. Airflow front to back.



ELECTRICAL SPECIFICATIONS Input

Input......90 -264 VAC; 47-63Hz; Power Factor >0.99

Inrush Current (240 Vac)......80 Amps peak Isolation.....4242VDC (Input to Output)

Susceptibility specifications: EN 61000-3-2 AC Input line harmonic limits Complies with EN55022 & FCC Class A with minimum 6 dB margin

Efficiency.....> 83% typical at full load

Output

DC Output......Maximum continuous output power 1000 Watts with internal cooling. See Voltage/Current Rating Chart.

Load Regulation......<1% Ripple and Noise < 350mV typical

Transient Response...2% Maximum deviation; Third Wire Current Share.

MECHANICAL

12.8" L X 3.5" H X 4.3" W (324 mm X 132 mm X 108 mm) *May be installed in 19" rack mountable bay

Status signals and indicators

PS Present DC Power Good AC FAIL warning

Visual LED indicators identify power supply status. The indicators are: AC/`DC Good



Output

Over and under voltage protection – (Latching) Over current protection (Latching)

Over temperature protection.

Short Circuit Protection.....Will withstand a continuous short without damage.

Minimum Load Rqmt.....0% of full load main output.

No Load Operation.....No damage to supply when operating at no load.

Hold-Up Time......20 mSec typical

OVP.....58 V typical

Voltage/Current Rating Chart

Voltage	48V	48.03V
Current	21A	0A

PS ELCON CONNECTOR PIN ASSIGNMENT

Description	PIN
Line Ground	1
Line	2
Neutral	4
+48V	26
48V RTN	28
DC OK	23
PS Present	20
Remote ON/ OFF	17
System GND	14
OVP Test	11

