

A 60-ft tower was erected and instrumented for wind data collection in October 1981 and has been in operation since then. This tower is located on Molokai, in one of the candidate wind turbine locations. Also, turbine, battery, and utility interface equipment data and specifications have been obtained in order to make preliminary selections and for use in a computer model. A simulation code has been developed and is being used to evaluate the value of batteries in various system configurations. Initial results indicate that large batteries (greater than 1000 kW h) do not provide sufficient benefit to justify their cost, but a small battery may be very useful to maintain utility network stability and to reduce peak generating requirements.

Phase II, a 1-yr project, will begin in September 1982 and involves a final system evaluation using the computer model developed in Phase I. A utility-oriented battery system will be evaluated, rather than a site-specific battery/turbine system. Using the optimum system configuration from the modeling work, a blueprint design with complete component specifications will be done by an engineering design subcontractor. A go/no-go decision will be made near the end of Phase II regarding the feasibility of Phase III, system construction and operation.

## **ROCKY FLATS STAND-ALONE WIND/BATTERY EXPERIMENT**

*Rockwell International, Rocky Flats Plant*

The objective is to set up and operate a small turbine with a conventional lead-acid battery in a stand-alone mode. The experiment is expected to permit battery performance and life evaluation in a controlled and instrumented environment. Data from the experiment may permit battery optimization for this application.

A 26-kW h Exide lead-acid battery was purchased after competitive bidding and delivered to SNL prior to being shipped to Rocky Flats. The battery was damaged in shipment, and several months were required to complete the repairs. The battery was shipped to Rocky Flats in late June 1982. It will be instrumented and wired to the test equipment during the summer. A north wind 2-kW d.c. wind turbine is in place and available for use in the experiment. Test startup is planned for September 1982.

The experiment will be operated for 1 yr following startup. Data will be collected and evaluated continuously. Experiment parameters will be adjusted to optimize battery use. If conditions warrant, a second battery (possibly a sealed lead-acid type) will be purchased and readied for use in the experiment starting in early 1984.