

Structural Mimicry of the α -Helix in Aqueous Solution with an Isoatomic $\alpha/\beta/\gamma$ -Peptide Backbone

Tomohisa Sawada and Samuel H. Gellman*

Department of Chemistry, University of Wisconsin, Madison, Wisconsin 53706, United States

Supporting Information

ABSTRACT: Artificial mimicry of α -helices offers a basis for development of protein–protein interaction antagonists. Here we report a new type of unnatural peptidic backbone, containing α -, β -, and γ -amino acid residues in an $\alpha\gamma\alpha\beta\alpha$ repeat pattern, for this purpose. This unnatural hexad has the same number of backbone atoms as a heptad of α residues. Two-dimensional NMR data clearly establish the formation of an α -helix-like conformation in aqueous solution. The helix formed by our 12-mer $\alpha/\beta/\gamma$ -peptide is considerably more stable than the α -helix formed by an analogous 14-mer α -peptide, presumably because of the preorganized β and γ residues employed.

Unnatural oligomers that can reproduce the three-dimensional (3D) shapes and side-chain projection patterns characteristic of natural polypeptides offer a basis for rational development of protein–protein interaction antagonists.¹ Considerable effort has been devoted to mimicry of individual helices, which frequently mediate information transfer in biological systems.² Many alternatives to the α -helical scaffold have been examined, including oligomers based on unnatural peptidic backbones (e.g., β -peptides³) and entirely nonpeptidic oligomers (e.g., oligophenyls⁴). Evaluation of these new designs has typically focused on α -helices two to four turns in length (e.g., mimicry of the p53 N-terminal domain in binding to hDM2,⁵ or mimicry of a BH3 domain in binding to Bcl-2-family proteins⁶); however, epitopes of this size can be effectively mimicked by small molecules.⁷ We have recently shown that the recognition properties of a 10-turn α -helix, the CHR domain of HIV protein gp41, can be recapitulated with α/β -peptide oligomers in which two of every seven among the original α -amino acid residues are replaced by analogous β -amino acid residues (Figure 1).⁸ Oligomers with the $\alpha\beta\alpha\alpha\alpha\beta$ heptad repeat can adopt a helical secondary structure in which each turn contains one extra backbone carbon relative to an α -helix. This backbone alteration confers significant resistance to proteolytic degradation while allowing reasonably good mimicry of the side-chain projection pattern along one side of the helix. However, this mimicry is not perfect: the resulting α/β -peptides have lower affinity for the target surface than does the original α -peptide.

Here we introduce a new foldamer design containing α -, β -, and γ -amino acid residues in an $\alpha\gamma\alpha\beta\alpha$ hexad repeat pattern, which is intended to mimic an $\alpha\alpha\alpha\alpha\alpha\alpha$ heptad without additional backbone atoms (Figure 1a). Both the $\alpha/\beta/\gamma$ hexad




Figure 1. (a) Three backbones that correspond to approximately two helical turns: $\alpha\alpha\alpha\alpha\alpha\alpha\alpha$, $\alpha\beta\alpha\alpha\alpha\beta$, $\alpha\gamma\alpha\beta\alpha$; (b) helical wheels for the $\alpha\gamma\alpha\beta\alpha$ hexad and the $\alpha\alpha\alpha\alpha\alpha\alpha\alpha$ heptad.

and the all- α heptad correspond to two helical turns.⁹ The helical wheel juxtaposition in Figure 1b shows that the $\alpha\gamma\alpha\beta\alpha$ repeat potentially allows a direct correspondence between the α residues of this hexad and four of the α residues in a standard peptide heptad. In the parlance of coiled coil-forming sequences, the common α residues could correspond to positions *a*, *d*, *e*, and *g* of an all- α heptad repeat, which define a large and continuous surface that runs along one side of the helix.¹⁰

In order to test the α -helix mimicry hypothesis outlined above, we prepared $\alpha/\beta/\gamma$ -peptide 12-mer **1** via solid-phase methods. All of the α residues in **1** are derived from proteinogenic amino acids. The helix-forming properties of β -amino acid residues¹¹ and γ -amino acid residues¹² have been widely studied, and based on these precedents we employed conformationally preorganized β and γ residues that seemed likely to maximize the propensity of **1** to adopt an α -helix-like conformation (Figure 2). The β residues are derived from (*S,S*)-*trans*-2-aminocyclopentanecarboxylic acid (ACPC), which promotes helical α/β -peptide conformations that strongly resemble the α -helix,¹³ including the gp41 CHR-mimetic oligomers mentioned above.⁸ The γ residues in **1** are derived from α -ethyl-*cis*-2-aminocyclohexanecarboxylic acid (EtACHA; **3**), which has recently been shown to participate in helical conformations.¹⁴

Received: March 9, 2011

Published: April 26, 2011





Figure 2. Sequences for $\alpha/\beta/\gamma$ -peptide 1 and α -peptide 2. Proteinogenic α residues are indicated with the conventional single-letter code; for nonproteinogenic α residues, Orn = ornithine and Nle = norleucine; the β and γ residue structures are shown.



The α - and β -amino acid residues of 1 were incorporated via microwave-assisted solid-phase synthesis employing common reagents.¹⁵ Coupling of Fmoc-EtACHA to the growing polypeptide proved to be challenging, because of intrinsically limited reactivity (perhaps resulting from steric hindrance) and a tendency toward epimerization, presumably at the α -position of the γ -amino acid backbone. The best method for addition of Fmoc-EtACHA proved to be the use of 4 equiv of HOAt and EDCI in DMF for 6 h at room temperature (no microwave irradiation).

$\alpha/\beta/\gamma$ -Peptide 1 is highly water-soluble and displayed sufficient ¹H NMR resonance dispersion to enable 2D NMR analysis in aqueous solution (8 mM 1, 9:1 H₂O/D₂O, 100 mM acetate buffer, pH 3.8, 10 °C). Resonances from backbone amides and

side chains (6.5–9.0 ppm) were monitored between 0.02 and 14 mM 1; no concentration-dependent variations in chemical shift were observed, which suggests that 1 does not self-associate under these conditions. Numerous NOEs were detected between protons on sequentially nonadjacent residues ($i \rightarrow i+2$ or $i \rightarrow i+3$; Figure 3a,b), all of which could be accommodated by a single helical conformation. The expected alignment of the β and γ residues along one side of this helix was indicated by characteristic NOE patterns: EtACHA C _{γ} H (i) \rightarrow ACPC NH ($i+3$) and ACPC C _{β} H (i) \rightarrow EtACHA NH ($i+3$). These NOEs between β and γ residues were detected even at 50 °C, which implies that the helical conformation of $\alpha/\beta/\gamma$ -peptide 1 is quite robust. Further evidence of $\alpha/\beta/\gamma$ -peptide helix stability was obtained from H/D exchange studies. When 1 was dissolved in D₂O at room temperature, some NH resonances disappeared completely within 4 min (the backbone NH of Glu 1 and the side-chain NH resonances of Lys, Arg, and Gln), but most of the backbone NH resonances could be detected even after 1 h. α -Peptide 14-mer 2 was prepared for direct comparison with 1, but the ¹H NMR spectrum of 2 displayed poor dispersion, which precluded resonance assignment and 2D NMR analysis.

NOE-restrained molecular dynamics calculations for $\alpha/\beta/\gamma$ -peptide 1 in aqueous buffer were carried out with the CNS program.¹⁶ Only $i \rightarrow i+1$, $i \rightarrow i+2$ and $i \rightarrow i+3$ NOEs were used for these calculations. Good overlap among backbone atoms was observed for the 10 best among 1000 calculated structures (rmsd = 0.86 \pm 0.24 Å; Figure 3c). Figure 3d shows superimposition of the average of these 10 helical structures for 1 on a canonical α -helix.¹⁷ Of particular interest is the overlap between the six central α residues of 1 and the corresponding residues of the α -helix (the terminal α residues of 1 were excluded from this comparison because of expected “fraying” effects). For overlay of the two sets of six α -carbons, rmsd = 0.98 \pm 0.50 Å.¹⁸ Inspection




Figure 3. (a) Structure of $\alpha/\beta/\gamma$ -peptide 1 with NOEs observed in aqueous buffer between nonadjacent residues indicated by curved arrows (8 mM peptide in 100 mM acetate buffer, pH 3.8); (b) NOEs indicated on the $\alpha/\beta/\gamma$ -peptide helix wheel; (c) overlay of the 10 best conformations generated via NOE-restrained dynamics (see text for details); (d) stereoview of the average of the 10 structures from the NOE-strained dynamics simulations (blue backbone) overlaid on a canonical α -helix (black backbone).




Figure 4. Circular dichroism data for $\alpha/\beta/\gamma$ -peptide **1** and α -peptide **2** in 10 mM aqueous acetate buffer, pH 3.8, or 50 vol % aqueous methanol (one volume of methanol added to the aqueous buffer). The concentration of peptides is 0.2 mM.

of the stereoview in Figure 3d shows that the C_{α} -to-side chain vectors for these two sets of α residues are largely coincident.

We turned to circular dichroism (CD) to compare $\alpha/\beta/\gamma$ -peptide **1** and α -peptide **2**, because the latter could not be studied via 2D NMR. Figure 4 shows far-UV CD data for **1** and **2** in aqueous buffer and in 50 vol % aqueous methanol. In aqueous solution, the CD signature of α -peptide **2** suggests a largely unfolded state. In the presence of 50 vol % methanol **2** manifests a typical α -helical CD signature, with minima at ~ 208 and ~ 222 nm; the pronounced helix-promoting impact of the organic cosolvent is typical for short α -peptides. The behavior of $\alpha/\beta/\gamma$ -peptide **1** is quite different in that the CD signature is not strongly affected by changing the solvent. In both cases a single strong minimum is observed (~ 204 nm in aqueous buffer, ~ 205 nm in aqueous methanol), with only a minor intensity difference between solvents. Since NMR analysis indicates substantial population of an α -helix-like conformation by **1** in aqueous buffer, we assign the CD signature observed for **1** to this conformation. A similar far-UV CD signature has been established for α -helix-like conformations adopted by α/β -peptides;¹³ it is unclear why these heterogeneous peptidic backbones fail to manifest a second minimum in the helical state. The fact that similar CD signatures are observed for **1** in aqueous buffer and in 50% aqueous methanol suggests that the α -helix-like conformation of this $\alpha/\beta/\gamma$ -peptide is highly populated even in a fully aqueous environment, an extent of folding that would be unusual for a linear α -peptide of comparable length. Further evidence of the high stability of the $\alpha/\beta/\gamma$ -peptide **1** helix is provided by variable-temperature CD: the minimum at ~ 204 nm becomes less intense on heating from 10 to 90 °C, as expected from thermally induced unfolding, but at 90 °C this minimum retains $\sim 70\%$ of the intensity observed at 10 °C.¹⁹

We have introduced a new type of heterogeneous peptidic foldamer and shown via 2D NMR that this system supports a helical conformation in aqueous solution. The $\alpha\gamma\alpha\alpha\beta\alpha$ hexad pattern we designed leads to mimicry of the side-chain display along one side of an α -helix, despite the presence of nonproteinogenic backbone components. Direct comparison with a conventional α -peptide reveals that the $\alpha/\beta/\gamma$ -peptide has a much stronger folding propensity, a feature that should facilitate the

development of biologically active examples. The high stability of the new $\alpha/\beta/\gamma$ -peptide helix is attributed to the use of appropriately preorganized β and γ residues. Additional studies will be required to determine whether other $\alpha\alpha\alpha\alpha+\beta+\gamma$ hexads with different subunit ordering give rise to stable helical conformations. To our knowledge, this study represents the first example of high-resolution structural analysis of a γ -amino acid-containing foldamer in aqueous solution. It will now be important to determine whether the $\alpha/\beta/\gamma$ -peptide design introduced here can support functional mimicry of biological α -helices.

■ ASSOCIATED CONTENT

S Supporting Information. All experimental procedures and data; complete ref 7b. This material is available free of charge via the Internet at <http://pubs.acs.org>.

■ AUTHOR INFORMATION

Corresponding Author

gellman@chem.wisc.edu

■ ACKNOWLEDGMENT

This research was supported in part by the NSF (CHE-0848847). T.S. was supported in part by a JSPS Postdoctoral fellowship for Research Abroad. NMR spectrometers were purchased with partial support from NSF and NIH. We thank Aaron Almeida for assistance of NMR measurements, and Michael Giuliano and Dr. Li Guo for helpful discussion.

■ REFERENCES

- (1) (a) Goodman, C. M.; Choi, S.; Shandler, S.; DeGrado, W. F. *Nat. Chem. Biol.* **2007**, *3*, 252–262. (b) Hecht, S.; Huc, L., Eds. *Foldamers: Structure, Properties, and Applications*; Wiley-VCH: Weinheim, Germany, 2007.
- (2) (a) Jochim, A. L.; Arora, P. S. *ACS Chem. Biol.* **2010**, *5*, 919–923. (b) Jochim, A. L.; Arora, P. S. *Mol. BioSyst.* **2009**, *5*, 924–926.
- (3) (a) Werder, M.; Hauser, H.; Abele, S.; Seebach, D. *Helv. Chim. Acta* **1999**, *82*, 1774–1783. (b) Kritzer, J. A.; Lear, J. D.; Hodsdon, M. E.; Schepartz, A. *J. Am. Chem. Soc.* **2004**, *126*, 9468–9469. (c) English, E. P.; Chumanov, R. S.; Gellman, S. H.; Compton, T. *J. Biol. Chem.* **2006**, *281*, 2661–2667.
- (4) (a) Orner, B. P.; Ernst, J. T.; Hamilton, A. D. *J. Am. Chem. Soc.* **2001**, *123*, 5382–5383. (b) Kutzi, O.; Park, H. S.; Ernst, J. T.; Orner, B. P.; Yin, H.; Hamilton, A. D. *J. Am. Chem. Soc.* **2002**, *124*, 11838–11839. (c) Davis, J. M.; Tsou, L. K.; Hamilton, A. D. *Chem. Soc. Rev.* **2007**, *36*, 326–334. (d) Hu, X.; Sun, J.; Wang, H.-G.; Manetsch, R. *J. Am. Chem. Soc.* **2008**, *130*, 13820–13821. (e) Shaginian, A.; Whitby, L. R.; Hong, S.; Hwang, I.; Farooqi, B.; Searcey, M.; Chen, J.; Vogt, P. K.; Boger, D. L. *J. Am. Chem. Soc.* **2009**, *131*, 5564–5572. (f) Marimnganti, S.; Cheemala, M. N.; Ahn, J.-M. *Org. Lett.* **2009**, *11*, 4418–4421. (g) Plante, J. P.; Burnley, T.; Malkova, B.; Webb, M. E.; Warriner, S. L.; Edwards, T. A.; Wilson, A. J. *Chem. Commun.* **2009**, 5091–5093. (h) Campbell, F.; Plante, J. P.; Edwards, T. A.; Warriner, S. L.; Wilson, A. J. *Org. Biomol. Chem.* **2010**, *8*, 2344–2351.
- (5) Murray, J. K.; Gellman, S. H. *Biopolymers* **2007**, *88*, 657–686.
- (6) Youle, R. J.; Strasser, A. *Nat. Rev. Mol. Cell Biol.* **2008**, *9*, 47–59.
- (7) (a) Vassilev, L. T.; Vu, B. T.; Graves, B.; Carvajal, D.; Podlaski, F.; Filipovic, Z.; Kong, N.; Kammlott, U.; Lukacs, C.; Klein, C.; Fotouhi, N.; Liu, E. A. *Science* **2004**, *303*, 844–848. (b) Oltersdorf, T.; et al. *Nature* **2005**, *435*, 677–681. (c) Lessene, G.; Czabotar, P. E.; Colman, P. M. *Nat. Rev. Drug Discov.* **2008**, *7*, 989–1000.

(8) Horne, W. S.; Johnson, L. M.; Ketas, T. J.; Klasse, P. J.; Lu, M.; Moore, J. P.; Gellman, S. H. *Proc. Natl. Acad. Sci. U.S.A.* **2009**, *106*, 14751–14756.

(9) (a) For crystal structures showing that a β -alanine- γ -aminobutyric acid dipeptide segment can replace a tri- α -peptide segment in short helical oligomers, see: Karle, I. L.; Pramanik, A.; Banerjee, A.; Bhattacharjya, S.; Balaram, P. *J. Am. Chem. Soc.* **1997**, *119*, 9087–9095. (b) For related work, see: Araghi, R. R.; Jäckel, C.; Cölfen, H.; Salwiczek, M.; Völkel, A.; Wagner, S. C.; Wiczorek, S.; Baldauf, C.; Kokschi, B. *ChemBioChem* **2010**, *11*, 335–339. Araghi, R. R.; Kokschi, B. *Chem. Commun.* **2011**, 3544–3546.

(10) (a) Woolfson, D. N. *Adv. Protein Chem.* **2005**, *70*, 79–112. (b) Grigoryan, G.; Keating, A. E. *Curr. Opin. Struct. Biol.* **2008**, *18*, 477–483.

(11) (a) Cheng, R. P.; Gellman, S. H.; DeGrado, W. F. *Chem. Rev.* **2001**, *101*, 3219–3232. (b) Seebach, D.; Gardiner, J. *Acc. Chem. Res.* **2008**, *41*, 1366–1375.

(12) (a) Hanessian, S.; Luo, X.; Schaum, R.; Michnick, S. *J. Am. Chem. Soc.* **1998**, *120*, 8569–8570. (b) Hintermann, T.; Gademann, K.; Jaun, B.; Seebach, D. *Helv. Chim. Acta* **1998**, *81*, 983–1002. (c) Seebach, D.; Hook, D. F.; Glättli, A. *Biopolymers* **2006**, *84*, 23–37.

(13) (a) Horne, W. S.; Price, J. L.; Keck, J. L.; Gellman, S. H. *J. Am. Chem. Soc.* **2007**, *129*, 4178–4180. (b) Horne, W. S.; Price, J. L.; Gellman, S. H. *Proc. Natl. Acad. Sci. U.S.A.* **2008**, *105*, 9151–9156. (c) Price, J. L.; Horne, W. S.; Gellman, S. H. *J. Am. Chem. Soc.* **2010**, *132*, 12378–12387.

(14) (a) Guo, L.; Chi, Y.; Almeida, A. M.; Guzei, I. A.; Parker, B. K.; Gellman, S. H. *J. Am. Chem. Soc.* **2009**, *131*, 16018–16020. (b) Guo, L.; Almeida, A. M.; Zhang, W.; Reidenbach, A. G.; Choi, S. H.; Guzei, I. A.; Gellman, S. H. *J. Am. Chem. Soc.* **2010**, *132*, 7868–7869. (c) For related γ -amino acid building blocks, see: Nodes, W. J.; Nutt, D. R.; Chippindale, A. M.; Cobb, A. J. A. *J. Am. Chem. Soc.* **2009**, *131*, 16016–16017.

(15) (a) Murray, J. K.; Gellman, S. H. *Org. Lett.* **2005**, *7*, 1517–1520. (b) Murray, J. K.; Gellman, S. H. *Nat. Protoc.* **2007**, *2*, 624–631.

(16) (a) Brünger, A. T.; Adams, P. D.; Clore, G. M.; DeLano, W. L.; Gros, P.; Grosse-Kunstleve, R. W.; Jiang, J.-S.; Kuszewski, J.; Nilges, M.; Pannu, N. S.; Read, R. J.; Rice, L. M.; Simonson, T.; Warren, G. L. *Acta Crystallogr.* **1998**, *D54*, 905–921. (b) Brünger, A. T. *Nat. Protoc.* **2007**, *2*, 2728–2733.

(17) The canonical α -helix structure was built by molecular modeling using *HyperChem*, 8.0.6.

(18) Superimposition of two helices was carried out by using the *pair fitting* function in *PyMol*, 1.3.

(19) See Supporting Information.