CECW-EH-Y  Engineer  Manual  1110-2-1415	Department of the Army U.S. Army Corps of Engineers Washington, DC 20314-1000	EM 1110-2- 1415 5 March 1993
	Engineering and Design	
	HYDROLOGIC FREQUENCY ANALYSIS	
	Distribution Restriction Statement Approved for public release; distribution is unlimited.	

# U.S. Army Corps of Engineers Washington, D.C. 20314-1000

CECW-EH-Y

Engineer Manual No. 1110-2-1415

5 March 1993

# Engineering and Design HYDROLOGIC FREQUENCY ANALYSIS

- 1. <u>Purpose</u>. This manual provides guidance and procedures for frequency analysis of: flood flows, low flows, precipitation, water surface elevation, and flood damage.
- 2. Applicability. This manual applies to major subordinate commands, districts, and laboratories having responsibility for the design of civil works projects.
- 3. General. Frequency estimates of hydrologic, climatic and economic data are required for the planning, design and evaluation of flood control and navigation projects. The text illustrates many of the statistical techniques appropriate for hydrologic problems by example. The basic theory is usually not provided, but references are provided for those who wish to research the techniques in more detail.

FOR THE COMMANDER:

WILLIAM D. BROWN Colonel, Corps of Engineers

Chief of Staff

CECW-EH-Y

Engineer Manual No. 1110-2-1415

5 March 1993

# Engineering and Design HYDROLOGIC FREQUENCY ANALYSIS

# Table of Contents

		Subject	Paragraph	Page
CHAPTER	1	INTRODUCTION		
		Purpose and Scope	1-1	<b>i</b> - 1
		References	1-2	1 - 1
		Definitions	1-3	1-1
		Need for Hydrologic Frequency Estimates	1-4	1-1
		Need for Professional Judgement	1-5	1-2
CHAPTER	2	FREQUENCY ANALYSIS		
		Definition	2-1	2-1
		Duration Curves	2-2	2-3
		Selection of Data for Frequency Analysis	2-3	2-6
		Graphical Frequency Analysis	2-4	2-10
		Analytical Frequency Analysis	2-5	2-12
CHAPTER	3	FLOOD FREQUENCY ANALYSIS		
		Introduction	3-1	3-1
		Log-Pearson Type III Distribution	3-2	3-1
		Weighted Skew Coefficient	3-3	3-6
		Expected Probability	3-4	3-7
		Risk	3-5	3-10
		Conditional Probability Adjustment	3-6	3-11
		Two-Station Comparison	3-7	3-13
		Flood Volumes	3-8	3-18
		Effects of Flood Control Works on		
		Flood Frequencies	3-9	3-22
		Effects of Urbanization	3-10	3-28
CHAPTER	4	LOW-FLOW FREQUENCY ANALYSIS		
		Uses	4-1	4-1
		Interpretation	4-2	4-1
		Application Problems	4-3	4_1

	_	Subject	Paragraph	Page
CHAPTER	5	PRECIPITATION FREQUENCY ANALYSIS		
		General Procedures	5-1	5 - 1
		Available Regional Information  Derivation of Flood-Frequency Relations	5-2	5-2
		from Precipitation	5-3	5-2
CHAPTER	6	` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` `		
		Uses	6-1	6-1
		Stage Data	6-2	6-1
		Frequency Distribution	6-3	6-2
		Expected Probability	6-4	6-2
CHAPTER	7	DAMAGE-FREQUENCY RELATIONSHIPS		
		Introduction	7-1	7 - 1
		Computation of Expected Annual Damage	7-2	7 – 1
		Equivalent Annual Damage	7-3	7-3
CHAPTER	8	STATISTICAL RELIABILITY CRITERIA		
		Objective	8-1	8-1
		Reliability of Frequency Statistics	8-2	8-1
		Reliability of Frequency Curves	8-3	8-1
CHAPTER	9	REGRESSION ANALYSIS AND APPLICATION STUDIES	TO REGIONAL	_
		Nature and Application	9-1	9-1
		Calculation of Regression Equations The CorrelationCoefficient and Standard	9-2	9-1
		Error	9-3	9-3
		Simple Linear Regression Example	9-4	9-4
		Factors Responsible of Nondetermination	9-5	9-7
		Multiple Linear Regression Example	9-6	9-8
		Partial Correlation	9-7	9-8
		Verification of Regression Results	9-8	9-10
		Regression by Graphical Techniques	9-9	9-10
		Practical Guidelines	9-10	9-10
		Regional Frequency Analysis	9-11	9-11
CHAPTER	10	ANALYSIS OF MIXED POPULATIONS		
		Definition	10-1	10-1
		Procedure	10-2	10-1
		Cautions	10-3	10-2
CHAPTER	11	FREQUENCY OF COINCIDENT FLOWS		
		Introduction	11-1	11-1
		A Procedure for Coincident Frequency Analysis	11-2	11-1

		Subject	Paragraph	Pag
CHAPTER	12	STOCHASTIC HYDROLOGY Introduction Applications Basic Procedure Monthly Streamflow Model Data Fill In Application In Areas of Limited Data Daily Streamflow Model Reliability	12-1 12-2 12-3 12-4 12-5 12-6 12-7 12-8	12- 12- 12- 12- 12- 12- 12- 12-
APPENDIX	Α	SELECTED BIBLIOGRAPHY References and Textbooks	A B	A- A-
APPENDIX	В	GLOSSARY		B-
APPENDIX	С	COMPUTATION PROCEDURE FOR EXTREME VALUE (GUMBEL) DISTRIBUTION		<b>C-</b> 3
APPENDIX	D	HISTORIC DATA		D-
APPENDIX	E	EXAMPLES OF RELIABILITY TESTS FOR THE MEAN AND STANDARD DEVIATION		E-1
APPENDIX	F	STATISTICAL TABLES  Median Plotting Positions  Deviates for Pearson Type III Distribution  Normal Distribution  Percentage Points of the One-Tailed  t-Distribution  Values of Chi-Square Distribution		F-1 F-2 F-4 F-6 F-7
		Values of the F Distribution  Deviates for the Expected Probability  Adjustment		F-9
		Percentages for the Expected Probability Adjustment		F-l
		Confidence Limit Deviates for Normal Distribution		F-1
		Coefficient		F-1
		Significance Level)		F-1 F-1

# List of Figures

Title	Number	Page
Histogram and Probability Density Function	2-1a	2-2
Sample and Theoretical Cumulative Distribution Functions	2-1b	2-2
Daily Flow-Duration Curve	2-2	2-3
Daily Flow-Duration Curves for Each Month	2-3	2-5
Illustration of Chronologic Sequence and Arrayed Flood Peaks.	2-4	2-9
Example of Graphical Frequency Analysis	2-5	2-12
Partial Duration Frequency Curve, Log-Log Paper	2-6a	2-12
Partial Duration Frequency Curve, Probability Paper	2-6b	2-14
Annual Frequency Curve	3-1	3-4
Confidence Limit Curves based on the Non-central t-Distribution	3-2	3-8
Cumulative Probability Distribution of Exceedances per 100 Years	3-2	3-8
Two-Station Comparison Computations	3-3 3-4	3-16
	3-4 3-5	3-10
Observed and Two-Station Comparison Frequency Curves		3-17
Coordination of Flood-Volume Statistics	3-6	3-20
Flood-Volume Frequency Curves	3-7	
Flood-Volume Frequency Relations	3-8a	3-23
Storage Requirement Determination	3-8b	3-23
Daily Reservoir Elevation-Duration Curve	3-9	3-25
Seasonal Variation of Elevation-Duration Relations	3-10	3-25
Example With-Project versus Without-Project Peak Flow Relations	3-11	3-27
Example Without-Project and With-Project Frequency Curves.	3-12	3-27
Typical Effect of Urbanization on Flood Frequency Curves	3-13	3-29
Low-Flow Frequency Curves	4-1	4-3
Frequency Curve, Annual Precipitation	5-1	5-1
Flow-Frequency Curve, Unregulated and Regulated Conditions	6-1	6-1
Rating Curve for Present Conditions	6-2	6-3
Derived Stage-Frequency Curves, Unregulated and		
Regulated Conditions	6-3	6-3
Maximum Reservoir Elevation-Frequency Curve	6-4	6-4
Schematic for Computation of Expected Annual Damage	7-1	7-2
Frequency Curve with Confidence Limit Curves	8-1	8-2
Computation of Simple Linear Regression Coefficients	9-1	9-5
Illustration of Simple Regression	9-2	9-6
Example Multiple Linear Regression Analysis	9-3	9-9
Regression Analysis for Regional Frequency Computations	9-4	9-14
Regional Analysis Computations for Mapping Errors	9-5	9-15
Regional Map of Regression Errors	9-6	9-15
Annual Peaks and Sequential Computed Skew by Year	9-7	9-18
Nonhurricane, Hurricane and Combined Flood Frequency Curves	10-1	10-3
Illustration of Water-Surface Profiles in Coincident		
Frequency Analysis	11-1	11-2
Data Estimation from Regression Line	12-1a	12-2
Data Ferimation with Addition of Random Frons	12-1b	12_2

# List of Tables

Title	Number	Page	
Daily Flow-Duration Data and Interpolated Values	2-1	2-4	
Annual Peaks, Sequential and Arrayed with Plotting Positions	2-2	2-11	
Partial Duration Peaks, Arrayed with Plotting Positions	2-3	2-13	
Computed Frequency Curve and Statistics	3-1	3-3	
High-Flow Volume-Duration Data	3-2	3-18	
Low-Flow Volume-Duration Data	4-1	4-2	

# ENGINEERING AND DESIGN HYDROLOGIC FREQUENCY ANALYSIS

#### CHAPTER 1

#### INTRODUCTION

- 1-1. <u>Purpose and Scope</u>. This manual provides guidance in applying statistical principles to the analysis of hydrologic data for Corps of Engineers Civil Works activities. The text illustrates, by example, many of the statistical techniques appropriate for hydrologic problems. The basic theory is usually not provided, but references are provided for those who wish to research the techniques in more detail.
- 1-2. <u>References</u>. The techniques described herein are taken principally from "Guidelines for Determining Flood Flow Frequency" (46)<sup>1</sup>, "Statistical Methods in Hydrology" (1), and "Hydrologic Frequency Analysis" (41). References cited in the text and a selected bibliography of literature pertaining to frequency analysis techniques are contained in Appendix A.
- 1-3. <u>Definitions</u>. Appendix B contains a list of definitions of terms common to hydrologic frequency analysis and symbols used in this manual.

# 1-4. Need for Hydrologic Frequency Estimates.

- a. Applications. Frequency estimates of hydrologic, climatic and economic data are required for the planning, design and evaluation of water management plans. These plans may consist of combinations of structural measures such as reservoirs, levees, channels, pumping plants, hydroelectric power plants, etc., and nonstructural measures such as flood proofing, zoning, insurance programs, water use priorities, etc. The data to be analyzed could be streamflows, precipitation amounts, sediment loads, river stages, lake stages, storm surge levels, flood damage, water demands, etc. The probability estimates from these data are used in evaluating the economic, social and environmental effects of the proposed management action.
- b. Objective. The objective of frequency analysis in a hydrologic context is to infer the probability that various size events will be exceeded or not exceeded from a given sample of recorded events. Two basic problems exist for most hydrologic applications. First the sample is usually small, by statistical standards, resulting in uncertainty as to the true probability. And secondly, a single theoretical frequency distribution does not always fit a particular data-type equally well in all applications. This manual provides guidance in fitting frequency distributions and construction of confidence limits. Techniques are presented which can possibly reduce the errors caused by small sample sizes. Also, some types of data are noted which usually do not fit any theoretical distributions.
- c. General Guidance. Frequency analysis should not be done without consideration of the primary application of the results. The application will have a bearing on the type of analysis (annual series or partial duration series), number of stations to be included,

<sup>&</sup>lt;sup>1</sup> Numbered references refer to Appendix A, Selected Bibliography.

whether regulated frequency curves will be needed, etc. A frequency study should be well coordinated with the hydrologist, the planner and the economist.

1-5. Need for Professional Judgment. It is not possible to define a set of procedures that can be rigidly applied to each frequency determination. There may be applications where more complex joint or conditional frequency methods, that were considered beyond the scope of this guidance, will be required. Statistical analyses alone will not resolve all frequency problems. The user of these techniques must insure proper application and interpretation has been made. The judgment of a professional experienced in hydrologic analysis should always be used in concert with these techniques.

#### CHAPTER 2

# FREQUENCY ANALYSIS

# 2-1. Definition.

- a. Frequency. Many of the statistical techniques that are applied to hydrologic data (to enable inferences to be made about particular attributes of the data) can be labeled with the term "frequency analysis" techniques. The term "frequency" usually connotes a count (number) of events of a certain magnitude. To have a perspective of the importance of the count, the total number of events (sample size) must also be known. Sometimes the number of events within a specified time is used to give meaning to the count, e.g., two daily flows were this low in 43 years. The probability of a certain magnitude event recurring again in the future, if the variable describing the events is continuous, (as are most hydrologic variables), is near zero. Therefore, it is necessary to establish class intervals (arbitrary subdivisions of the range) and define the frequency as the number of events that occur within a class interval. A pictorial display of the frequencies within each class interval is called a histogram (also known as a frequency polygon).
- b. Relative Frequency. Another means of representing the frequency is to compute the relative frequency. The relative frequency is simply the number of events in the class interval divided by the total number of events:

$$\mathbf{f}_{i} = \mathbf{n}_{i}/\mathbf{N} \tag{2-1}$$

where:

f; = relative frequency of events in class interval i

n; = number of events in interval i

N = total number of events

A graph of the relative frequency values is called a frequency distribution or histogram, Figure 2-1a. As the number of observations approaches infinity and the class interval size approaches zero, the enveloping line of the frequency distribution will approach a smooth curve. This curve is termed the probability density function (Figure 2-1a).

c. <u>Cumulative Frequency</u>. In hydrologic studies, the probability of some magnitude being exceeded (or not exceeded) is usually the primary interest. Presentation of the data in this form is accomplished by accumulating the probability (area) under the probability density function. This curve is termed the cumulative distribution function. In most statistical texts, the area is accumulated from the smallest event to the largest. The accumulated area then represents non-exceedance probability or percentage (Figure 2-1b). It is more common in hydrologic studies to accumulate the area from the largest event to the smallest. Area accumulated in this manner represents exceedance probability or percentage.




Figure 2-1a. Histogram and Probability Density Function.




Figure 2-1b. Sample and Theoretical Cumulative Distribution Functions.

#### 2-2. Duration Curves.

a. <u>Computation</u>. The computation of flow-duration curves was probably the first attempt to analyze hydrologic data by statistical techniques. The events for flow-duration curves are usually mean daily flow values. One of the first steps in preparation of a duration curve is dividing the range of the data into class intervals. Table 2-1 shows the class intervals of daily flows input into the computer program STATS (58) for a duration analysis of Fishkill Creek at Beacon, New York. The flows tend to be grouped near the low end with very few large flows. Therefore, the relative frequency curve is skewed to the right. It has been found that making the logarithmic transform reduces the skewness of the curve. The class intervals in Table 2-1 are based on a logarithmic distribution of the flows. Plotting the data in Table 2-1 on log-probability paper, Figure 2-2, provides a plot that is easily read at the extremities of the data. The daily flow-duration curve cannot be considered a frequency curve in the true sense, because the daily flow on a particular day is highly correlated with the flow on the preceding day. For this reason, the abscissa is labeled "percent of time."




Figure 2-2. Daily Flow-Duration Curve.

Table 2-1. Daily Flow-Duration Data and Interpolated Values.

-	DURATION	DATA- FI	SHKILL C	R AT BE	ACON, NY	- :	DAILY FL	.OWS			••••	
***	CLASS NUMBER	LOWER CLASS LIMIT FLOW,CFS	NUMBER IN CLASS	ACCUM NUMBER	PERCENT EQUAL OR EXCEED	* * * *	CLASS NUMBER	LOWER CLASS LIMIT FLOW, CFS	NUMBER IN CLASS	ACCUM NUMBER	PERCENT EQUAL OR EXCEED	* * *
*	1	1.00	5	8766	100.00	*	16	100.00	888	5606	63.95	*
-	2	2.00	4	8761	99.94	*	17	150.00	783	4718	53.82	*
*	3	3.00	8	8757	99.90	*	18	200.00	1246	3935	44.89	*
*	4	4.00	22	8749	99.81	*	19	300.00	822	2689	30.68	*
*	5	5.00	37	8727	99.56	*	20	400.00	484	1867	21.30	*
•	6	6.00	56	8590	99.13	*	21	500.00	340	1383	15.78	*
*	7	8,00	95	8624	98.38	*	22	600.00	465	1043	11.90	*
*	8	10.00	254	8529	97.30	*	23	800.00	239	578	6.59	*
*	9	15.00	261	8275	94.40	*	24	1000.00	251	339	3.87	*
*	10	20.00	423	8014	91.42	*	25	1500.00	47	88	1.00	*
*	11	30.00	405	7591	85.50	*	26	2000.00	32	41	0.47	*
*	12	40.00	359	7186	81.98	*	27	3000.00	6	9	0.10	*
*	13	50.00	332	6827	77.88	*	28	4000.00	ō	3	0.03	*
*	14	60.00	480	6495	74.09	*	29	6000.00	3	3	0.03	*
*	15	80.00	409	6015	68.62	*	30	7000.00	Ö	, , , , , , , , , , , , , , , , , , ,	0.00	*

-INTERPOLATED DURATION CURVE- FISHKILL CR AT BEACON, NY - DAILY FLOWS

* * *	PERCENT EQUAL OR EXCEED	INTERPOLATED MAGNITUDE FLOW, CFS	*	PERCENT EQUAL OR EXCEED	Interpolated Magnitude Flow, CFS	*
**	0.01 0.05 0.10 0.20 0.50 1.00 2.00 5.00 10.00 15.00 20.00	6970.0 3480.0 3020.0 2530.0 1960.0 1500.0 1230.0 903.0 658.0 518.0 420.0	* * * * * * * * * * * * * * * * * * * *	60.00 70.00 80.00 85.00 90.00 95.00 98.00 99.00 99.50 99.80	118.0 74.5 44.7 33.4 22.7 14.0 8.8 6.3 5.2 4.0 2.9	***
- * *	40.00 50.00	230.0 171.0	*	99.95 99.99 100.00	1.9 1.5 1.1	*

Output from HEC computer program STATS.

b. <u>Uses</u>. Duration curves are useful in assessing the general low flow characteristics of a stream. If the lower end drops rapidly to the probability scale, the stream has a low ground-water storage and, therefore, a low or no sustained flow. The overall slope of the flow-duration curve is an indication of the flow variability in the stream. Specific uses that have been made of duration curves are: 1) assessing the hydropower potential of run-of-river plants; 2) determining minimum flow release; 3) water quality studies; 4) sediment yield studies; and 5) comparing yield potential of basins. It must be remembered that the chronology of the flows is lost in the assembly of data for duration curves. For some studies, the low-flow sequence, or persistence, may be more important (see Chapter 4).

- c. Monthly Curves. Occasionally the distribution of the flows during particular seasons of the year is of interest. Figure 2-3 illustrates a way of presenting daily-flow-duration curves that were computed from the daily flows during each month.
- d. <u>Stage-Duration</u>. Stage-duration curves are often used to establish vertical navigation clearances for bridges. If there have been no changes in the discharge versus stage relationship (rating curve), then the stages may be used instead of flows to compute a stage-duration curve. But, if there have been significant changes to the rating curve (because of major levee construction, for instance) then the stage-duration curve should be derived from the flow-duration curve and the latest rating curve. The log transformation is <u>not</u> recommended for stages.




Figure 2-3. Daily Flow-Duration Curves for Each Month.

e. <u>Future Probabilities</u>. A duration curve is usually based on a fairly large sample size. For instance, Figure 2-2 is based on 8766 daily values (Table 2-1). Even though the observed data can be used to make inferences about future probabilities, conclusions drawn from information at the extremities can be misleading. The data indicate there is a zero percent chance of exceeding 6970 cfs, however, it is known that there is a finite probability of experiencing a larger flow. And similarly, there is some chance of experiencing a lower flow than the recorded 1.1 cfs. Therefore, some other means is needed for computing the probabilities of infrequent future events. Section 2-4 describes the procedure for assigning probabilities to independent events.

#### 2-3. Selection of Data for Frequency Analysis.

a. Selection Based on Application of Results. The primary question to be asked before selection of data for a frequency study is: how will the frequency estimates be used? If the frequency curve is to be used for estimating damage that is related to the peak flow in a stream, maximum peak flows should be selected from the record. If the damage is best related to a longer duration of flow, the mean flow for several days' duration may be appropriate. For example, a reservoir's behavior may be related to the 3-day or 10-day rain flood volume or to the seasonal snowmelt volume. Occasionally, it is necessary to select a related variable in lieu of the one desired. For example, where mean-daily flow records are more complete than the records of peak flows, it may be more desirable to derive a frequency curve of mean-daily flows and then, from the computed curve, derive a peak-flow curve by means of an empirical relation between mean daily flows and peak flows. All reasonably independent values should be selected, but only the annual maximum events should be selected when the application of analytical procedures discussed in Chapter 3 is contemplated.

# b. Uniformity of Data.

- (1) General Considerations. Data selected for a frequency study must measure the same aspect of each event (such as peak flow, mean-daily flow, or flood volume for a specified duration), and each event must result from a uniform set of hydrologic and operational factors. For example, it would be improper to combine items from old records that are reported as peak flows but are in fact only daily readings, with newer records where the instantaneous peak was actually measured. Similarly, care should be exercised when there has been significant change in upstream storage regulation during the period of record to avoid combining unlike events into a single series. In such a case, the entire record should be adjusted to a uniform condition (see Sections 2-3f and 3-9). Data should always be screened for errors. Errors have been noted in published reports of annual flood peaks. And, errors have been found in the computer files of annual flood peaks. The transfer of data to either paper or a computer file always increases the probability that errors have been accidentally introduced.
- (2) Mixed Populations. Hydrologic factors and relationships during a general winter rain flood are usually quite different from those during a spring snowmelt flood or during a local summer cloudburst flood. Where two or more types of floods are distinct and do not occur predominately in mutual combinations, they should not be combined into a single series for frequency analysis. It is usually more reliable in such cases to segregate the data in accordance with type and to combine only the final curves, if necessary. In the Sierra Nevada region of California and Nevada, frequency studies are made separately for rain floods which occur principally during the months of November through March,

and for snowmelt floods, which occur during the months of April through July. Flows for each of these two seasons are segregated strictly by cause - those predominantly caused by snowmelt and those predominantly caused by rain. In desert regions, summer thunderstorms should be excluded from frequency studies of winter rain flood or spring snowmelt floods and should be considered separately. Along the Atlantic and Gulf Coasts, it is often desirable to segregate hurricane floods from nonhurricane events. Chapter 10 describes how to combine the separate frequency curves into one relation.


- c. <u>Location Differences</u>. Where data recorded at two different locations are to be combined for construction of a single frequency curve, the data should be adjusted as necessary to a single location, usually the location of the longer record. The differences in drainage area, precipitation and, where appropriate, channel characteristics between the two locations must be taken into account. When the stream-gage location is different from the project location, the frequency curve can be constructed for the stream-gage location and subsequently adjusted to the project location.
- d. Estimating Missing Events. Occasionally a runoff record may be interrupted by a period of one or more years. If the interruption is caused by destruction of the gaging station by a large flood, failure to fill in the record for that flood would result in a biased data set and should be avoided. However, if the cause of the interruption is known to be independent of flow magnitude, the record should be treated as a broken record as discussed in Section 3-2b. In cases where no runoff records are available on the stream concerned, it is usually best to estimate the frequency curve as a whole using regional generalizations, discussed in Chapter 9, instead of attempting to estimate a complete series of individual events. Where a longer or more complete record at a nearby station exists, it can be used to extend the effective length of record at a location by adjusting frequency statistics (Section 3-7) or estimating missing events through correlation (Chapter 12).
- e. <u>Climatic Cycles</u>. Some hydrologic records suggest regular cyclic variations in precipitation and runoff potential, and many attempts have been made to demonstrate that precipitation or streamflows evidence variations that are in phase with various cycles, particularly the well established 11-year sunspot cycle. There is no doubt that long-duration cycles or irregular climatic changes are associated with general changes of land masses and seas and with local changes in lakes and swamps. Also, large areas that have been known to be fertile in the past are now arid deserts, and large temperate regions have been covered with glaciers one or more times. Although the existence of climatic changes is not questioned, their effect is ordinarily neglected, because the long-term climatic changes have generally insignificant effect during the period concerned in water development projections, and short-term climatic changes tend to be self-compensating. For these reasons, and because of the difficulty in differentiating between stochastic (random) and systematic changes, the effect of natural cycles or trends during the analysis period is usually neglected in hydrologic frequency studies.


# f. Effect of Basin Development on Frequency Relations.

(1) Hydrologic frequency estimates are often used for some purpose relating to planning, design or operation of water resources control measures (structural and nonstructural). The anticipated effects of these measures in changing the rate and volume of flow is assessed by comparing the without project frequency curve with the corresponding with project frequency curve. Also, projects that have existed in the past have affected the rates and volumes of flows, and the recorded values must be adjusted to reflect uniform conditions in order that the frequency analysis will conform to the basic

assumption of homogeneity. In order to meet the assumptions associated with analytical frequency analysis techniques, the flows must be essentially unregulated by manmade storage or diversion structures. Consequently, wherever practicable, recorded runoff values should be adjusted to natural (unimpaired) conditions before an analytical frequency analysis is made. In cases where the impairment results from a multitude of relatively small improvements that have not changed appreciably during the period of record, it is possible that analytical frequency analysis techniques can be applied. The adjustment to natural conditions may be unnecessary and, because of the amount of work involved, not cost effective.

- (2) One approach to determining a frequency curve of regulated or modified runoff consists of routing all of the observed flood events under conditions of proposed or anticipated development. Then a relationship is developed between the modified and the natural flows, deriving an average or dependable relationship. A frequency curve of modified flows is derived from this relationship and the frequency curve of natural flows. In order to determine frequencies of runoff for extreme floods, routings of multiples of the largest floods of record or multiples of a large hypothetical flood can be used. Techniques of estimating project effects are outlined in Chapter 3-09d.
- g. Annual Series Versus Partial Duration Series. There are two basic types of frequency curves used to estimate flood damage. A curve of annual maximum events is ordinarily used when the primary interest lies in the larger events or when the second largest event in any year is of little concern in the analysis. The partial-duration curve represents the frequency of all independent events of interest, regardless of whether two or more occurred in the same year. This type of curve is sometimes used in economic analysis, where there is considerable damage associated with the second largest and third largest floods that occurred in some of the years. Caution must be exercised in selecting events because they must be both hydrologically and economically independent. The selected series type should be established early in the study in coordination with the planner and/or economist. The time interval between flood events must be sufficient for recovery from the earlier flood. Otherwise damage from the later flood would not be as large as computed. When both the frequency curve of annual floods and the partial-duration curve are used, care must be exercised to assure that the two are consistent. A graphic demonstration of the relation between a chronologic record, an annual-event curve and a partial-duration curve is shown on Figure 2-4.
- h. Presentation of Data and Results of Frequency Analysis. When frequency curves are presented for technical review, adequate information should be included to permit an independent review of the data, assumptions and analysis procedures. The text should indicate clearly the scope of the studies and include a brief description of the procedure used, including appropriate references. A summary of the basic data consisting of a chronological tabulation of values used and indicating sources of data and any adjustments should be included. The frequency data should also be presented in graphical form, ordinarily on probability paper, along with the adopted frequency curves. Confidence limit curves should also be included for analytically-derived frequency curves to illustrate the relative value of the frequency relationships. A map of the gage locations and tables of the adopted statistics should also be included.








Figure 2-4. Illustration of Chronologic Sequence and Arrayed Flood Peaks.

# 2-4. Graphical Frequency Analysis.

- a. Advantages and Limitations. Every set of frequency data should be plotted graphically, even though the frequency curves are obtained analytically. It is important to visually compare the observed data with the derived curve. The graphical method of frequency-curve determination can be used for any type of frequency study, but analytical methods have certain advantages when they are applicable. The principal advantages of graphical methods are that they are generally applicable, that the derived curve can be easily visualized, and that the observed data can be readily compared with the computed results. However, graphical methods of frequency analysis are generally less consistent than analytical methods as different individuals would draw different curves. Also, graphical procedures do not provide means for evaluating the reliability of the estimates. Comparison of the adopted curve with plotted points is not an index of reliability, but it is often erroneously assumed to be, thus implying a much greater reliability than is actually attained. For these reasons, graphical methods should be limited to those data types where analytical methods are known not to be generally applicable. That is, where frequency curves are too irregular to compute analytically, for example, stream or reservoir stages and regulated flows. Graphical procedures should always be to visually check the analytical computations.
- b. Selection and Arrangement of Peak Flow Data. General principles in the selection of frequency data are discussed in Section 2-3. Data used in the construction of frequency curves of peak flow consist of the maximum instantaneous flow for each year of record (for annual-event curve) or all of the independent events that exceed a selected base value (for partial-duration curve). This base value must be smaller than any flood flow that is of importance in the analysis, and should also be low enough so that the total number of floods in excess of the base equals or exceeds the number of years of record. Table 2-2 is a tabulation of the annual peak flow data with dates of occurrence, the data arrayed in the order of magnitude, and the corresponding plotting positions.
- c. <u>Plotting Formulas</u>. Median plotting positions are tabulated in Table F-1. In ordinary hydrologic frequency work, N is taken as the number of years of record rather than the number of events, so that percent chance exceedance can be thought of as the number of events per hundred years. For arrays larger than 100, the plotting position, P<sub>1</sub>, of the largest event is obtained by use of the following equation:

$$P_1 = 100 (1 - (.5)^{1/N})$$
 (2-2a)

The plotting position for the smallest event  $(P_y)$  is the complement  $(1-P_1)$  of this value, and all the other plotting positions are interpolated linearly between these two. The median plotting positions can be approximated by

$$P_m = 100(m - .3)/(N + .4)$$
 (2-2b)

where m is the order number of the event.

For partial-duration curves, particularly where there are more events than years (N), plotting positions that indicate more than one event per year can also be obtained using

Table 2-2. Annual Peaks, Sequential and Arrayed with Plotting Positions.

-:	-PLOTTING POSITIONS-FISHKILL CREEK AT BEACON, N.Y.										
*		EVEN	ITS ANA	LYZED			ORD	ERED EVENTS		*	
*					·*		WATER		MEDIAN		
*	MON	DAY	YEAR	FLOW, CFS		RANK	YEAR	FLOW, CFS	PLOT POS	*	
*					-*-					-*	
*	3	5	1945	2290.	*	1	1955	8800.	2.87	*	
*	12	27	1945	1470.	*	2	1956	8280.	6.97	*	
*	3	15	1947	2220.	*	3	1961	4340.	11.07	*	
*	3	18	1948	2970.	*	4	1968	3630.	15.16	*	
*	1	1	1949	3020.	*	5	1953	3220.	19.26	*	
*	3	9	1950	1210.	*	6	1952	3170.	23.36	*	
*	4	1	1951	2490.	*	7	1962	3060.	27.46	*	
*	3	12	1952	3170.	*	8	1949	3020.	31.56	*	
*	1	25	1953	3220.	*	9	1948	2970.	35.66	*	
*	9	13	1854	1760.	*	10	1958	2500.	39.75	*	
*	8	20	1955	8800.	*	11	1951	2490.	43.85	*	
*	10	16	1955	8280.	*	12	1945	2290.	47.95	*	
*	4	10	1957	1310.	*	13	1947	2220.	52.05	*	
*	12	21	1957	2500.	*	14	1960	2140.	56.15	*	
*	2	11	1959	1960.	*	15	1959	1960.	60.25	*	
*	4	6	1960	2140.	*	16	1963	1780.	64.34	*	
*	2	26	1961	4340.	*	17	1954	1760.	68.44	*	
*	3	13	1962	3060.	*	18	1967	1580.	72.54	*	
*	3	28	1963	1780.	*	19	1946	1470.	76.64	*	
*	1	26	1964	1380.	*	20	1964	1380.	80.74	*	
*	2	9	1965	980.	*	21	1957	1310.	84.84	*	
*	2	15	1966	1040.	*	22	1950	1210.	88.93	*	
*	3	30	1967	1580.	*	23	1966	1040.	93.03	*	
*	3	19	1968	3630.	*	24	1965	980.	97.13	*	
**	***	****	****	****	***	****	****	****	****	**	

Output from HEC computer program HECWRC.

Equation 2-2b. This is simply an approximate method used in the absence of knowledge of the total number of events in the complete set of which the partial-duration data constitute a subset.

- d. <u>Plotting Grids</u>. The plotting grid recommended for annual flood flow events is the logarithmic normal grid developed by Allen Hazen (ref 13) and designed such that a logarithmic normal frequency distribution will be represented by a straight line, Figure 2-5. The plotting grid used for stage frequencies is often the arithmetic normal grid. The plotting grids may contain a horizontal scale of exceedance probability, exceedance frequency, or percent chance exceedance. Percent chance exceedance (or nonexceedance) is the recommended terminology.
- e. Example Plotting of Annual-Event Frequency Curve. Figure 2-5 shows the plotting of a frequency curve of the annual peak flows tabulated in Table 2-2. A smooth curve should be drawn through the plotted points. Unless computed by analytical frequency procedures, the frequency curve should be drawn as close to a straight line as possible on the chosen probability graph paper. The data plotted on Figure 2-5 shows a tendency to curve upward, therefore, a slightly curved line was drawn as a best fit line.
- f. Example Plotting of Partial-Duration Curve. The partial-duration curve corresponding to the partial-duration data in Table 2-3 is shown of Figure 2-6a. This curve has been drawn through the plotted points, except that it was made to conform with the annual-event curve in the upper portion of the curve. The annual-event curve was

developed in accordance with the procedures described in Chapter 3. When partial-duration data must include more events than there are years of record (see Subparagraph b) it will be necessary to use logarithmic paper for plotting purposes, as on Figure 2-6a, in order to plot exceedance frequencies greater than 100 percent. Otherwise, the curve can be plotted on probability grid, as illustrated on Figure 2-6b.

## 2-5. Analytical Frequency Analysis.

a. General Procedures and Common Distributions. The fitting of data by an analytical procedure consists of selecting a theoretical frequency distribution, estimating the parameters of the distribution from the data by some fitting technique, and then evaluating the distribution function at various points of interest. Some theoretical distributions that have been used in hydrologic frequency analysis are the normal (Gaussian), log normal, exponential, two-parameter gamma, three-parameter gamma, Pearson type III, log-Pearson type III, extreme value (Gumbel) and log Gumbel. Chapter 3 describes the fitting of the log-Pearson type III to annual flood peaks and Appendix C describes fitting the extreme value (Gumbel) distribution.




Figure 2-5. Example of Graphical Frequency Analysis

Table 2-3. Partial Duration Peaks, Arrayed with Plotting Positions.

FISHKILL CREEK AT BEACON, NY PEAKS ABOVE 1500 CFS												
***	*****	*****	*****	*****	***							
*		ORDI	ERED EVENTS		. *		٠		ORD	ERED EVENTS		*
*		WATER		MEDIAN	*				WATER		MEDIAN	*
*	RANK	YEAR	FLOW, CFS	PLOT POS	*		*	RANK	YEAR	FLOW, CFS	PLOT POS	; *
*	1	1955	8800.	2.87	*		*	26	1952	1820.	105.33	*
*	2	1956	8280.	6.97	*		*	27	1945	1780.	109.43	*
*	3	1961	4340.	11.07	*		*	28	1963	1780.	113.52	*
*	4	1968	3630.	15.16	*		*	29	1956	1770.	117.62	*
*	5	1953	3220.	19.26	*		*	30	1954	1760.	121.72	*
*	6	1952	3170.	23.36	*		*	31	1952	1730.	125.82	*
*	7	1962	3060.	27.46	*		*	32	1968	1720.	129.92	*
*	8	1949	3020.	31.56	*		*	33	1955	1660.	134.02	*
*	9	1948	2970.	35.66	*		*	34	1958	1650,	138.11	*
*	10	1948	2750.	39.75	*		*	35	1958	1650.	142.21	*
*	11	1949	2700.	43.85	*		*	36	1953	1630.	146.31	*
*	12	1958	2500.	47.95	*		*	37	1960	1610.	150.41	*
*	13	1951	2490.	52.05	*		*	38	1956	1600.	154.51	*
*	14	1952	2460.	56.15	*		*	39	1958	1590.	158.61	*
*	15	1945	2290.	60.25	*		*	40	1958	1580.	162.70	*
*	16	1953	2290.	64.34	*		*	41	1967	1580.	166.80	*
*	17	1958	2290.	68.44	*		*	42	1951	1560.	170.90	*
*	18	1953	2280.	72.54	*		*	43	1959	1560.	175.00	*
*	19	1948	2220.	76.64	*		*	44	1955	1550.	179.10	*
*	20	1951	2210.	80.74	*		*	45	1951	1540.	183.20	*
*	21	1960	2140.	84.84	*		*	46	1968	1530.	187.30	*
*	22	1953	2080.	88.93	*		*	47	1960	1520.	191.39	*
*	23	1959	1950.	93.03	*		*	48	1958	1520.	195.49	*
*	24	1959	1920.	97.13	*		*	49	1952		199.59	*
*	25	1958	1900.	101.23	*		*	50	1948	1510.	203.69	*
*					*		*	51	1963	1510.	207.79	*
***	****	****	****	*****		***	****	****	****	*****	**	

- b. Advantages. Determining the frequency distribution of data by the use of analytical techniques has several advantages. The use of an established procedure for fitting a selected distribution would result in consistent frequency estimates from the same data set by different persons. Error distributions have been developed for some of the theoretical distributions that enable computing the degree of reliability of the frequency estimates (see Chapter 8). Another advantage is that it is possible to regionalize the parameter estimates which allows making frequency estimates at ungaged locations (see Chapter 9).
- c. <u>Disadvantages</u>. The theoretical fitting of some data can result in very poor frequency estimates. For example, stage-frequency curves of annual maximum stages are shaped by the channel and valley characteristics, backwater conditions, etc. Another example is the flow-frequency curve below a reservoir. The shape of this frequency curve would depend not only on the inflow but the capacities, operation criteria, etc. Therefore, graphical techniques must be used where analytical techniques provide poor frequency estimates.




Figure 2-6a. Partial Duration Frequency Curve, Log-Log Paper




Figure 2-6b. Partial Duration Frequency Curve, Probability Paper.

#### CHAPTER 3

#### FLOOD FREQUENCY ANALYSIS

#### 3-1. Introduction.

The procedures that federal agencies are to follow when computing a frequency curve of annual flood peaks have been published in Guidelines for Determining Flood Flow Frequency, Bulletin 17B (46). As stated in Bulletin 17B, "Flood events ... do not fit any one specific known statistical distribution." Therefore, it must be recognized that occasionally, the recommended techniques may not provide a reasonable fit to the data. When it is necessary to use a procedure that departs from Bulletin 17B, the procedure should be fundamentally sound and the steps of the procedure documented in the report along with the frequency curves.

This report contains most aspects of Bulletin 17B, but in an abbreviated form. Various aspects of the procedures are described in an attempt to clarify the computational steps. The intent herein is to provide guidance for use with Bulletin 17B. The step by step procedures to compute a flood peak frequency curve are contained in Appendix 12 of Bulletin 17B and are not repeated herein.

#### 3-2. Log-Pearson Type III Distribution.

a. General. The analytical frequency procedure recommended for annual maximum streamflows is the logarithmic Pearson type III distribution. This distribution requires three parameters for complete mathematical specification. The parameters are: the mean, or first moment, (estimated by the sample mean, X); the variance, or second moment, (estimated by the sample variance, S<sup>2</sup>); the skew, or third moment, (estimated by the sample skew, G). Since the distribution is a logarithmic distribution, all parameters are estimated from logarithms of the observations, rather than from the observations themselves. The Pearson type III distribution is particularly useful for hydrologic investigations because the third parameter, the skew, permits the fitting of non-normal samples to the distribution. When the skew is zero the log-Pearson type III distribution becomes a two-parameter distribution that is identical to the logarithmic normal (often called log-normal) distribution.

# b. Fitting the Distribution.

(1) The log-Pearson type III distribution is fitted to a data set by calculating the sample mean, variance, and skew from the following equations:

$$\overline{X} = \frac{\sum X}{N}$$
 (3-1)

$$S = \frac{\sum x^2}{N-1} = \frac{\sum (X-\overline{X})^2}{N-1}$$
 (3-2a)

$$= \frac{\sum X^2 - (\sum X)^2/N}{N-1}$$
 (3-2b)

$$G = \frac{N(\sum x^3)}{(N-1)(N-2)S^3} = \frac{N(\sum (X-\overline{X})^3)}{(N-1)(N-2)S^3}$$
(3-3a)

$$= \frac{N^2(\sum X^3) - 3N(\sum X)(\sum X^2) + 2(\sum X)^3}{N(N-1)(N-2)S^3}$$
(3-3b)

in which:

 $\overline{X}$  = mean logarithm

X = logarithm of the magnitude of the annual event

N = number of events in the data set

S<sup>2</sup> = unbiased estimate of the variance of logarithms

 $x = X - \overline{X}$ , the deviation of the logarithm of a single event from the mean logarithm

G = unbiased estimate of the skew coefficient of logarithms

The precision of the computed values is more sensitive to the number of significant digits when Equations 3-2b and 3-3b are used.

- (2) In terms of the frequency curve itself, the mean represents the general magnitude or average ordinate of the curve, the square root of the variance (the standard deviation, S) represents the slope of the curve, and the skew represents the degree of curvature. Computation of the unadjusted frequency curve is accomplished by computing values for the logarithms of the streamflow corresponding to selected values of percent chance exceedance. A reasonable set of values and the results are shown in Table 3-1. The number of values needed to define the curve depends on the degree of curvature (i.e., the skew). For a skew value of zero, only two points would be needed, while for larger skew values all of the values in the table would ordinarily be needed.
- (3) The logarithms of the event magnitudes corresponding to each of the selected percent chance exceedance values are computed by the following equation:

$$\log Q = \overline{X} + KS \tag{3-4}$$

where  $\overline{X}$  and S are defined as in Equations 3-1 and 3-2 and where

- log Q = logarithm of the flow (or other variable) corresponding to a specified value of percent chance exceedance
  - K = Pearson type III deviate that is a function of the percent chance exceedance and the skew coefficient.

# c. Example Computation.

(1) As shown in the following example, Equation 3-4 is solved by using the computed values of  $\overline{X}$  and S and obtaining from Appendix V-3 the value of K corresponding to the adopted skew, G, and the selected percent chance exceedance (P). An example computation for P=1.0, where  $\overline{X}$ , S and G are taken from Table 3-1, is:

$$\log Q = 3.3684 + 2.8236 (.2456)$$
  
= 4.0619  
Q = 11500 cfs

(2) It has been shown (36) that a frequency curve computed in this manner is biased in relation to average future expectation because of uncertainty as to the true mean and standard deviation. The effect of this bias for the normal distribution can be eliminated by an adjustment termed the expected probability adjustment that accounts for the actual sample size. This adjustment is discussed in more detail in Section 3-4. Table 3-1 and Figure 3-1 shows the derived frequency curve along with the expected probability adjusted curves and the 5 and 95 percent confidence limit curves.

Table 3-1. Computed Frequency Curve and Statistics.

**	FREQUENCY	CURVE- 01-37	35	FISHKILL	CRE	EK AT	BEACO	NEW Y	ORK	**
* *	COMPUTED	W,CFS EXPECTED PROBABILITY	*	CHANCE	*			LIMITS		*
*-		INCOMBILLI		EACEEDANC	#-		CIMI	0.93 61		-*
*	19200.	28300.	*	0.2	*	39	100.	1230	0.	*
*	14500.	19000.	*	0.5	*	26	900.	974	0.	*
*	11500.	14100.	*	1.0	*	20	100.	808	0.	*
*	9110.	10500.	*	2.0	*	14	800.	664	0.	*
*	7100.	7820.	*	4.0	*	10	800.	538	0.	*
*	4960.	5210.	*	10.0	*	6	850.	395	Ο.	*
*	3650.	3740.	*	20.0	*	4	710.	299	0.	*
*	2190.	2190.	*	50.0	*	2	650.	179	0.	*
*	1440.	1420.	*	80.0	*	1	760.	111	.0.	*
*	1200.	1170.	*	90.0	*	1	490.	88	4.	*
*	1040.	1010.	*	95.0	*	1	320.	74	6.	*
*	841.	791.	*	99.0	*	1	100.	56	8.	*
*+	<del>*********</del>	********		<del>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</del>	++++	+++++	++++	++++++	+++	+*
*	FREQUENC	Y CURVE STAT	IST	rics *	S	TATIST	ICS BA	ASED ON		*
*	MEAN LOGA	RITHM	3.	3684 *	HIST	ORIC E	VENTS		0	*
*	STANDARD					OUTLI		0	•	*
*	COMPUTED					OUTLIE		Õ		*
*	GENERALIZ					OR MI		Õ		*
*	ADOPTED S					EMATIC		rs °	24	*
**	*****	*****	***	*****	***	****	****	*****	***	**




Figure 3-1. Annual Frequency Curve.

- d. <u>Broken Record</u>. A broken record results when one or more years of annual peaks are missing for any reason not related to the flood magnitude. In other words, the missing events were caused by a random occurrence. The gage may have been temporarily discontinued for budgetary or other reasons. The different segments of the record are added together and analyzed as one record, unless the different parts of the record are considered non-homogeneous. If a portion of the record is missing because the gage was destroyed by a flood or the flood was too low to record, then the observed events should be analyzed as an incomplete record.
- e. <u>Incomplete Record</u>. An incomplete record can result when some of the peak flow events were either too high or too low. Different analysis procedures are recommended for missing high events and for missing low events. Missing high events may result from the gage being out of operation or the stage exceeding the rating table. In these cases, every effort should be made to obtain an estimate of the missing events. Missing low floods usually result when the flood height is below the minimum reporting level or the bottom of a crest stage gage. In these cases, the record should be analyzed using the conditional probability adjustment described in Appendix 5 of Bulletin 17B and Section 3-6 of this report.

f. Zero-flood years. Some of the gaging stations in arid regions record no flow for the entire year. A zero flood peak precludes the normal statistical analysis because the logarithm of zero is minus infinity. In this case the record should be analyzed using the conditional probability adjustment described in Appendix 5 of Bulletin 17B and Section 3-6 of this report.

#### g. Outliers.

- (1) Guidance. The Bulletin 17B (46) defines outliers as "data points which depart significantly from the trend of the remaining data." The sequence of steps for testing for high and low outliers is dependent upon the skew coefficient and the treatment of high outliers differs from that of low outliers. When the computed (station) skew coefficient is greater than +0.4, the high-outlier test is applied first and the adjustment for any high outliers and/or historic information is made before testing for low outliers. When the skew coefficient is less than -0.4, the low-outlier test is applied first and the adjustment for any low outlier(s) is made before testing for high outliers and adjusting for any historic information. When the skew coefficient is between -0.4 and +0.4, both the high-and low-outlier tests are made to the systematic record (minus any zero flood events) before any adjustments are made.
  - (2) Equation. The following equation is used to screen for outliers:

$$\overline{X}_{o} = X \pm K_{N}S \tag{3-5}$$

where:

- $X_0$  = outlier threshold in log units
- $\overline{X}$  = mean logarithm (may have been adjusted for high or low outliers, and/or historical information depending on skew coefficient)
- S = standard deviation (may be adjusted value)
- K<sub>N</sub> = K value from Appendix 4 of Bulletin 17B or Appendix F, Table 11 of this report. Use plus value for high-outlier threshold and minus value for low-outlier threshold
- N = Sample size (may be historic period (H) if historically adjusted statistics are used)
- (3) <u>High Outliers</u>. Flood peaks that are above the upper threshold are treated as high outliers. The one or more values that are determined to be high outliers are weighted by the historical adjustment equations. Therefore, for any flood peak(s) to be weighted as high outlier(s), either historical information must be available or the probable occurrence of the event(s) estimated based on flood information at nearby sites. If it is not possible to obtain any information that weights the high outlier(s) over a longer period than that of the systematic record, then the outlier(s) should be retained as part of the systematic record.

(4) <u>Low Outliers</u>. Flood peaks that are below the low threshold value are treated as low outliers. Low outliers are deleted from the record and the frequency curve computed by the conditional probability adjustment (Section 3-6). If there are one or more values very near, but above the threshold value, it may be desirable to test the sensitivity of the results by considering the value(s) as low outlier(s).

# h. Historic Events and Historical Information.

- (1) <u>Definitions</u>. Historic events are large flood peaks that occurred outside of the systematic record. Historical information is knowledge that some flood peak, either systematic or historic, was the largest event over a period longer than that of the systematic record. It is historical information that allows a high outlier to be weighted over a longer period than that of the systematic record.
- (2) Equations. The adjustment equations are applied to historic events and high outliers at the same time. It is important that the lowest historic peak be a fairly large peak, because every peak in the systematic record that is equal to or larger than the lowest historic peak must be treated as a high outlier. Also a basic assumption in the adjusting equations is that no peaks higher than the lowest historic event or high outlier occurred during the unobserved part of the historical period. Appendix D in this manual is a reprint of Appendix 6 from Bulletin 17B and contains the equations for adjusting for historic events and/or historical information.

#### 3-3. Weighted Skew Coefficient.

- a. General. It can be demonstrated, either through the theory of sampling distributions or by sampling experiments, that the skew coefficient computed from a small sample is highly unreliable. That is, the skew coefficient computed from a small sample may depart significantly from the true skew coefficient of the population from which the sample was drawn. Consequently, the skew coefficient must be compared with other representative data. A more reliable estimate of the skew coefficient of annual flood peaks can be obtained by studying the skew characteristics of all available streamflow records in a fairly large region and weighting the computed skew coefficient with a generalized skew coefficient. (Chapter 9 provides guidelines for determining generalized skew coefficients.)
  - b. Weighting Equation. Bulletin 17B recommends the following weighting equation:

$$G_{W} = \frac{MSE_{\overline{G}}(G) + MSE_{G}(\overline{G})}{MSE_{\overline{G}} + MSE_{G}}$$
(3-6)

where:

G<sub>u</sub> = weighted skew coefficient

G = computed (station) skew

 $\overline{G}$  = generalized skew

MSE<sub>c</sub> = mean-square error of generalized skew

MSE<sub>c</sub> = mean-square error of computed (station) skew

#### c. Mean Square Error.

(1) The mean-square error of the computed skew coefficient for log-Pearson type III random variables has been obtained by sampling experiments. Equation 6 in Bulletin 17B provides an approximate value for the mean-square error of the computed (station) skew coefficient:

$$MSE_{G} \simeq 10^{(A-B[log_{10}(N/10)])}$$
 (3-7a)  
  $\simeq 10^{A+B}/N^{B}$  (3-7b)

A = 
$$-0.33 + 0.08 |G| \text{ if } |G| \le 0.90$$
  
=  $-0.52 + 0.30 |G| \text{ if } |G| > 0.90$   
B =  $0.94 - 0.26 |G| \text{ if } |G| \le .50$   
=  $0.55$  if  $|G| > 1.50$ 

where:

|G| = absolute value of the computed skew

N = record length in years

Appendix F-10 provides a table of mean-square error for several record lengths and skew coefficients based on Equation 3-7a.

(2) The mean-square error (MSE) for the generalized skew will be dependent on the accuracy of the method used to develop generalized skew relations. For an isoline map, the MSE would be the average of the squared differences between the computed (station) skew coefficients and the isoline values. For a prediction equation, the square of the standard error of estimate would approximate the MSE. And, if an arithmetic mean of the stations in a region were adopted, the square of the standard deviation (variance) would approximate the MSE.

# 3-4. Expected Probability.

a. The computation of a frequency curve by the use of the sample statistics, as an estimate of the distribution parameters, provides an estimate of the true frequency curve. (Chapter 8 discusses the reliability and the distribution of the computed statistics.) The fact of not knowing the location of the true frequency curve is termed uncertainty. For the normal distribution, the sampling errors for the mean are defined by the t distribution and the sampling errors for the variance are defined by the chi-squared distribution. These two error distributions are combined in the formation of the non-central t distribution. The non-central t-distribution can be used to construct curves that, with a specified confidence (probability), encompass the true frequency curve. Figure 3-2 shows

the confidence limit curves around a frequency curve that has the following assumed statistics: N=10, X=0., S=1.0.

b. If one wished to design a flood protection work that would be exceeded, on the average, only one time every 100 years (one percent chance exceedance), the usual design would be based on the normal standard deviate of 2.326. Notice that there is a 0.5 percent chance that this design level may come from a "true" curve that would average 22 exceedances per 100 years. On the other side of the curve, instead of the expected one exceedance, there is a 99.5 percent chance that the "true" curve would indicate 0.004 exceedances. Note the large number of exceedances possible on the left side of the curve. This relationship is highly skewed towards the large exceedances because the bound on the right side is zero exceedance. A graph of the number of possible "true" exceedances versus the probability that the true curve exceeds this value, Figure 3-3, provides a curve with an area equal to the average (expected) number of exceedances.

c. The design of many projects with a target of 1 exceedance per 100 years at each project and assuming N=10 for each project, would actually result in an average of 2.69 exceedances (see Appen ix F-8).




Figure 3-2. Confidence Limit Curves based on the Non-central t Distribution.




Figure 3-3. Cumulative Probability Distribution of Exceedances per 100 Years.

- d. There are two methods that can be used to correct (expected probability adjustment) for this bias. The first method, as described above, entails plotting the curve at the "expected" number of exceedances rather that at the target value, drawing the new curve and then reading the adjusted design level. Appendix F-8 provides the percentages for the expected probability adjustment.
- e. The second method is more direct because an adjusted deviate (K value) is used in Equation 3-4 that makes the expected probability adjustment for a given percent chance exceedance. Appendix F-7 contains the deviates for the expected probability adjustment. These values may be derived from the t-distribution by the following equation:

$$K_{P,N} = t \sum_{P,N-1} [(N+1)/N]^{\frac{N}{2}}$$
 (3-8)

where:

P = exceedance probability (percent chance exceedance divided by 100)

N = sample size

K = expected probability adjusted deviate

t = Student's t-statistic from one-tailed distribution

- f. For a sample size of 10 and a 1% percent chance exceedance, the expected probability adjusted deviate is 2.959 as compared to the value of 2.326 used to derive the computed frequency curve.
- g. As mentioned in the first paragraph, the non-central t distribution, and consequently the expected probability adjustment, is based on the normal distribution. The expected probability adjustment values in Appendices F-7 and F-8 are considered applicable to Pearson type III distributions with small skew coefficients. The phrase "small skew coefficients" is usually interpreted as being between -0.5 to +0.5. Note also that the uncertainty in the skew coefficient is not considered. In other words, the skew coefficient is treated as if it were the population skew coefficient.
- h. The expected probability adjustment can be applied to frequency curves derived by other than analytical procedures if the equivalent worth (in years) of the procedure can be computed or estimated.

#### 3-5. Risk.

- a. <u>Definition</u>. The term risk is usually defined as the possibility of suffering loss or injury. In a hydrologic context, risk is defined as "the probability that one or more events will exceed a given flood magnitude within a specified period of years" (46). Note that this narrower definition includes a time specification and assumes that the annual exceedance frequency is exactly known. Uncertainty is <u>not</u> taken into account in this definition of risk. Risk then enables a probabilistic statement to be made about the chances of a particular location being flooded when it is occupied for a specified number of consecutive years. The percent chance of the location being flooded in any given year is assumed to be known.
- b. <u>Binomial Distribution</u>. The computation of risk is accomplished by the equation for the binomial distribution:

$$R_{I} = \frac{N!}{I!(N-I)!} P^{I}(1-P)^{N-I}$$
 (3-9)

where:

R, = risk (probability) of experiencing exactly I flood events

N = number of years (trials)

I = number of flood events (successes)

P = exceedance probability, percent chance exceedance divided by 100, of the annual event (probability of success)

(The terms in parentheses are those usually used in statistical texts)

When I equals zero (no floods), Equation 3-9 reduces to:

$$R_0 = (1-P)^N \tag{3-10a}$$

and the probability of experiencing one or more floods is easily computed by taking the complement of the probability of no floods:

$$R_{(1 \text{ or more})} = 1 - (1 - P)^{N}$$
 (3-10b)

#### c. Application.

(1) Risk is an important concept to convey to those who are or will be protected by flood control works. The knowledge of risk alerts those occupying the flood plain to the fact that even with the protection works, there could be a significant probability of being flooded during their lifetime. As an example, if one were to build a new house with the ground floor at the 1% chance flood level, there is a fair (about one in four) chance that the house will be flooded before the payments are completed, over the 30-year mortgage life. Using Equation 3-10b:

$$R_{(1 \text{ or more})} = 1 - (1 - .01)^{30}$$

$$= 1 - .99^{30}$$

$$= 1 - .74$$

$$= .26 \text{ or } 26\% \text{ chance}$$

- (2) Appendix F-12 provides a table for risk as a function of percent chance exceedance, period length and number of exceedances. This table could also be used to check the validity of a derived frequency curve. As an example, if a frequency curve is determined such that 3 observed events have exceeded the derived 1% chance exceedance level during the 50 years of record, then there would be reason to question the derived frequency curve. From Appendix F-12, the probability of this occurring is 0.0122 or about 1%. It is possible for the situation to occur, but the probability of occurring is very low. This computation just raises questions about the validity of the derived curve and indicates that other validation checks may be warranted before adopting the derived curve.
- 3-6. <u>Conditional Probability Adjustment</u>. The conditional probability adjustment is made when flood peaks have either been deleted or are not available below a specified truncation level. This adjustment will be applied when there are zero flood years, an incomplete record or low outliers. As stated in Appendix 5 of Bulletin 17B, this procedure is not appropriate when 25 percent or more of the events are truncated. The computation steps in the conditional probability adjustment are as follows:
  - 1. Compute the estimated probability  $(\tilde{P})$  that an annual peak will exceed the truncation level:

$$\tilde{P} = N/n \tag{3-11a}$$

where N is the number of peaks above the truncation level and n is the total number of years of record. If the statistics reflect the adjustments for historic information, then the appropriate equation is

$$\tilde{P} = \frac{H - WL}{H}$$
 (3-11b)

where H is the length of historic period, W is the systematic record weight and L is the number of peaks truncated.

2. The computed frequency curve is actually a conditional frequency curve. Given that the flow exceeds the truncation level, the exceedance frequency for that flow can be estimated. The conditional exceedance frequencies are converted to annual frequencies by the probability computed in Step 1:.

$$P = \tilde{P} P_{d}$$
 (3-12)

where P is the annual percent chance exceedance and P<sub>d</sub> is the conditional percent chance exceedance.

- 3. Interpolate either graphically or mathematically to obtain the discharge values  $(Q_p)$  for 1, 10 and 50 percent chance exceedances.
- 4. Estimate log-Pearson type III statistics that will fit the upper portion of the adjusted curve with the following equations:

$$G_s = -2.50 + 3.12 \frac{\log (Q_1/Q_{10})}{\log (Q_{10}/Q_{50})}$$
 (3-13)

$$S_s = \frac{\log (Q_1/Q_{50})}{K_1 - K_{50}}$$
 (3-14)

$$X_{s} = \log (Q_{50}) - K_{50} S_{s}$$
 (3-15)

where  $G_s$ ,  $S_s$  and  $\overline{X}_s$  are the synthetic skew coefficient, standard deviation and mean, respectively;  $Q_1$ ,  $Q_{10}$  and  $Q_{50}$  the discharges determined in Step 3; and  $K_1$  and  $K_{50}$  are the Pearson Type III deviates for percent change exceedances of 1 and 50 and skew coefficient  $G_s$ .

- 5. Combine the synthetic skew coefficient with the generalized skew by use of Equation 3-6 to obtain the weighted skew.
- 6. Develop the computed frequency curve with the synthetic statistics and compare it with the plotted observed flood peaks.

#### 3-7. Two-Station Comparison.

#### a. Purpose.

- (1) In most cases of frequency studies of runoff or precipitation there are locations in the region where records have been obtained over a long period. The additional period of record at such a nearby station is useful for extending the record at a short record station provided there is reasonable correlation between recorded values at the two locations.
- (2) It is possible, by regression or other techniques, to estimate from concurrent records at nearby locations the magnitude of individual missing events at a station. However, the use of regression analysis produces estimates with a smaller variance than that exhibited by recorded data. While this may not be a serious problem if only one or two events must be estimated to "fill in" or complete an otherwise unbroken record of several years, it can be a significant problem if it becomes necessary to estimate more than a few events. Consequently, in frequency studies, missing events should not be freely estimated by regression analysis.
- (3) The procedure for adjusting the statistics at a <u>short-record station</u> involves three steps: (1) computing the degree of correlation between the two stations, (2) using the computed degree of correlation and the statistics of the longer record station to compute an adjusted set of statistics for the shorter-record station, and (3) computing an equivalent "length of record" that approximately reflects the "worth" of the adjusted statistics of the short-record station. The longer record station selected for the adjustment procedure should be in a hydrologically similar area and, if possible, have a drainage area size similar to that of the short-record station.
- b. Computation of Correlation. The degree of correlation is reflected in the correlation coefficient  $R^2$  as computed through use of the following equation:

$$R^{2} = \frac{\left[\sum XY - (\sum X\sum Y)/N\right]^{2}}{\left[\sum X^{2} - (\sum X)^{2}/N\right]\left[\sum Y^{2} - (\sum Y)^{2}/N\right]}$$
(3-16)

where:

R<sup>2</sup> = the determination coefficient

Y = the value at the short-record station

X = the concurrent value at the long-record station

N = the number of years of concurrent record

For most studies involving streamflow values, it is appropriate to use the logarithms of the values in the equations in this section.

c. Adjustment of Mean. The following equation is used to adjust the mean of a short-record station on the basis of a nearby longer-record station:

$$\overline{Y} = \overline{Y}_1 + (\overline{X}_3 - \overline{X}_1) R (S_{Y_1}/S_{X_1})$$
(3-17)

where:

 $\overline{Y}$  = the adjusted mean at the short-record station

 $\overline{Y}_1$  = the mean for the concurrent record at the short-record station

 $\overline{X}_{\tau}$  = the mean for the complete record at the longer-record station

 $\overline{X}_1$  = the mean for the concurrent record at the longer-record station

R = the correlation coefficient

 $S_{y}$  = the standard deviation for the concurrent record at the short-record station

S<sub>x1</sub> = the standard deviation for the concurrent record at the longer-record

All of the above parameters may be derived from the logarithms of the data where appropriate, e.g., for annual flood peaks. The criterion for determining if the variance of the adjusted mean will likely be less than the variance of the concurrent record is:

$$R^2 > 1/(N_1 - 2)$$
 (3-18)

where  $N_1$  equals the number of years of concurrent record. If  $R^2$  is less than the criterion, Equation 3-17 should not be applied. In this case just use the computed mean at the short-record station or check another nearby long-record station. See Appendix 7 of Bulletin 17B for procedures to compare the variance of the adjusted mean against the variance of the entire short-record period.

d. Adjustment of Standard Deviation. The following equation can be used to adjust the standard deviation:

$$S_{\gamma}^2 = S_{\gamma_1}^2 + (S_{\chi}^2 - S_{\chi_1}^2) R^2 (S_{\gamma_1}^2 / S_{\chi_1}^2)$$
 (3-19)  
(approximate)

where:

 $S_v$  = the adjusted standard deviation at the short-record station

 $S_{\gamma_1}$  = the standard deviation for the period of concurrent record at the short-record station

 $S_y$  = the standard deviation for the complete record at the base station

 $S_{Y_{\bullet}}$  = the standard deviation for the period of concurrent record at the base station

R<sup>2</sup> = the determination coefficient

All of the above parameters may be derived from the logarithms of the data where appropriate, e.g., for annual flood peaks. This equation provides approximate results compared to Equation 3-19 in Appendix 7 of Bulletin 17B, but in most cases the difference in the results does not justify the additional computations.

e. Adjustment of Skew coefficient. There is no equation to adjust the skew coefficient that is comparable to the above equations. When adjusting the statistics of annual flood peaks either a weighted or a generalized skew coefficient may be used depending on the record length.

f. Equivalent Record Length. The final step in adjusting the statistics is the computation of the "equivalent record length" which is defined as the period of time which would be required to establish unadjusted statistics that are as reliable (in a statistical sense) as the adjusted values. Thus, the equivalent length of record is an indirect indication of the reliability of the adjusted values of Y and S<sub>Y</sub>. The equivalent record length for the adjusted mean is computed from the following equation:

$$N_{Y} = \frac{N_{Y_{1}}}{1 - [(N_{X} - N_{Y_{1}})/N_{X}][R^{2} - (1 - R^{2})/(N_{Y_{1}} - 3)]}$$
(3-20)

where:

 $N_{y}$  = the equivalent length of record of the mean at the short-record station

 $N_{\gamma_4}$  = the number of years of concurrent record at the two stations

 $N_y$  = the number of years of record at the longer-record station

R = the adjusted correlation coefficient

Figure 3-4 shows the data and computations for a two-station comparison for a short record station with 21 events and a long record station with 60 systematic events. It can be seen that the adjustment of the frequency statistics provides an increased reliability in the mean equivalent to having an additional 17 years of record at the short-record station.

			STATISTICS OF DATA								
Year	Flo	)w				Long Record					
	Chattooga River	Tallulah River			Total	Concurre	Not ent Concurr	ent			
1915 1917	12600 14000		Systemet	ic Events	60	21	39	2			
1918	5900		Historic	Period	71	C	0				
1919	16000	1	<del></del>			7 0740					
1920 1921	8200 4100		Log Mear	\ 	3.8866	3.9310	3.8650	3.479			
1922	6200	1	Standard	Deviation	0.2322	0.2678	0.2140	0.2609			
1923	5300		<u> </u>		0.5075	A 4588					
1924 1925	9200 3900	1		computed ieneralized	0.5075	0.1588	0.7340	-0.081			
1926	6200			dopted	-	•	-	-0.100			
1927	3600	- 1	L								
1928	20100		COMPUTA		O- 67471		cou.				
1929 1940	11400 29000*	- 1	COMPUTA	TIONS FOR TH	U-SIALIC	M COMPARI	<u>50N</u> :				
1941	7530	į		pe: b = 0.7							
1942	6870	ļ	Cor	relation Coe	fficient	:: R =0.81	1351 (See F	igure 9-0			
1943 1944	6870 3840	1	From	equations 19	). 21. ar	nd 22:					
1945	2930	ļ		,	•						
1946	6650		٧,	= 3.4796 + 0	.790495	(3.8866 +	3.9310)				
1947 1948	6440 12400		٧,	= 3.4445							
949	13900				_	_	_	_			
1950	4740	}	s,²	= [(0.2322)	<sup>2</sup> - (0.2	(678) <sup>2</sup> ] (0.	8114) <sup>2</sup> (0.260	9/0.2678)			
951	5220		•	÷ (0.260	9)2						
952 953	13400 6020	1	•	= 0.2386	-						
954	6230	1	1								
955	5820	1	N.,	=	2	1	0.6583	8			
1956 1957	5820 5820		<sup></sup> *1	1 - 71 -	0.6) کے	583 - <del>1 -</del>	0.6585)				
958	5620			• • • • • • • • • • • • • • • • • • • •		•	' -				
959	5620		Ġ=	0.0 MSE:	= 0.302	G = -	0.0811 MS	E. = 0.142			
1960 1961	6440 7310	1		•				-6			
962	9660		G.,	_( <u>0.302)(-0.</u>	0811) +	(0.0142)(	0.0)				
963	5420	1	•	U	.302 + 0	1.142					
964 965	9880 27200	7440	Gu	<b>*</b> -0.055 <b>*</b>	> -0.1						
966	13400	5140	•								
967	15400	2800									
968	5620	3100	FRE	QUENCY CURVE	, TALLUL	AN RIVER	NEAR CLAYTON	, GA			
969 970	14700 3480	2470 2010	Ft	OW, CFS	DE	RCENT	CONFIDENCE	IMITS			
971		976		EXPECTED		HANCE		C161.13			
711	3290				1 -		.05 LIMIT	OF			
972	7440	2160	COMPUTED	PROBABILIT	Y EXC	EEDANCE	.UJ CINII	AD FIBLE			
972 973	7440 19600	2160 8500			YEXC						
972 973 974	7440 19600 6400	2160 8500 4660	12700	14200	Y EXC	.2	18800	9580			
972 973 974 975 976	7440 19600 6400 6340 18500	2160 8500	12700 10900 9590		Y EXC						
972 973 974 975 976 977	7440 19600 6400 6340 18500 13000	2160 8500 4660 2410 6530 3580	12700 10900 9590 8350	14200 11900 10300 8800	Y EXC	.2 .5 1.0 2.0	18800 15600 13400 11300	9580 8410 7540 6680			
972 973 974 975 976 977 978	7440 19600 6400 6340 18500 13000 7850	2160 8500 4660 2410 6530 3580 4090	12700 10900 9590 8350 6760	14200 11900 10300 8800 6990		.2 .5 1.0 2.0 5.0	18800 15600 13400 11300 8810	9580 8410 7540 6680 5550			
972 973 974 975 976 977 978 979	7440 19600 6400 6340 18500 13000	2160 8500 4660 2410 6530 3580	12700 10900 9590 8350	14200 11900 10300 8800		.2 .5 1.0 2.0 5.0	18800 15600 13400 11300 8810 7040	9580 8410 7540 6680 5550 4680			
972 973 974 975 976 977 978 979 980 981	7440 19600 6400 6340 18500 13000 7850 14800 10900 4120	2160 8500 4660 2410 6530 3580 4090 6240 2880 1600	12700 10900 9590 8350 6760 5590 4430 2810	14200 11900 10300 8800 6990 5710 4480 2810		.2 .5 1.0 2.0 5.0 10.0 20.0 50.0	18800 15600 13400 11300 8810 7040 5370 3260	9580 8410 7540 6680 5550 4680 3780 2420			
972 973 974 975 976 977 978 979 980 981 982	7440 19600 6400 6340 18500 13000 7850 14800 10900 4120 5000	2160 8500 4660 2410 6530 3580 4090 6240 2880 1600 1960	12700 10900 9590 8350 6760 5590 4430 2810 1760	14200 11900 10300 8800 6990 5710 4480 2810 1740		.2 .5 1.0 2.0 5.0 10.0 20.0 50.0	18800 15600 13400 11300 8810 7040 5370 3260 2060	9580 8410 7540 6680 5550 4680 3780 2420 1450			
972 973 974 975 976 977 978 979 980 981 982 983	7440 19600 6400 6340 18500 13000 7850 14800 10900 4120	2160 8500 4660 2410 6530 3580 4090 6240 2880 1600	12700 10900 9590 8350 6760 5590 4430 2810	14200 11900 10300 8800 6990 5710 4480 2810		.2 .5 1.0 2.0 5.0 10.0 20.0 50.0	18800 15600 13400 11300 8810 7040 5370 3260	9580 8410 7540 6680 5550 4680 3780 2420			

<sup>\*</sup> Historic information, peak largest since 1915.

Figure 3-4. Two-Station Comparison Computations.

(Figure 9-1 shows the computations for b and R and Figure 9-2 shows the Tallulah River annual peaks plotted against the Chattooga River peaks.) Figure 3-5 shows the resulting unadjusted and adjusted frequency curves based on the computed and adjusted statistics in Figure 3-4. Although N<sub>y</sub> is actually the equivalent years of record for the mean, the value is used as an estimate equivalent record length in the computation of confidence limits and the expected probability adjustment.

- g. <u>Summary of Steps</u>. The procedure for computing and adjusting frequency statistics using a longer-record station can be summarized as follows:
  - (1) Arrange the streamflow data by pairs in order of chronological sequence.
  - (2) Compute  $\overline{Y}_1$  and  $S_{Y_1}$  for the entire record at the short-record station.
  - (3) Compute  $\overline{X}$  and  $S_{\chi}$  for the entire record at the longer-record station.
  - (4) Compute  $\overline{X}_1$  and  $S_{\chi_1}$  for the portion of the longer-record station which is concurrent with the short-record station.
  - (5) Compute the correlation coefficient using Equation 3-16.
  - (6) Compute  $\overline{Y}$  and  $S_{\gamma}$  for the short-record station using Equations 3-17 and 3-18.




Figure 3-5. Observed and Two-Station Comparison Frequency Curves.

- (7) Calculate the equivalent length of record of the mean for the short-record station using Equation 3-20.
- (8) Compute the frequency curve using adjusted values of  $\overline{Y}$  and S in Equation 3-4 and K values from Appendix F-2 corresponding to the adopted skew coefficient.
- (9) Compute the expected probability adjustment and the confidence limits.

## 3-8. Flood Volumes.

a. Nature and Purpose. Flood volume frequency studies involve frequency analysis of maximum runoff within each of a set of specified durations. Flood volume-duration data normally obtained from the USGS WATSTORE files consists of data for 1, 3, 7, 15, 30, 60, 90, 120, and 183 days. These same values are the default values in the HEC computer program STATS (Table 3-2). Runoff volumes are expressed as average flows in order that peak flows and volumes can be readily compared and coordinated. Whenever it is necessary to consider flows separately for a portion of the water year such as the rain season or snowmelt season, the same durations (up to the 30-day or 90-day values) are selected from flows during that season only. Flood volume-duration curves are used primarily for reservoir design and operation studies, and should generally be developed in the design of reservoirs having flood control as a major function.

Table 3-2. High Flow Volume-Duration Data

-	VOLUME-DURATION	DATA	-	FISHKILL	CR	AT	BEACON	NY	-	DAILY !	FLOWS	
---	-----------------	------	---	----------	----	----	--------	----	---	---------	-------	--

YEAR	1	3	7	15	30	60	90	120	183
1945	2080.0	1936.7	1714.3	1398.7	1106.8	752.3	742.2	649.4	559.2
1946	1360.0	1180.3	923.0		657.8	605.3	476.2	451.5	379.9
1947	1800.0	1616.7	1159.1	820.5	687.1	611.9	558.5	485.8	396.4
1948	2660.0	2430.0	2322.9	1641.7	1145.1	862.0	706.2	638.1	512.7
1949	2900.0	2346.7	1715.7	1358.9	888.9	680.7	586.8	522.4	422.4
1950	1050.0	909.7	746.9	639.7	588.1	455.9	423.0	387.2	335.1
1951	2160.0	1886.7	1744.3		872.9	832.1	781.2	689.8	568.9
1952	2870.0	2266.7	1557.6	1186.5	1032.8	925.1	854.1	732.6	692.9
1953	2850.0	2233.3	1644.3	1317.2	1145.5	994.6	831.1	794.4	654.5
1954	1520.0	1096.7	811.7	620.4	482.9	397.0	405.7	372.7	348.1
1955	6970.0	4536.7	2546.1	1360.0	758.2	606.0	494.0	463.1	478.7
1956	6760.0	5456.7	3354.3	1959.7	1572.8	1080.9	767.7	_	641.7
1957	1230.0	1117.3	1037.7	758.9	524.2	408.8	363.3	373.4	324.4
1958	2130.0	1916.7	1587.1	1354.5	1128.1	972.0	848.2	777.8	654.1
1959	1670.0	986.7	782.1		517.6	466.7	437.5		346.2
1960	2080.0	1770.0	1374.3	1046.9	712.3	605.5	530.5	515.1	468.4
1961	3440.0	2966.7	2155.7	1590.2	1152.3	845.2	759.5	656.2	491.4
1952	2570.0	2070.0	1547.7	1105.0	857.7	600.9	461.3	429.4	325.0
1963	1730.0	1616.7	1309.0	1216.0	900.8	569.1	438.0	370.8	305.9
1964	1300.0	1106.7	945.3	737.8	541.2	514.8	486.6	450.1	368.3
1965	900.0	826.3		455.7	375.8	303.3	275.7	235.0	175.0
1966	930.0	774.7	693.3	546.5	445.7	352.5	296.2	272.5	209.0
1967	1520.0	1416.7	1247.1	1023.5	906.8	701.3	581.4	521.1	436.8
1968	3500.0	2810.0	1934.3	1328.5	878.7	611.7		567.3	460.3

Note - Data based on water year of October 1 of preceeding year through September 30 of given year.

b. <u>Data for Comprehensive Series</u>. Data to be used for a comprehensive flood volume-duration frequency study should be selected from nearly complete water year records. Unless overriding reasons exist, the durations in Table 3-2 should be used in order to assure consistency among various studies for comparison purposes. Maximum flood events should be selected only for those years when recorder gages existed or when the maximum events can be estimated by other means. Where a minor portion of a water year's record is missing, the longer-duration flood volumes for that year can often be estimated adequately. If upstream regulation or diversion is known to have an effect, care should be exercised to assure that the period selected is the one when flows would have been maximum under the specified (usually natural) conditions.

#### c. Statistics for Comprehensive Series.

(1) The probability distribution recommended for flood volume-duration frequency computations is the log-Pearson type III distribution; the same as that used for annual flood peaks. In practice, only the first two moments, mean and standard deviations are based on station data. As discussed in Section 3-3, the skew coefficient should not be based solely on the station record, but should be weighted with information from regional studies. To insure that the frequency curves for each duration are consistent, and especially to prevent the curves from crossing, it is desirable to coordinate the variation in standard deviation and skew with that of the mean. This can be done graphically as shown in Figure 3-6. For a given skew coefficient, there is a maximum and minimum allowable slope for the standard deviation-versus-mean relation which prevents the curves from crossing within the established limits. For instance, to keep the curves from crossing within 99.99 and .01 percent chance exceedances with a skew of 0., the slope must not exceed .269, nor be less than -.269, respectively. The value of this slope constraint is found by stating that the value of one curve (X<sub>A</sub> for curve A) must equal or exceed the value for a second curve (X<sub>B</sub> for curve B) at the desired exceedance frequency. Each of these values can be found by substitution into Equation 3-4 (the K for zero skew and 99.99 percent chance exceedance is -3.719):

$$X_{A} \geq X_{B}$$

$$\overline{X}_{A} + (-3.719) S_{A} \geq \overline{X}_{B} + (-3.719) S_{B}$$

$$3.719 (S_{B} - S_{A}) \geq \overline{X}_{B} - \overline{X}_{A}$$

$$\frac{(S_{B} - S_{A})}{(\overline{X}_{B} - X_{A})} \geq 0.269$$

where:

 $X_A$  = Value of frequency curve A at 99.99 percent chance exceedance

 $X_B$  = Value of frequency curve B at 99.99 percent chance exceedance

 $\overline{X}_A$  = Mean of frequency curve A

 $\overline{X}_{B}$  = Mean of frequency curve B

S<sub>A</sub> = Standard deviation of frequency curve A

 $S_{R}$  = Standard deviation of frequency curve B




Figure 3-6. Coordination of Flood-Volume Statistics.

- (2) When the skew changes between durations, it is probably easiest to adopt smoothed relations for the standard deviation and skew and input the statistics into a computer program that computes the ordinates. The curves can then be inspected for consistency.
- (3) If the statistics for the peak flows have been computed according to the procedures in Bulletin 17B, the smoothing relations should be forced through those points. The procedure for computing a least-squares line through a given intersection can be found in texts describing regression analyses.

# d. Frequency Curves for Comprehensive Series.

(1) General Procedure. Frequency curves of flood volumes are computed analytically using general principles and methods of Chapters 2 and 3. They should also be shown graphically and compared with the data on which they are based. This is a general check on the analytic work and will ordinarily reveal any inconsistency in data and methodology. The computed frequency curves and the observed data should be plotted on a single sheet for comparison purposes, Figure 3-7.




Figure 3-7. Flood-Volume Frequency Curves.

(2) Interpolation Between Fixed Durations. The runoff volume for any specified frequency can be determined for any duration between 1-day and 365-days by drawing a curve on logarithmic paper relating mean discharge (or volume) to duration for that specified frequency (see Figure 3-8a). When runoff volumes for durations shorter than 24 hours are important, special frequency studies should be made. These could be done in the same manner as for the longer durations, using skew coefficients interpolated in some reasonable manner between those used for peak and 1-day flows.

#### e. Applications of Flood Volume-Duration Frequencies.

- (1) Volume-duration Curves. The use of flood volume-duration frequencies in solving reservoir planning, design, and operation problems usually involves the construction of volume-duration curves for specified frequencies. These are drawn first on logarithmic paper for interpolation purposes, as illustrated on Figure 3-8a. The mean discharge values are multiplied by appropriate durations to obtain volumes and are then replotted on an arithmetic grid as shown on the Figure 3-8b. A straight line on this grid represents a constant rate of flow. The straight line represents a uniform flow of 1,500 cfs, and the maximum departure from the 2% chance exceedance curve demonstrates that a reservoir capacity of 16,000 cfs-days (31,700 acre-feet) is required to control the indicated runoff volumes by a constant release of 1,500 cfs. The curve also indicates that a duration of about 8 days is critical for this project release rate and associated flood-control storage space.
- (2) Application to a Single Reservoir. In the case of a single flood-control reservoir located immediately upstream of a single damage center, the volume frequency problems are relatively simple. A series of volume-duration curves, similar to that shown on Figure 3-8, corresponding to selected exceedance frequencies should first be drawn. The project release rate should be determined, giving due consideration to possible channel deterioration, encroachment into the flood plain, and operational contingencies. This procedure can be used not only as an approximate aid in selecting a reservoir capacity, but also as an aid in drawing filling-frequency curves.
- (3) Application to a Reservoir System. In solving complex reservoir problems, representative hydrographs at all locations can be patterned after one or more past floods. The ordinates of these hydrographs can be adjusted so that their volumes for the critical durations will equal corresponding magnitudes at each location for the selected frequency. A design or operation scheme based on regulation of such a set of hydrographs would be reasonably well balanced. Some aspects of this problem are described in Section 3-9g.

## 3-9. Effects of Flood Control Works on Flood Frequencies.

a. Nature of the Problem. Flood control reservoirs are designed to substantially affect the frequency of flood flows (or flood stages) at various downstream locations. Many land use changes such as urbanization, forest clearing, etc. can also have significant effects on downstream flood flows (see Section 3-10). Channel improvements (intended to reduce stages) and levee improvements (intended to confine flows) at specified locations can substantially affect downstream flows by eliminating some of the natural storage effects. Levees can also create backwater conditions that affect river stages for a considerable distance upstream. The degree to which flows and stages are modified by various flood control works or land use changes can depend on the timing, areal distribution and magnitude of rainfall (and snowmelt, if pertinent) causing the flood. Accordingly, the studies should include evaluations of the effects on representative flood




Figure 3-8a. Flood-Volume Frequency Relations.




Figure 3-8b. Storage Requirement Determination.

events, with careful consideration given to the effects of different temporal and areal distributions.

#### b. Terminology.

- (1) Natural Conditions. Natural conditions in the drainage basin are defined as hydrologic conditions that would prevail if no regulatory works or other works of man were constructed. Natural conditions, however, include the effects of natural lakes, swamp areas, etc.
- (2) <u>Present Conditions</u>. Present or base conditions are defined as the conditions that exist as of the date of the study or some specified time.
- (3) <u>Without-Project Conditions</u>. Without-project conditions are defined as the conditions that would exist without the projects under consideration, but with all existing projects and may include future projects whose construction is imminent.
- (4) With-Project Conditions. With-project conditions are defined as the conditions that will exist after the projects under consideration are completed.

## c. Reservoir-Level Frequency Computation.

- (1) Factors to be Considered. Factors affecting the frequency of reservoir levels include historical inflow rates and anticipated future inflow rates estimated by volume-frequency studies, the storage-elevation curves, and the plan of reservoir regulation including location and size of reservoir outlets and spillway. A true frequency curve of annual maxima or minima can only be computed when the reservoir completely fills every year. Otherwise, the events would not be independent. If there is dependence between annual events, the ordinate should be labeled "percent of years exceeded" for maximum events and "percent of years not exceeded" for minimum events.
- (2) Computation and Presentation of Results. A frequency curve of annual maximum reservoir elevations (or stages) is ordinarily constructed graphically, using procedures outlined in Section 2-4. Observed elevations (or stages) are used to the extent that these are available, if the reservoir operation will remain the same in the future. Historical and/or large hypothetical floods may also be routed through the reservoir using future operating plans. A typical frequency curve is illustrated on Figure 6-4. Elevation-duration curves are constructed from historical operation data or from routings of historical runoff in accordance with procedures discussed in Section 2-2, Figure 3-9. Such curves may be constructed for the entire period of record or for a selected wet period or dry period. For many purposes, particularly recreation uses, the seasonal variation of reservoir elevation (stages) is important. In this case a set of frequency or duration curves for each month of the year may be valuable. One format for presenting this information is illustrated on Figure 3-10.




Figure 3-9. Daily Reservoir Elevation-Duration Curve.




Figure 3-10. Seasonal Variation of Elevation-Duration Relations.

## d. Effects of Reservoirs on Flows at Downstream Points.

- (1) Routing for Period of Record. The frequency of reservoir outflows or of flows at a downstream location can be obtained from routings of the period-of-record runoff by the following methods:
- (a) Determine the annual maximum flow at each location of interest and construct a frequency curve of the regulated flows by graphical techniques (Section 2-4).
- (b) Construct a graph of with-project versus without-project flows at the location of interest and draw a curve relating the two quantities as illustrated on Figure 3-11. The points should be balanced in the direction transverse to the curve, but factors such as flood volume of the events and reliability of regulation must be considered in drawing the curve. This curve can be used in conjunction with a frequency curve of without-project flows to construct a frequency curve of with-project flows as illustrated on Figure 3-12. This latter procedure assures consistency in the analysis and gives a graphical presentation of the variability of the regulated events for a given unregulated flow.
- (2) Use of Hypothetical-Flood Routings. Usually recorded values of flows are not large enough to define the upper end of the regulated frequency curve. In such cases, it is usually possible to use one or more large hypothetical floods (whose frequency can be estimated from the frequency curve of unregulated flows) to establish the corresponding magnitude of regulated flows. These floods can be multiples of the largest observed floods or of floods computed from rainfall; but it is best not to multiply any one flood by a factor greater than two or three. The floods are best selected or adjusted to represent about equal severity in terms of runoff frequency of peak and volumes for various durations. The routings should be made under reasonably conservative assumptions as to initial reservoir stages.
- (3) <u>Incidental Control by Water Supply Space</u>. In constructing frequency curves of regulated flows, it must be recognized that reservoir operation for purplies other than flood control will frequently provide incidental regulation of floods. However, the availability of such space cannot usually be depended upon, and its value is considerably diminished for this reason. Consequently, the effects of such space on the reduction of floods should be estimated very conservatively.
- (4) Allowance for Operational Contingencies. In constructing frequency curves of regulated flows, it should be recognized that actual operation is rarely perfect and that releases will frequently be curtailed or diminished because of unforeseen operation contingencies. Also, where flood forecasts are involved in the reservoir operation, it must be recognized that these are subject to considerable uncertainty and that some allowance for uncertainty will be made during operation. In accounting for these factors, it will be found that the actual control of floods is somewhat less than could be expected if full release capacities and downstream channel capacities were utilized efficiently and if all forecasts were exact.
- (5) Runoff from Unregulated Areas. In estimating the frequency of runoff at a location that is a considerable distance downstream from one or more reservoir projects, it must be recognized that none of the runoff from the intermediate areas between the reservoir(s) and the damage center will be regulated. This factor can be accounted for by constructing a frequency curve of the runoff from the intermediate area, and using this curve as an indicator of the lower limit for the curve of regulated flows. Streamflow




Figure 3-11. Example With-Project versus Without-Project Peak Flow Relations.




Figure 3-12. Example Without-Project and With-Project Frequency Curves.

routing and combining of both the flows from the unregulated area and those from the regulated area is the best procedure for deriving the regulated frequency curve.

- e. Effects of Channel, Levee and Floodway Improvements. The effect of channel, levee and floodway improvements on river stages at the project location and on river discharges downstream from the project location can generally be evaluated by routing several typical floods through the reaches of the improvement and the upstream reaches affected by backwater. The stages or discharges thus derived can be plotted against corresponding without-project values, and a smooth curve drawn. This curve could be used in conjunction with a frequency curve of without-project values to construct a frequency curve of with-project values as discussed in Paragraph 3-09d(1)b. Corresponding stages upstream from the selected control point can be estimated from water-surface profile computations.
- f. Changes in Stage-Discharge Relationships. Changes in stage-discharge relations due to channel improvements, levee construction or flow obstructions can best be evaluated by computing theoretical water surface profiles for each of a number of discharges. The resulting relationships for modified conditions can be used to modify routing criteria to enable evaluation of the downstream effects of these changes.

### g. Effects of Multiple Reservoir Systems.

- (1) Representative events. When more than one reservoir exists above a damage center, the problem of evaluating reservoir stages and downstream flows under project conditions becomes increasingly complex. Whenever practicable, it is best to make complete routings of five to ten historic flood events and a large event that has been developed from a hypothetical rainfall pattern. If necessary, it is possible to supplement these events by using multiples of the flow values. Care muse be exercised in selecting events that have representative flood volumes, timings, and areal distributions. Also, there should be a balance of events caused by particular climatic factors, i.e. snowmelt, tropical storm, thunderstorm, etc. Furthermore, the flood-volume-duration characteristics of the hypothetical events should be similar to the recorded events (see Section 3-8). Hypothetical events must be used with caution, however, because certain characteristics of atypical floods may be responsible for critical flooding conditions. Accordingly, such studies should be supplemented by a critical examination of the potential effects of atypical floods.
- (2) <u>Computer Program.</u> It is generally impossible to make all of the flood routings necessary to evaluate the effect of a reservoir system by hand computations. Computer programs have been developed to route floods through a reservoir system with complex operational criteria (55).

### 3-10. Effects of Urbanization.

a. General Effects. Urbanization has two major effects on the watershed which influence the runoff characteristics. First, there is a substantial increase in the impervious area, which results in more water entering the stream system as direct runoff. Second, the drainage system collecting the runoff is generally more efficient and tends to concentrate the water faster in the downstream portion of the channel system. It is important to keep these two effects in mind when considering the changes in the flood peak frequency curve caused by increasing urbanization.

- b. Effect on Frequency Relations. A general statement can be made about the effects of urbanization on flood-peak frequency relations. The usual effect on the frequency relation is to cause a significant increase in the magnitude of the more frequent events, but a lesser increase in the less frequent events. This results in an increase in the mean of the annual flood peaks, a decrease in the standard deviation and an unpredictable effect on the skew coefficient (see Figure 3-13). The resulting frequency relation may not fit any of the standard theoretical distributions. Graphical techniques should be applied if a good fit is not possible by an analytical distribution.
- c. Other Considerations. The actual effect of urbanization at a specific location is dependent on many factors. Some of the factors that must be considered are basin slope, basin shape, previous land use and ground cover, number of depressional areas drained, magnitude and nature of urban development and the typical flood source (snowmelt, thunderstorm, hurricane, or frontal storm). It is possible for urbanization to cause a decrease in the flood peaks at a particular site. For instance, consider an area downstream of two tributary areas of such size and shape that the large floods are caused by the addition of the nearly coincident peaks from the two tributaries. Urbanization in one of the tributary areas will likely cause the contribution from this area to arrive downstream earlier. This change in the timing of the peaks would result in lower downstream peaks. Of course, when both areas have become equally urbanized, the flood peaks may coincide again. The construction of bridges or other encroachments can reduce the flood peak downstream, but causes backwater flooding upstream.




Figure 3-13. Typical Effect of Urbanization on Flood Frequency Curves.

- d. Adjustment of a Series of Nonstationary Peak Discharges. When the annual peak discharges have been recorded at the outlet of a basin which has been undergoing progressive urbanization during the period of record, the peak discharges are nonstationary because of the varying basin condition. It is generally necessary to adjust the discharges to a stationary series representative of existing conditions. One approach to adjusting the peaks to a stationary series is as follows:
  - (1) Develop and calibrate a rainfall-runoff model for existing basin conditions and for conditions at several other points in time during the period of record.
  - (2) Develop a hypothetical storm for the basin using generalized rainfall criteria, such as that contained in Weather Bureau Technical Paper 40 (14). Select the magnitude of the storm, e.g., a 25-year recurrence interval, to be used. The recurrence interval is arbitrary as it is not assumed in this approach that runoff frequency is equal to rainfall frequency. The purpose of adopting a specific magnitude is to establish a base storm to which ratios can be applied for subsequent steps in the analysis.
  - (3) Apply several ratios (say 5 to 8) to the hypothetical storm developed in the previous step such that the resulting calculated peak discharges at the gage will cover the range desired for frequency analysis. Input the balanced storms to the rainfall-runoff model for each of the basin conditions selected in step (1), and determine peak discharges at the gaged location.
  - (4) From the results of step (3), plot curves representing peak discharge versus storm ratio for each basin condition (or point in time).
  - (5) Use the curves developed in step (4) to adjust the observed annual peak discharges. For example, an observed annual peak discharge that occurred in 1975 is adjusted by entering the "1975" curve (or interpolating) with that discharge, locating the frequency of that event, and reading the magnitude of the adjusted peak from the base-condition curve for the same frequency. The adjusted peak thus obtained is assumed to be the peak discharge that would have occurred for the catchment area and development at the base condition. It is not necessary to adjust to natural conditions. A stationary series could be developed for one or more points in time.
  - (6) A conventional frequency analysis can be performed on the adjusted peak discharges determined in the preceding step. If the data represent natural conditions, Bulletin 17B procedures would be applicable. If the basin conditions represent significant urbanization, graphical analysis may be appropriate.
- e. Development of Frequency Curves at Ungaged Sites. There are several approaches that can be taken to develop frequency curves at ungaged sites that have been subject to urbanization. In order of increasing difficulty, they are: 1) application of simple transfer procedures (e.g., Q = CIA); 2) application of available region-specific criteria, e.g., USGS regression equations; 3) application of rainfall-runoff models to hypothetical storm events; 4) application of simple and detailed rainfall-runoff models with observed storm events and 5) complete period-of-record simulation. As approaches (3) and (4) are often applied, the computational steps are presented in some detail.

## (1) Hypothetical Storm Approach

- (a) Develop peak-discharge frequency curve for specific land use conditions from available gaged data and/or regional relationships.
- (b) Develop balanced storms of various frequencies using data from generalized criteria, a nearby gage or the equivalent.
- (c) Develop rainfall-runoff model for the specific watershed with the adopted land-use conditions. Calibrate runoff and routing parameters by reproducing observed hydrographs occurring under natural conditions.
- (d) Input balanced storms (from b) to rainfall-runoff model (from c). Determine exceedance probabilities to associate with balanced storms from adopted specific land-use conditions peak discharge frequency curve (from a) with computed peak discharges.
- (e) Modify parameters of rainfall-runoff model to reflect future urban runoff characteristics. Input balanced storms to the urban- conditions model.
- (f) Plot results assuming frequency of each event is the same for both the adopted land use and the future urban conditions.
- (2) "Simple" and Detailed Simulation of Historic Events
  - (a) Simulate all major historic events with a relatively simple model to establish the ranking of events and an approximate peak discharge for each. The approximate peaks could be developed by using a multiple linear regression approach, by using a very simple rainfall-runoff model, or by any other approach that will capture the hydrologic response of the basin.
  - (b) Perform a conventional frequency analysis of the approximate peaks obtained in step a.
  - (c) Make detailed simulations of selected events and correlate the more precise peaks with the approximate peaks.
  - (d) Use the relationship developed in step c to determine the desired frequency curve. The same approach can be followed for both existing and future conditions.

### LOW-FLOW FREQUENCY ANALYSIS

4-1. <u>Uses</u>. Low-flow frequency analyses are used to evaluate the ability of a stream to meet specified flow requirements at a particular location. The analysis can provide an indication of the adequacy of the natural flow to meet a given demand with a stated probability of experiencing a shortage. Additional analyses can indicate the amount of storage that would be required to meet a given demand, again with a stated probability of being deficient. The design of hydroelectric power plants, determination of minimum flow requirements for water quality and/or fish and wildlife, and design of water storage projects can benefit from low-flow frequency analysis.

## 4-2. Interpretation.

- a. Analytical frequency techniques are usually not applicable to low-flow data because most theoretical frequency distributions cannot satisfactorily fit the recorded data. It is recommended that graphical techniques be used and that known geologic and hydrologic conditions be kept in mind when developing the relationships. As the low values are the major interest, the data are arranged with the smallest value first. The probability scale is usually labeled "percent chance nonexceedance."
- b. Annual low flows are usually computed for several durations (in days) with the flow rate expressed as the mean flow for the period. For example, the USGS WATSTORE output provides the mean flow values for daily durations of 1, 3, 7, 14, 30, 60, 90, 120 and 183 days. The default values for the HEC program STATS are the same with the exception of using a 15-day duration instead of 14 (Table 4-1). Often a climatic year from April 1 to March 31 is specified to provide a definite separation of the seasonal low-flow periods. Figure 4-1 is a plot of the data in Table 4-1.

### 4-3. Application Problems.

- a. <u>Basin Development</u>. The effects of any basin developments on low flows are usually quite significant. For example, a relatively moderate diversion can be neglected when evaluating flood flow relations, but it would reduce, or even eliminate, low flows. Accordingly, one of the most important aspects of low flows concerns the evaluation of past and future effects of basin developments.
- b. <u>Multi-Year Events</u>. In regions of water scarcity and where a high degree of development has been attained, projects that entail carryover of water for several years are often planned. In such projects it is desirable to analyze low-flow volume frequencies for periods ranging from 1-1/2 to 8-1/2 years or more. Because the number of independent low-flow periods of these lengths, in even the longest historical records, is very small and because the concept of multi- annual periods is somewhat inconsistent with the basic concept of an "annual event;" there is no truly satisfactory way for computing the percent chance nonexceedance for low-flow periods that are more than I year in length. One procedure described in reference (37) has been used with long sequences of synthetically generated streamflows to derive estimates of drought frequency. Although

Table 4-1. Low-Flow Volume-Duration Data.

	LOWEST MEAN VALUE FOR DURATION, FLOW, CFS											
YEAR	1	3	7	15	30	60	90	120	183			
1945	92.0	104.0	115.1	127.7	143.0	179.5		254.1	305.3			
946	9.4	12.8	17.6	21.3	28.5	49.8	62.1	58.7	75.4			
947	9.4	12.8	17.3	19.0	21.2	32.1	41.0	62.0	137.0			
948	8.3	10.2	15.7	15.7	18.9	21.6	27.4	33.5	78.			
949	7.1	8.2	9.0	9.1	10.0	11.3	12.3	14.3	21.2			
950	22.0	22.0	23.9	27.0	32.6	37.0	43.1	51.1	119.0			
951	20.0	33.3	40.9	45.5	58.4	73.2	84.0	88.7	116.4			
952	34.0	39.7	43.0	44.0	46.2	64.6	100.1	97.9	135.3			
953	4.4	4.8	4.9	7.3	10.4	11.0	15.2	25.3	49.9			
954	8.4	9.5	12.3	14.6	16.7	22.9	39.8	99.8	160.8			
955	6.1	6.3	7.0	11.2	14.7	37.2	67.6	148.4	247.9			
956	19.0	21.3	23.0	26.8	29.5	53.5	59.5	71.3	98.2			
957	3.7	5.1	5.8	6.4	8.9	9.8	12.5	15.5	25.6			
958	12.0	13.3	17.4	19.2	23.8	29.6	41.5	50.9	118.5			
959	17.0	17.3		25.1	39.0	49.8	53.2	60.4	111.0			
960	48.0	48.3			77.5	122.1	136.3	149.1	213.9			
961	17.0	17.0	19.7	22.9	27.9	32.1	31.9	37.2	57.2			
962	5.9	6.6	7.0	7.8	9.9	15.0	16.7	20.6	41.9			
963	19.0	19.0	19.6	21.6	27.4	32.1	38.8	58.9	70.5			
964	1.1	1.4				7.1	9.0	11.5	19.1			
965	5.7	6.7				13.7	15.8	20.6	26.1			
966	4.0	4.5	4.7	4.8	5.0	6.4	13.2	21.8	64.8			
967	43.0	44.0	49.3	58.1	62.0	92.4	122.4	147.2	188.6			

the results obtained through the use of this procedure seem reasonable, it is impossible to verify the accuracy of the frequency estimates.

c. <u>Regionalization</u>. Regionalization of low-flow events is usually not very successful. The variations in geologic conditions such as depth to ground water, size of ground water basin, permeability of the aquifer, etc., are not easily quantifiable to enable translation into probable low-flow rates. It may be possible to estimate low-flow rates on a per unit area basis for a given exceedance frequency if the study area is relatively homogeneous with respect to geology, topography, and climate. If information is needed at several ungaged sites, the procedures described by Riggs (28) should be reviewed for applicability.




Figure 4-1. Low-Flow Frequency Curves.

# PRECIPITATION FREQUENCY ANALYSIS

5-1. General Procedures. The computation of frequency curves of station precipitation can be done by procedures similar to those for streamflow analysis described in the preceding sections. Both graphical and analytical methods may be used. In precipitation studies, however, instantaneous peak intensities are ordinarily not analyzed since they are virtually impossible to measure and are of little practical value. Cumulative precipitation amounts for specified durations are commonly analyzed, mostly for durations of less than 3 or 4 days. The National Weather Service has traditionally used the Fisher-Tippett Type I frequency distribution with Gumbel's fitting procedure. The logarithmic normal, Pearson Type III and log-Pearson Type III (Figure 5-1) distributions, have also been used with success. Station precipitation alone is not adequate for most hydrologic studies, and some method of evaluating the frequency of simultaneous or near-simultaneous precipitation over an area is necessary. Procedures for obtaining depth-area frequency curves are usually available from National Weather Service publications (references are given in subsequent paragraphs).




Figure 5-1. Frequency Curve, Annual Precipitation.

5-2. Available Regional Information. Where practical, use should be made of previous precipitation-frequency-duration studies that have incorporated regional information. For durations of 5 to 60 minutes in an area generally east of 105th meridian, see Hydro-35 (9). For durations of 2 to 24 hours in the same area see Technical Paper 40 (10). Because of the orographic effect, individual reports have been prepared for each of the 11 western states (24). These reports have maps for 6- and 24-hour durations with extrapolation procedures to obtain durations less than 6 hours. Longer duration events (2- to 10-days) are presented in references (21), (22) and (23).

# 5-3. Derivation of Flood-Frequency Relations from Precipitation.

- a. Application. Precipitation-frequency relations are often used to derive flood-frequency relations where inadequate flow data are available or where existing (or proposed) watershed changes have modified (or will modify) the rainfall-runoff relationships. Guidelines for developing runoff frequencies from precipitation frequencies are presented in references (10) and (44). Flood-frequency curves developed by rainfall-runoff procedures often have less variance (lower standard deviation) than those developed from annual flood peaks. This results because not all the possible loss rates for a given magnitude of precipitation are modeled. If extensive use will be made of frequency curves derived by rainfall-runoff modeling, an appropriate ratio adjustment for the standard deviation should be developed for the region.
- b. <u>Calibration</u>. Reference (44) describes the procedures involved in calibrating a HEC-1 model to a flow-frequency curve based either on gaged data from a portion of the basin or on regional flood-frequency relations. The coefficients from the calibrated model must be consistent with those from nearby basins that have also been modeled. It must be remembered that a frequency curve computed from observed flood peaks is based on a relatively small sample. It is possible that the flow-frequency curve derived from precipitation-frequency data is more representative of the population flow-frequency curve than the one computed from the statistics of the observed flood peaks. But, there are also errors in calibrating the model and establishing loss rates approximate with the different frequency events. Therefore, the derivation of frequency relations by rainfall-runoff modeling requires careful checking for consistency at every step.
- c. <u>Partial Duration</u>. The precipitation-frequency relations presented in the National Weather Service publications represent all the events above a given magnitude; therefore, these relations are from a partial-duration series. The resulting flood frequency relations must be adjusted if an annual peak flood frequency relationship is desired. Or, more typically, the partial-duration series precipitation estimates are adjusted to represent annual series estimates prior to use.

## STAGE (ELEVATION) - FREQUENCY ANALYSIS

6-1. <u>Uses</u>. Maximum stage-frequency relations are often required to evaluate inundation damage. Inundation can result from a flooding river, storm surges along a lake or ocean, wind driven waves (runup), a filling reservoir, or combinations of any of these. Minimum elevation-frequency curves are used to evaluate the recreation benefits at a lake or reservoir, to locate a water supply intake, to evaluate minimum depths available for navigation purposes, etc. (Stages are referenced to an arbitrary datum; whereas, elevations are generally referenced to mean sea level.)

### 6-2. Stage Data.

- a. The USGS WATSTORE Peak Flow File has, in addition to annual peak flows, maximum annual stages at most sites. Also, some sites located near estuaries have only stage information because the flow is affected by varying backwater conditions.
- b. River stages can be very sensitive to changes in the river channel and floodway. Therefore, the construction of levees, bridges, or channel modifications can result in stage data that is non-homogeneous with respect to time. For riverine situations, it is usually recommended that the flow-frequency curve (Figure 6-1) and a rating curve (stage versus




Figure 6-1. Flow Frequency Curve, Unregulated and Regulated Conditions.

flow, Figure 6-2) be used to derive a stage-frequency curve (Figure 6-3). A stage-frequency curve derived by indirect methods may not always represent the true relation if the site is subject to occasional backwater situations. Backwater conditions can be caused by an ice jam, a debris flow, a downstream reservoir, a high tide, a storm surge, or a downstream river. A coincident frequency analysis may be necessary to obtain an accurate estimate of the stage-frequency relationship (see Chapter 11).

- c. Usually the annual extreme value is used to develop an annual series, but a seasonal series or a partial-duration series could be developed if needed. Caution must be used in selecting independent events. Independent events are not easily determined if the events are elevations of a large lake or reservoir; in fact even the annual events may be significantly correlated.
- 6-3. Frequency Distribution. Stage (elevation) data are usually not normally distributed (not a straight line on probability paper). Therefore, an analytical analysis should not be made without observing the fit to the plotted points (see Chapter 2). Usually, an arithmetic-probability plot is appropriate for stage or elevation data, but there may be situations where a logarithmic or some other appropriate transformation will make the plot more nearly linear. When drawing the curve, known constraints must be kept in mind. As an example, the bottom elevation, bankfull stage, levee heights, etc., would be important for a riverine site. The minimum pool, top of conservation pool, top of flood control pool, spillway elevation, operation criteria, etc., all influence the elevation-frequency relation for a reservoir, Figure 6-4. These constraints usually make these frequency relations very non-linear. Extrapolation of stage (elevation) frequency relations must be done very cautiously. Again, any constraints acting on the relations must be used as a guide in drawing the curves. Historical information can be incorporated into a graphical analysis of stage (elevation) data by use of the procedures in Appendix 6 of Bulletin 17B (ref 46). The statistical tests (Appendix 4, ref 46) to screen for outliers should not be applied unless the stage (elevation) data can be shown to nearly fit a normal distribution.
- 6-4. Expected Probability. The expected probability adjustment should <u>not</u> be made to frequency relations derived by graphical methods. The median plotting position formula corrects for the bias caused by small sample sizes. The expected probability adjustment should be made when an analytical method is used directly to derive the stage (elevation) frequency relation. The expected probability adjustment should be made to the flow-frequency curve when the stage (elevation) frequency relation is derived indirectly.




Figure 6-2. Rating Curve for Present Conditions.




Figure 6-3. Derived Stage-Frequency Curves, Unregulated and Regulated Conditions




Figure 6-4. Maximum Reservoir Elevation-Frequency Curve.

## DAMAGE-FREQUENCY RELATIONSHIPS

#### 7-1. Introduction.

- a. There are three methods that may be used to compute average annual damage and are herein termed the historic method, the simulation method and the frequency method. If 50 years of damage information were available for an area that has remained in essentially the same land use with a reasonably constant level of economic activity, historic damage could be scaled to the present to account for price differences (inflation) and the average simply computed. This approach is termed the historic method and is the most direct but is seldom used because sufficient data usually do not exist and the land use and economic activity of an area are usually changing.
- b. A hydrologic simulation model could be developed, or the historic record used, along with damage functions to generate a time trace of simulated damage. The average of the time trace of damage would be the average annual damage. This would be termed the "simulation" method. The simulation method has the advantage of permitting the use of complex damage functions that can consider more than a single parameter and thus enable a more accurate computation of damage. The disadvantage of this method is that the future floods are assumed to exactly duplicate the historic floods and no consideration given to the possibility of larger floods.
- c. The most widely used approach within the Corps of Engineers is the frequency technique. This technique is described in detail in Section 7-2. This technique addresses the disadvantages of the previous two methods, and yet is fairly easily applied. Experience in the development and application of damage functions is essential to computation of reasonable estimates. Care should be taken to assure the rating curve is not looped so that discharge is a unique function of stage. Otherwise more complex functions that correctly relate stage and discharge should be developed and applied. Damage functions in agricultural areas are often a function of the season and the duration of flooding. Sensitivity analysis may be useful in determining the reliability of the computed expected annual damage considering the uncertainties involved.

# 7-2. Computation of Expected Annual Damage.

- a. Figure 7-1 shows a schematic of the application of the three basic damage evaluation functions used to compute the expected value of the annual damage. The term "expected" is used rather than "average" because a frequency curve is used to represent the distribution of future flood events and the expected value of damage is computed by the summation of probability weighted estimates of damage.
- b. The steps involved in determining the reduction in annual damage due to project measures are:
  - (1) Develop the basic relationships (stage-damage, stage-discharge, and discharge-exceedance frequency functions) for each index location for existing conditions.




Figure 7-1. Schematic for Computation of Expected Annual Damage.

- (2) Combine the stage-damage and the stage-discharge relations into an intermediate discharge-damage function. Make certain that the stage datum for the stage-damage and stage-discharge functions is consistent for the index location.
- (3) Combine the discharge-exceedance frequency (in events per year) and discharge-damage function into a damage-exceedance frequency relationship.
- (4) Compute the area beneath the damage-exceedance frequency relation (expected annual damage) for each index location and sum to obtain the total expected annual flood damage.
- (5) Repeat step (1) for each alternative flood plain management plan under investigation, i.e., revise the three basic evaluation functions as necessary.
- (6) Repeat steps (2)-(4).
- (7) Subtract results of step (4) (with project) for each plan from results of step (4) for without-project measures. The differences will be expected annual damage reduction (raw damage reduction benefits) for each plan.

# 7-3. Equivalent Annual Damage.

- a. To determine the expected annual benefit it is necessary to account for the changes in expected annual damage that might occur over the life of the project. This adjustment can be of substantial significance. Watershed runoff characteristics may be changing with time due to changes in land use, there may be long-term adjustments in alluvial channel flow regimes that would cause the rating curve to change with time, and the damage potential of structures and facilities will certainly change with time resulting in changed stage-damage functions.
- b. To develop a single measure of the damage potential, the expected annual damage must be evaluated over time, at say 10 year intervals with revised evaluation functions at each interval. The revised expected annual damage is discounted to the base period and then the raw damage value is amortized over the life of the project to obtain equivalent annual damage. The computer program "Expected Annual Flood Damage Computation" (54) has the capability to make these computations, and describes in detail the basic concepts presented in this chapter.

## STATISTICAL RELIABILITY CRITERIA

- 8-1. Objective. One principal advantage of analytical frequency analysis is that there are means for evaluating the reliability of the parameter estimates. This permits a more complete understanding of the frequency estimates and provides criteria for decision-making. For instance, a common statistical index of reliability is the standard error of estimate, which is defined as the root-mean-square error. In general, it is considered that the standard error is exceeded on the positive side one time out of six estimates, and equally frequently on the negative side, for a total of one time in three estimates. An error twice as large as the standard error of estimate is considered to be exceeded one time in 40 in either direction, for a total of one time in 20. These statements are based on an assumed normal distribution of the errors; thus, they are only approximate for other distributions of errors. Exact statements as to error probability must be based on examination of the frequency curve of errors or the distribution of the errors. Both the standard error of estimate and the confidence limits are discussed in this chapter.
- 8-2. Reliability of Frequency Statistics. The standard errors of estimate of the mean, standard deviation, and skew coefficient, which are the principal statistics used in frequency analysis, are given by the following equations:

$$S_{\overline{Y}} = S/(N)^{\frac{1}{2}} \tag{8-1}$$

$$S_s = S/(2N)^{\frac{1}{2}} \tag{8-2}$$

$$S_{c} = \{6N(N-1)/[(N-2)(N+1)(N+3)]\}^{\frac{N}{2}}$$
(8-3)

where:

 $S_{\overline{v}}$  = the standard error of estimate for the mean

 $S_c =$  the standard error of estimate for the standard deviation

S<sub>G</sub> = the standard error for estimate for the skew coefficient, and S and N are defined in Section 3-2.

These have been used to considerable advantage, as discussed in Chapter 9, in drawing maps of mean, standard deviation and skew coefficient for regional frequency studies.

8-3. Reliability of Frequency Curves. The reliability of analytical frequency determinations can best be illustrated by establishing confidence limits. The error of the estimated value at a given frequency based on a sample from a normal distribution is a function of the errors in estimating the mean and standard deviation. (Note that in practical application there are errors introduced by not knowing the true theoretical distribution of the data, often termed model error.) Criteria for construction of confidence limits are based on the non-central t distribution. Selected values are given in Table F-9. Using that appendix, the confidence limit curves shown on Figure 8-1

were calculated. While the expected frequency is that shown by the middle curve, there is one chance in 20 that the true value for any given frequency is greater than that indicated by the .05 curve and one chance in 20 that it is smaller than the value indicated by the .95 curve. There are, therefore, nine chances in 10 that the true value lies between the .05 and .95 curves. Appendix E and Example 1 in Appendix 12 of Bulletin 17B (40) provide additional information and example computations.




Figure 8-1. Frequency Curve with Confidence Limit Curves.

### REGRESSION ANALYSIS AND APPLICATION TO REGIONAL STUDIES

#### 9-1. Nature and Application.

- a. General. Regression analysis is the term applied to the analytical procedure for deriving prediction equations for a variable (dependent) based on given values of one or more other variables (independent). The dependent variable is the value sought and is to be related to various explanatory variables which will be known in advance, and which will be physically related to the dependent variable. For example, the volume of spring-season runoff from a river basin (dependent variable) might be correlated with the depth of snow cover in the watershed (explanatory variable). Recorded values of such variables over a period of years might be graphed and the apparent relation sketched in by eye. However, regression analysis will generally permit a more reliable determination of the relation and has the additional advantage of providing a means for evaluating the reliability of the relation or of estimates based on the relation.
- b. <u>Definitions</u>. The function relating the variables is termed the "regression equation," and the proportion of the variance of the dependent variable that is explained by the regression equation is termed the "coefficient of determination," which is the square of the "correlation coefficient." Correlation is a measure of the association between two or more variables. Regression equations can be linear or curvilinear, but linear regression suffices for most applications, and curvilinear regression is therefore not discussed herein. Often a curvilinear relation can be linearized by using a logarithmic or other transform of one or more of the variables.

### 9-2. Calculation of Regression Equations.

a. <u>Simple Regression</u>. In a simple regression (one in which there is only one independent, or explanatory, variable), the linear regression equation is written:

$$Y = a + bX \tag{9-1}$$

in which Y is the dependent variable, X is the independent variable, "a" is the regression constant, and "b" is the regression coefficient. The coefficient "b" is evaluated from the tabulated data by use of the following equations:

$$b = \sum (yx)/\sum (x)^2$$
 (9-2a)

or

$$b = RS_{\gamma}/S_{\chi} \tag{9-2b}$$

in which y is the deviation of a single value  $y_i$  from the mean  $(\overline{Y})$  of its series, x is similarly defined,  $S_Y$  and  $S_X$  are the respective standard deviations and R is computed by

Equation 9-11. The regression constant is obtained from the tabulated data by use of the following equation:

$$\mathbf{a} = \overline{\mathbf{Y}} - \mathbf{b}\overline{\mathbf{X}} \tag{9-3}$$

All summations required for a simple linear regression can be obtained using Equations 9-8 and 9-9a.

b. <u>Multiple Regression</u>. In a multiple regression (one in which there is more than one explanatory variable) the linear regression equation is written:

$$Y = a + b_1 X_1 + b_2 X_2 + \dots + b_n X_n$$
 (9-4)

In the case of two explanatory variables, the regression coefficients are evaluated from the tabulated data by solution of the following simultaneous equations:

$$\sum (x_1)^2 b_1 + \sum (x_1 x_2) b_2 = \sum (y x_1)$$

$$\sum (x_1 x_2) b_1 + \sum (x_2)^2 b_1 = \sum (y x_2)$$
(9-5)

In the case of three explanatory variables, the b coefficients can be evaluated from the tabulated data by solution of the following simultaneous equations:

$$\sum (x_1)^2 b_1 + \sum (x_1 x_2) b_2 + \sum (x_1 x_3) b_3 = (yx_1)$$

$$\sum (x_1 x_2) b_1 + \sum (x_2)^2 b_2 + \sum (x_2 x_3) b_3 = (yx_2)$$

$$\sum (x_1 x_2) b_1 + \sum (x_2 x_3) b_2 + \sum (x_2 x_3)^2 b_3 = (yx_2)$$
(9-6)

For cases of more than three explanatory variables, the appropriate set of simultaneous equations can be easily constructed after studying the patterns of the above two sets of equations. In such cases, solution of the equations becomes tedious, and considerable time can be saved by use of the Crout method outlined in reference (51) or (52). Also, programs are available for solution of simple or multiple linear regression problems on practically any type of electronic computer. For multiple regression equations, the regression constant is determined as follows:

$$\mathbf{a} = \overline{\mathbf{Y}} - \mathbf{b}_1 \overline{\mathbf{X}}_1 - \mathbf{b}_2 \overline{\mathbf{X}}_2 \cdot \ldots - \mathbf{b}_n \overline{\mathbf{X}}_n \tag{9-7}$$

In Equations 9-2, 9-5 and 9-6, the quantities  $\sum (x)^2$ ,  $\sum (yx)$  and  $\sum (x_1x_2)$  can be determined by use of the following equations:

$$\sum (x)^2 = \sum (X)^2 - (\sum X)^2 / N$$
 (9-8)

$$\sum (yx) = \sum (XY) - \sum X \sum Y/N$$
 (9-9a)

$$\sum (\mathbf{x}_1 \mathbf{x}_2) = \sum (\mathbf{X}_1 \mathbf{X}_2) - \sum \mathbf{X}_1 \sum \mathbf{X}_2 / \mathbf{N}$$
 (9-9b)

## 9-3. The Correlation Coefficient and Standard Error.

- a. General. The correlation coefficient is the square root of the coefficient of determination, which is the proportion of the variance of the dependent variable that is explained by the regression equation. A correlation coefficient of 1.0 would correspond to a coefficient of determination of 1.0, which is the highest theoretically possible and indicates that whenever the values of the explanatory variables are known exactly, the corresponding value of the dependent variable can be calculated exactly. A correlation coefficient of 0.5 would correspond to a coefficient of determination of 0.25, which would indicate that 25 percent of the variance is accounted for and 75 percent unaccounted for by the regression equation. The remaining variance (error variance) would be 75 percent of the original variance and the remaining standard error would be the square root of 0.75 (or 87 percent) multiplied by the original standard deviation of the dependent variable. Thus, with a correlation coefficient of 0.5, the average error of estimate would be 87 percent of the average errors of estimate based simply on the mean observed value of the dependent variable without a regression analysis.
- b. <u>Determination Coefficient</u>. The sample coefficient of multiple determination (R<sup>2</sup>) can be computed by use of the following equation:

$$R^{2} = \frac{b_{1} \sum (yx_{1}) + b_{2} \sum (yx_{2}) \dots + b_{N} \sum (yx_{n})}{\sum (y)^{2}}$$
(9-10)

In the case of simple correlation, Equation 9-10 resolves to:

$$R^{2} = \sum_{(yx)^{2}} \sum_{(y)^{2}} \sum_{(x)^{2}} (9-11)$$

An unbiased estimate of the coefficient of determination is recommended for most applications, and is computed by the following equation:

$$\bar{R}^2 = 1 - (1 - R^2)(N - 1)/df$$
 (9-12)

The number of degrees of freedom (df), is obtained by subtracting the number of variables (dependent and explanatory) from the number of events tabulated for each variable.

c. <u>Standard Error</u>. The adjusted standard error (S<sub>e</sub>) of a set of estimates is the root-mean-square error of those estimates corrected for the degrees of freedom. On the

average, about one out of three estimates will have errors greater than the standard error and about one out of 20 will have errors greater than twice the standard error. The adjusted error variance is the square of the adjusted standard error. The adjusted standard error or error variance of estimates based on a regression equation is calculated from the data used to derive the equation by use of one of the following equations:

$$S_e^2 = \frac{\sum (y)^2 - b_1 \sum (yx_1) - b_2 \sum (yx_2) \dots - b_n \sum (yx_n)}{df}$$
(9-13a)

$$= (1-\overline{R}^2) \sum (y)^2/(N-1)$$
 (9-13b)

$$= (1 - \overline{R}^2) S_{\nu}^2$$
 (9-13c)

Inasmuch as there is some degree of error involved in estimating the regression coefficients, the actual standard error of an estimate based on one or more extreme values of the explanatory variables is somewhat larger than is indicated by the above equations, but this fact is usually neglected.

d. Reliability. In addition to considering the amount of variance that is explained by the regression equation, as indicated by the determination coefficient or the standard error, it is important to consider the reliability of these indications. There is some chance that any correlation is accidental, but the higher the correlation and the larger the sample upon which it is based, the less is the chance that it would occur by accident. Also, the reliability of a regression equation decreases as the number of independent variables increases. Ezekiel (8) gives a set of charts illustrating the reliability of correlation coefficients. It shows, for example, that an unadjusted correlation coefficient (R) of 0.8 based on a simple linear correlation with 12 degrees of freedom could come from a relationship that has a true value as low as 0.53 in one case out of 20. On the other hand, the same unadjusted correlation coefficient based on a multiple linear correlation with the same number of degrees of freedom but with seven independent variables, could come from a relationship that has a true value as low as zero in one case out of 20. With only 4 degrees of freedom, an unadjusted correlation coefficient of 0.97 would one time in 20 correspond to a true value of 0.8 or lower, in the case of simple correlation, and as low as zero in a seven-variable multiple correlation. Accordingly, extreme care must be exercised in the use of multiple correlation in cases based on small samples.

### 9-4. Simple Linear Regression Example.

- a. General. An example of a simple linear regression analysis is illustrated on Figures 9-1 and 9-2. The data for this example are the concurrent flows at two stations in Georgia for which a two-station comparison is desired (see Section 3-7). The long record station is the Chattooga, so the flows for this station are selected as X; therefore the flows for the short record station (Tallulah) are assigned to Y.
- b. <u>Physical Relationship</u>. The values in the table are the annual peak flows for the water years 1965-1985 (21 values). These two stations are less than 20 miles apart and are likely to be subject to the same storm events; therefore, the first requirement of a

	Chatto	oga River	Tallu	lah River				
	Flow	Log	Flow	Log				
ear	y,	X	Y 1	Y				
965	27200	4.434568	7440	3.871572	Σx_= 82.55075			
966	13400	4.127104	5140	3.710963	ΣΧ <sup>2</sup> = 325.93995	ΣY <sup>Z</sup>	= 25	= 255.6148
967	15400	4.187520	2800	3.447158	$\hat{x} = 3.93099$			3.4799
968	5620	3.749736	3100	3.491361				3.477.
969	14700	4.167317	2470	3.392696	$(\mathbf{z} \times \mathbf{Y})^2 = 288.37484$			
1970	3480	3.541579	2010	3.303196				
971	3290	3.517195	976	2.989449	$\frac{(\Sigma X)^2}{1} = 324.50602$			
972	7440	3.871572	2160	3.334453	N = 324.50802			
973 974	19600 6400	4.292256 3.806179	8500 4660	3.929418 3.668385	, <del>.</del> 2			
975	6340	3.802089	2410	3.382017	$\frac{(\Sigma Y)^2}{\Sigma} = 254.25371$			
976	18500	4.267171	6530	3.814913	•			
977	13000	4.113943	3580	3.553883	$\frac{\Sigma X \Sigma Y}{N} = 287.24008$			
978	7850	3.894869	4090	3.611723	N 201.24000			
979	14800	4.170261	6240	3.795184	$x^2 = 1.43393$			
980	10900	4.037426	2880	3.459392	x= = 1.43393	(by		equati
981	4120	3.614897	1600	3.204119	xy = 1.13351	("		**
982	5000	3.698970	1960	3.292256	$y^2 = 1.26115$	7.0		**
983	7910	3.898176	3260	3.513217	y = 1.20113	,		
984	4810	3.682145	2000	3.301029				
85	4740	3.675778	1010	3.004321				
ь	= 1.133! = 0.7904	56 - (0.7904			(by equation 9-2a) (by equation 9-3)			
R <sup>2</sup>	= (1.133 = 0.6582	351) <sup>2</sup> /(1.433 290	193)(1.3	36115)	(by equation 9-11)			
ē2	= 1 - (1 = 0.6403	1-0.65 <b>89</b> 2)(2 31	21-1)/(2	?1-2)	(by equation 9-12)			
putat	ions for	r stendard e	error:					
s <sub>e</sub> <sup>2</sup>	= (1-0.6 = 0.0244		115)/(2	!1-1)	(by equation 9-13b)			
s <sub>e</sub>	= 0.1564	•6						


Figure 9-1. Computation of Simple Linear Regression Coefficients.

(without logarithms)

Regression equation: Y = 0.37213 + 0.79049X (by equation 9-1) Y'= 2.356X'<sup>0.79</sup>

regression analysis (logical physical relationship) is satisfied. Because runoff is a multiplicative factor of precipitation and drainage area, the logarithmic transformation is likely to be appropriate when comparing two stations with different drainage areas. A linear correlation analysis was made, as illustrated on Figure 9-1, using equations given in Section 9-2. The annual peaks for the each station are plotted against each other on Figure 9-2.

c. Regression Equation. The regression equation is plotted as Curve A on Figure 9-2. This curve represents the best estimate of what the annual peak Tallulah River would be given the observed annual peak on the Chattooga River. Although not computed in Figure 9-1, Curve B represents the regression line for estimating the annual peak flow for the Chattooga River given an observed annual peak on the Tallulah River.



Curve A - Regression line with Y as dependent variable Curve B - Regression line with X as dependent variable

Figure 9-2. Illustration of Simple Regression.

d. Reliability. In addition to the curve of best fit, an approximate confidence interval can be established at a distance of plus and minus 2 standard errors from Curve A. Because logarithms are used in the regression analysis, the effect of adding (or subtracting) twice the standard error to the estimate is equivalent to multiplying (or dividing) the annual peak values by the antilogarithm of twice the standard error. In this case, the standard error is 0.156, and the antilogarithm of twice this quantity is 2.05. Hence, values of annual peak flow represented by the confidence interval curves are those of Curve A multiplied and divided respectively by 2.05. There is a 95 percent chance that the true value of the dependent variable (Y) for a single observed independent value (X) will lie between these limits. The confidence interval is not correct for repeated predictions using the same sample (6).

## 9-5. Factors Responsible for Nondetermination.

- a. General. Factors responsible for correlations being less than 1.0 (perfect correlation) consist of pertinent factors not considered in the analysis and of errors in the measurement of those factors considered. If the effect of measurement errors is appreciable, it is possible in some cases to evaluate the standard error of measurement of each variable (see Paragraph 9-3c) and to adjust the correlation results from such effects.
- Measurement Errors. If an appreciable portion of the variance of Y (dependent variable) is attributable to measurement errors and these errors are random, then the regression equation would be more reliable than is indicated by the standard error of estimate computed from Equation 9-13. This is because the departure of some of the points from the regression line on Figure 9-2 is artificially increased by measurement errors and therefore exaggerates the unreliability of the regression function. In such a case, the curve is generally closer to the true values than to the erroneous observed values. Where there is large measurement error of the dependent variable, the standard error of estimate should be obtained by taking the square root of the difference of the error variance obtained from Equation 9-13 and the measurement error variance. If well over half of the variance of the points from the best-fit line is attributable to measurement error in the dependent variable, then the regression line would actually yield a better estimate of a value than the original measurement. If appreciable errors exist in the values of an explanatory variable, the regression coefficient and constant will be affected, and erroneous estimates will result. Hence, it is important that values of the explanatory variables be accurately determined, if possible.
- c. Other Factors. In the example used in Section 9-4 there may well be factors responsible for brief periods of high intensities that do not contribute appreciably to annual precipitation. Consequently, some locations with extremely high mean annual precipitation may have maximum short-time intensities that are not correspondingly high, and vice versa. Therefore, the station having the highest mean annual precipitation would not automatically have the highest short-time intensity, but would in general have something less than this. On the other hand, if mean annual precipitation were made the dependent variable, the station having the highest short-time intensity would be expected to have something less than the highest value of mean annual precipitation. Thus, by interchanging the variables, a change in the regression line is effected. Curve B of Figure 9-2 is the regression curve obtained by interchanging the variables Y and X. As there is a considerable difference in the two regression curves, it is important to use the variable whose value is to be calculated from the regression equation as the dependent variable in those cases where important factors have not been considered in the analysis.

d. Average Slope. If it is obvious that all of the pertinent variables are included in the analysis, then the variance of the points about the regression line is due entirely to measurement errors, and the resulting difference in slope of the regression lines is entirely artificial. In cases where all pertinent variables are considered and most of the measurement error is in one variable, that variable should be used as the dependent variable. Its errors will then not affect the slope of the regression line. In other cases where all pertinent variables are considered, an average slope should be used. An average slope can be obtained by use of the following equation:

$$b = S_{y}/S_{y} \tag{9-14}$$

## 9-6. Multiple Linear Regression Example.

- a. General. An example of a multiple linear regression analysis is illustrated on Figure 9-3. In this case, the volume of spring runoff is correlated with the water equivalent of the snow cover measured on April 1, the winter low-water flow (index of ground water) and the precipitation falling on the area during April. Here again, it was determined that logarithms of the values would be used in the regression equation. Although loss of 4 degrees of freedom of 12 available, as in this case, is not ordinarily desirable, the adjusted correlation coefficient attained (0.94) is particularly high, and the equation is consequently fairly reliable. The computations in Figure 9-3 were made with the HEC computer program MLRP (reference 50).
- b. Logarithmic Transformation. In determining whether logarithms should be used for the dependent variable as above, questions such as the following should be considered: "Would an increase in snow cover contribute a greater increment to runoff under conditions of high ground water (wet ground conditions) than under conditions of low ground water?" If the answer is yes, then a logarithmic dependent variable (by which the effects are multiplied together) would be superior to an arithmetic dependent variable (by which the effects are added together). Logarithms should be used for the explanatory variables when they would increase the linearity of the relationship. Usually logarithms should be taken of values that have a natural lower limit of zero and a natural upper limit that is large compared to the values used in the study.
- c. <u>Function of Multiple Regression</u>. It should be recognized that multiple regression performs a function that is difficult to perform graphically. Reliability of the results, however, is highly dependent on the availability of a large sampling of all important factors that influence the dependent variable. In this case, the standard error of an estimate as shown on Figure 9-3 is approximately 0.038, which, when added to a logarithm of a value, is equivalent to multiplying that value by 1.09. Thus, the standard error is about 9 percent, and the 1-in-20 error is roughly 18 percent. As discussed in Paragraph 9-3d, however, the calculated correlation coefficient may be accidentally high.
- 9-7. <u>Partial Correlation</u>. The value gained by using any single variable (such as April precipitation) in a regression equation can be measured by making a second correlation study using all of the variables of the regression equation except that one. The loss in correlation by omitting that variable is expressed in terms of the partial correlation coefficient. The square of the partial correlation coefficient is obtained as follows:

INPUT DATA						
OBS NO	OBS ID	LOG Q	LOG SNO	LOG GW	LOG PRO	P
1	1936	.939	.399	.325	.71	ın
ż	1937	.945	.343	.385	.63	-
3	1938	1.052	.369	.408	.88	
4	1939	.744	.246	.428	.58	-
5	1940	.666	.181	.316	1.02	
6	1941	1.081	.297	.460	1.31	-
7	1942	1.060	.299	.511	1.09	
8	1943	.892	.354	.379	.70	7
9	1944	1.021	.295	.395	1.24	•
10	1945	.920	.321	.376	1.09	1
11	1946	.755	. 168	.413	1.03	
12	1947	.960	.280	.410	.97	_
,-	.,	*****		• • • •		
STATISTICS OF	DATA					
				STA	ANDARD	
VARIABLE		VERAGE	VARIANCE	DE\	/IATION	
LOG SNO		.2960	.0050		.0704	
LOG GW		.4005	.0028		.0531	
LOG PRCP	•	.9421	.0572		.2392	
LOG Q		.9196	.0181		. 1346	DEPENDENT
						VARIABLE
						VARIABLE
UNBIASED CORRE	ELATION CO	EFFICIENTS	<u>(R)</u>			VARIABLE
		-	<del></del>	100.0		VARIABLE
	ELATION CO	-	(R) LOG PRCP	LOG Q		VARIABLE
	LOG SNO	LOG GW	<del></del>	LOG 9		VARIABLE
VARIABLE	LOG SNC	LOG GW	LOG PRCP			VARIABLE
VARIABLE LOG SNO	LOG SNC 1.0000	LOG GW .0000 1.0000	LOG PRCP	.6308		VARIABLE
VARIABLE LOG SNO LOG GW	1.0000 .0000 0459	LOG GW .0000 1.0000	LOG PRCP 0459 .1275	.6308 .4170		VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP	1.0000 .0000 0459	LOG GW .0000 1.0000	LOG PRCP0459 .1275 1.0000	.6308 .4170 .2011		VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG Q	1.0000 .0000 0459 .6308	LOG GW .0000 1.0000	LOG PRCP0459 .1275 1.0000	.6308 .4170 .2011		VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP	1.0000 .0000 0459 .6308	LOG GW .0000 1.0000	LOG PRCP0459 .1275 1.0000	.6308 .4170 .2011 1.0000		VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG G	1.0000 .0000 0459 .6308	.0000 1.0000 1.275 .4170	0459 1275 1.0000 .2011	.6308 .4170 .2011 1.0000		VARIABLE
VARIABLE  LOG SNO LOG GW LOG PRCP LOG Q  REGRESSION RES	1.0000 .0000 0459 .6308	LOG GW .0000 1.0000 .1275 .4170	LOG PRCP0459 .1275 1.0000 .2011	.6308 .4170 .2011 1.0000 PARTIAL	•••	VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG G	1.0000 .0000 0459 .6308	.0000 1.0000 1.275 .4170	LOG PRCP0459 .1275 1.0000 .2011	.6308 .4170 .2011 1.0000	•••	VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG Q  REGRESSION RES INDEPEND VARIAB	1.0000 .0000 0459 .6308 SULTS ENT LE	LOG GW .0000 1.0000 .1275 .4170 REGRESSIG	0459 .1275 1.0000 .2011	.6308 .4170 .2011 1.0000 PARTIAL TERMINATIO	•••	VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG Q  REGRESSION RES INDEPEND VARIAB	1.0000 .0000 0459 .6308 SULTS ENT LE	LOG GW .0000 1.0000 .1275 .4170 REGRESSIG COEFFICIE	0459 .1275 1.0000 .2011	.6308 .4170 .2011 1.0000 PARTIAL TERMINATIO DEFFICIENT .9106	•••	VARIABLE
VARIABLE LOG SNO LOG GW LOG PRCP LOG Q  REGRESSION RES INDEPEND VARIAB	1.0000 .0000 0459 .6308 SULTS ENT LE	LOG GW .0000 1.0000 .1275 .4170 REGRESSIG	0459 .1275 1.0000 .2011	.6308 .4170 .2011 1.0000 PARTIAL TERMINATIO	•••	VARIABLE

Figure 9-3. Example Multiple Linear Regression Analysis.

SQUARE

.9437

REGRESSION

CONSTANT

-.223698

UNBIASED

SQUARE

.9226

STANDARD ERROR OF

ESTIMATE

.0375

$$r_{y3.12}^2 = 1 - (1 - R_{y.123}^2)/(1 - R_{y.12}^2)$$
 (9-15)

in which the subscript to the left of the decimal indicates the variable whose partial correlation coefficient is being computed, and the subscripts on the right of the decimal indicate the independent variables. An approximation of the partial correlation can sometimes be made by use of beta coefficients. After the regression equation has been calculated, beta coefficients are very easy to obtain by use of the following equation:

$$\beta_{\rm p} = b_{\rm p} S_{\rm p} / S_{\rm y} \tag{9-16}$$

The beta coefficients of the variables are proportional to the influence of each variable on the result. While the partial correlation coefficient measures the increase in correlation that is obtained by addition of one more explanatory variable to the correlation study, the beta coefficient is a measure of the proportional influence of a given explanatory variable on the dependent variable. These two coefficients are related closely only when there is no interdependence among the various explanatory variables. However, some explanatory variables naturally correlate with each other, and when one is removed from the equation, the other will take over some of its weight in the equation. For this reason, it must be kept in mind that beta coefficients indicate partial correlation only approximately.

- 9-8. Verification of Regression Results. Acquisition of basic data after a regression analysis has been completed will provide an opportunity for making a check of the results. This is done simply by comparing the values of the dependent variable observed, with corresponding values calculated from the regression equation. The differences are the errors of estimate, and their root-mean-square is an estimate of the standard error of the regression-equation estimates (Paragraph 9-3). This standard error can be compared to that already established in Equation 9-13. If the difference is not significant, there is no reason to suspect the regression equation of being invalid, but if the difference is large, the regression equation and standard error should be recalculated using the additional data acquired.
- 9-9. Regression by Graphical Techniques. Where the relationships among variables used in a regression analysis are expected to be curvilinear and a simple transformation cannot be employed to make these relationships linear, graphical regression methods may prove useful. A satisfactory graphical analysis, however, requires a relatively large number of observations and tedious computations. The general theory employed is similar to that discussed above for linear regression. Methods used will not be discussed herein, but can be found in references 8 and 27.
- 9-10. <u>Practical Guidelines</u>. The most important thing to remember in making correlation studies is that accidental correlations occur frequently, particularly when the number of observations is small. For this reason, variables should be correlated only when there is reason to believe that there is a physical relationship. It is helpful to make preliminary examination of relationships between two or more variables by graphical plotting. This is particularly helpful for determining whether a relationship is linear and in selecting a transformation for converting curvilinear relationships to linear relationships. It should also be remembered that the chance of accidentally high

correlation increases with the number of correlations tried. If a variable being studied is tested against a dozen other variables at random, there is a chance that one of these will produce a good correlation, even though there may be no physical relation between the two. In general, the results of correlation analyses should be examined to assure that the derived relationship is reasonable. For example, if streamflow is correlated with precipitation and drainage area size, and the regression equation relates streamflow to some power of the drainage area greater than one, a maximum exponent value of one should be used, because the flow per square mile usually does not increase with drainage area when other factors remain constant.

# 9-11. Regional Frequency Analysis.

- a. General. In order to improve flood frequency estimates and to obtain estimates for locations where runoff records are not available, regional frequency studies may be utilized. Procedures described herein consist of correlating the mean and standard deviation of annual maximum flow values with pertinent drainage basin characteristics by use of multiple linear regression procedures. The same principles can be followed using graphical frequency and correlation techniques where these are more appropriate.
- b. <u>Frequency Statistics</u>. A regional frequency correlation study is based on the two principal frequency statistics: the mean and standard deviation of annual maximum flow logarithms. Prior to relating these frequency statistics to drainage basin characteristics, it is essential that the best possible estimate of each frequency statistic be made. This is done by adjusting short-record values by the use of longer records at nearby locations. When many stations are involved, it is best to select long-record base stations for each portion of the region. It might be desirable to adjust the base station statistics by use of the one or two longest-record stations in the region, and then adjust the short-record station values by use of the nearest or most appropriate base station. Methods of adjusting statistics are discussed in Section 3-7.
- c. <u>Drainage-Basin Characteristics</u>. A regional analysis involves the determination of the main factors responsible for differences in precipitation or runoff regimes between different locations. This would be done by correlating important factors with the long-record mean and with the long-record standard deviation of the frequency curve for each station (the long-record values are those based on extension of the records as discussed in Section 3-7). Statistics based on precipitation measurements in mountainous terrain might be correlated with the following factors:
  - Elevation of station
  - General slope of surrounding terrain
  - Orientation of that slope
  - Elevation of windward barrier
  - Exposure of gage
  - Distance of leeward controlling ridge

Statistics based on runoff measurements might be correlated with the following factors:

- Drainage area (contributing)
- Stream length
- Slope of drainage area or of main channel
- Surface storage (lakes and swamps)
- Mean annual rainfall
- Number of rainy days per year
- Infiltration characteristics
- Urbanized Area
- d. <u>Linear Relationships</u>. In order to obtain satisfactory results using multiple linear regression techniques, all variables must be expressed so that the relation between the independent and any dependent variable can be expected to be linear, and so that the interaction between two independent variables is reasonable. An illustration of the first condition is the relation between rainfall and runoff. If the runoff coefficient is sensibly constant, as in the case of urban or airport drainage, then runoff can be expected to bear a linear relation to rainfall. However, in many cases initial losses and infiltration losses cause a marked curvature in the relationship. Ordinarily, it will be found that the logarithm of runoff is very nearly a linear function of rainfall, regardless of loss rates, and in such cases, linear correlation of logarithms would be most suitable. An illustration of the second condition is the relation between rainfall, D, drainage area, A, and runoff, Q. If the relation used for correlation is as follows:

$$Q = aD + bA + c (9-17)$$

then it can be seen that one inch change in precipitation would add the same amount of flow, regardless of the size of drainage area. This is not reasonable, but again a transformation to logarithms would yield a reasonable relation:

$$\log Q = d \log D + e \log A + \log f \tag{9-18}$$

or transformed:

$$Q = fD^{d}A^{e} (9-19)$$

Thus, if logarithms of certain variables are used, doubling one independent quantity will multiply the dependent variable by a fixed ratio, regardless of what fixed values the other independent variables have. This particular relationship is reasonable and can be easily visualized after a little study. There is no simple rule for deciding when to use

logarithmic transformation. It is usually appropriate, however, when the variable has a fixed lower limit of zero. The transformation should provide for near-uniform variance throughout the range of data.

- e. Example of Regional Correlation. An illustrative example of a regional correlation analysis for the mean log of annual flood peaks (Y) with several basin characteristics is shown on Figure 9-4. In this example, the dependent variable is primarily related to the drainage area size, but precipitation and slope added a small amount to the adjusted determination coefficient. The regression equation selected for the regional analysis included only drainage area as an independent variable.
- f. Selection of Useful Variables. In the regression equations shown on Figure 9-4, the adjusted determination coefficient increases as variables are deleted according to their lack of ability to contribute to the determination. This increase is because there is a significant increase in the degrees of freedom as each variable is deleted for this small sample of 20 observations. Both the adjusted determination coefficient and standard error of estimate should be reviewed to determine how many variables are included in the adopted regression equation. Even in the case of a slight increase in correlation obtained by adding a variable, consideration of the increased unreliability of R as discussed in Section 9-3 might indicate that the factor should be eliminated in cases of small samples. The simplest equation that provides an adequate predictive capability should be selected. In this example, there is some loss in determination in only using drainage area, but this simple equation is adopted to illustrate regional analysis. The adopted equation is:

$$\log Y = 1.586 + 0.962 \log (AREA)$$
 (9-20)

or

$$Y = 38.5 \text{ AREA}^{.962}$$
 (9-21)

The  $\overline{R}^2$  for this equation is 0.839.

g. Use of Map. Many hydrologic variables cannot be expressed numerically. Examples are soil characteristics, vegetal cover, and geology. For this reason, numerical regional analysis will explain only a portion of the regional variation of runoff frequencies. The remaining unexplained variance is contained in the regression errors, which varies from station to station. These regression errors are computed by subtracting the predicted values from the observed values for each station. These errors can then be plotted on a regional map at the centroid of each station's area, and lines of equal values drawn (perhaps using soils, vegetation, or topographic maps as a guide). Combining this regional error with the regression equation should be much better than using the single constant for the entire region. In smoothing lines on such a map, consideration should be given to the reliability of computed statistics. Equations 8-1 and 8-2 can be used to compute the standard errors of estimating means and standard deviations. In Figure 9-5 for example, Station 5340 (observation 11) had 66 years of record and the standard error for the mean was 0.028. There is about one chance in three that the mean is in error by more than 0.029 or about one chance in twenty that the mean is in error by more than 0.056 (twice the standard error). Figure 9-6 shows a map of the errors and Figure 9-5 shows the regional map values for each station and evaluates the worth of the map. The map has a mean square error of 0.0112 compared to that of 0.0356 for the regression equation alone.

IMPUT D	ATA											
OBS NO	08S 1D	AREA	SLOPE	LENGTH	LAKES	ELEV	FOREST	PRECIP	SOILS	MEAN		
1	5090	292.0		31.5	1.5	1.230	35.0	40.0	3.5	3.783		
2	5140	185.0		30.3	1.0		52.0	38.2	3.2	3.783		
3	5180	282.0		29.8	1.0			35.0	3.3	4.030		
4	5200	298.0		37.3	1.0	1.600	30.0	36.5	3.3	4.044		
5	5205	771.0		44.8	1.0	1.447	33.0	36.0	3.2	4.333		
6	5260	114.0	35.8	17.5	1.0	1.383	30.0	34.0	3.0	3.751		
7	5270	52.2		17.4	1.0	1.489	26.0	33.0	3.0	2.637		
8	5280	66.8		20.1	1.0	1.305		33.6	3.0	3.186		
9	5305	77.5		18.9	1.0	1.123		34.6	3.0	3.348		
10	5320	215.0		27.5	1.1	.966		35.5	3.0	3.995		
11	5340	383.0		36.7	3.5	1.370		42.0	3.3	4.122		
12	5375	15.7		5.6		1.350		40.0	3.5	2.722		
13	5380	43.8		22.1		1.300	85.0	43.0	3.5	3.078		
14	5390	274.0		32.3	1.6	1.200	70.0	43.0	2.8	3.930		
15	5445	136.0			1.0	1.800		43.0	4.9	3.590		
16	5485	604.0		44.5		1.900		37.0	3.2	4.092		
17	5495	37.7		15.2		1.350	67.0	37.8	3.2	3.284		
18	5500	173.0		24.2		1.700		39.0	3.9	3.816		
19	5520	443.0	24.4	56.0	1.3	1.600		44.0	3.2	3.816 4.275 3.249		
20	5525	23.8	115.7	10.0	1.0	1.800	80.0	47.0	4.3	3.249		
STATIST	CS OF D	DATA				STANDARD						
VARIA	ILE	AVE	RAGE	VARIAN	Œ	DEVIATIO						
ARE/	l	2 1	1488	.22	LO	.474	τ.					
SLOPE			105	.12		.354	-					
LENG1			5832	.05		.234						
STORA			)540	.01		.130						
ELEV			339	.070		.265						
FORES			7293	.03		. 187						
PRECI			845	.00		.044						
SOIL			5230	.003		.058						
MEA			5524	.24				NDENT VA	RIABLE			
UMBIASED	CORREL	ATION CO	EFFICIENT	<u>s</u>								
VARIABL	.E	AREA	SLOPE	LENGTH	LAKE	S ELI	EV FI	OREST	PRECIP	SOILS	MEAN	
AREA	_		6327	.9304		.00		.0000	.0000		.9159	
SLOPE			1.0000	7144	131			.3635	.1867		4521	
LENGTH			7144	1.0000	.234			.0000	.0000		.8263	
STORAG			1318	.2345	1.000			.0000	.2812	.0000	.2596	
ELEV			.1187	.0000	.000			.2791	.0000		.0000	
FOREST				.0000	.000			.0000	.6877		.0000	
PRECIP			.1867	,0000	.281			.6877	1.0000		.0000	
SOILS		0000	.2053	1096	.000			.4304	.5412		.0000	
MEAN			4521	.8263	.259			.0000	.0000	.0000	1.0000	
							_					
JAMARY O			ALYSES FO							DJUSTED	STANDARD	MEAN
REGRESSI	ON			REGRESSIC	N COEFFI	CIENT .			. DETE	RMINATION	ERROR OF	SQUAR
	T ARI	EA SLO	PE LENGT	H LAKES	ELE1	FOREST		SOIL!	COE	FFICIENT	ESTIMATE	ERRO
CONSTAN										0 0007	0.21/2	0 05-
		ai A 1	82 -0.32				1.739			0.8097	0.2162	0.025
-1.52			48			0.054	1.874	·		0.8254	0.2070	0.025
-1.52 -1.63	3 1.2	69 0.1										
-1.52 -1.63	3 1.24 8 1.24	69 0.1 67 0.1	79 -0.35	0 -0.301	-0.165		2.023	5	•	0.8386	0.1990	
-1.52 -1.63 -1.80	3 1.24 8 1.24 8 1.13	69 0.1 67 0.1 30 0.2	79 -0.35 43	0 -0.301 0.251	-0.165 -0.167		2.023 1.753	5 5	•	0.8386 0.8469	0.1990 0.1939	0.026
-1.52 -1.63 -1.80 -1.66	3 1.2 8 1.2 8 1.1 0 1.1	69 0.1 67 0.1 30 0.2 04 0.2	79 -0.35 43 50	0 -0.301 0.251	-0.165 -0.167 -0.125		2.02 1.75 1.39	5 5	•	0. <b>838</b> 6 0.8469 0.8537	0.1990 0.1939 0.1896	0.026 0.026
-1.52 -1.63 -1.80 -1.66 -1.13 -1.03	3 1.2/8 1.2/8 1.1/9 1.1/9 1.1/9 1.1/9	69 0.1 67 0.1 30 0.2 04 0.2 69 0.1	79 -0.35 43 50 98	0 -0.301 0.251	-0.165 -0.167 -0.129		2.022 1.753 1.399 1.319	3 3 9	•	0.8386 0.8469 0.8537 0.8584	0.1990 0.1939 0.1896 0.1865	0.026 0.026 0.027
-1.52 -1.63 -1.80 -1.66	3 1.24 8 1.24 8 1.13 0 1.16 4 1.06 4 0.99	69 0.1 67 0.1 30 0.2 04 0.2 69 0.1	79 -0.35 43 50 98	0 -0.301 0.251	-0.165 -0.167 -0.125		2.02 1.75 1.39	3 3 9		0. <b>838</b> 6 0.8469 0.8537	0.1990 0.1939 0.1896	0.0256 0.026 0.026 0.027 0.030 0.0356

Figure 9-4. Regression Analysis for Regional Frequency Computations.

REGIONAL	ANALYSIS	WITH REGR	ESSION ON	DRAINAGE A	REA ONLY					
OBS NO	STATION	OBSERVED	COMPUTED	ERROR	MAP VALUE	DIFF	DIFF <sup>2</sup>	YEARS OF RECORD	STANDARD DEVIATION	S <sub>₹</sub>
1	5090	3.783	3.957	-0.174	-0.18	0.006	0.000036	43	0.190	0.029
2	5140	3.783	3.766	0.017	0.01	0.007	0.000049	52	0.195	0.027
3	5180	4.030	3.942	0.088	0.09	-0.002	0.000004	39	0.289	0.046
4	5200	4.044	3.965	0.079	0.07	0.009	0.000081	27	0.256	0.049
Š	5205	4.333	4.362	-0.029	0.08	-0.109	0.011881	50	0.251	0.035
6	5260	3.751	3.564	0.187	0.11	0.077	0.005929	35	0.293	0.050
7	5270	2.637	3.238	-0.601	-0.22	-0.381	0.145161	31	0.206	0.037
	5280	3.186	3.341	-0.155	-0.17	0.015	0.000225	45	0.186	0.028
ğ	5305	3.348	3.403	-0.055	-0.04	-0.015	0.000225	44	0.128	0.019
10	5320	3.995	3.829	0.166	0.16	0.006	0.000036	66	0.288	0.035
11	5340	4.122	4.070	0.052	0.02	0.032	0.001024	66	0.227	0.028
12	5375	2.722	2.736	-0.014	-0.05	0.036	0.001296	40	0.323	0.051
13	5380	3.078	3.164	-0.086	-0.08	-0.006	0.000036	60	0.226	0.029
14	5390	3.930	3.930	0.000	0.00	0.000	0.000000	41	0.261	0.041
15	5445	3.590	3.638	-0.048	-0.15	0.102	0.010404	39	0.278	0.045
16	5485	4.092	4.260	-0.168	-0.08	-0.088	0.007744	61	0.242	0.031
17	5495	3.284	3.102	0.182	0.04	0.142	0.020164	39	0.242	0.039
18	5500	3.816	3.738	0.078	0.08	-0.002	0.000004	66	0.237	0.029
19		4.275	4.131	0.144	0.17	-0.026	0.000676	54	0.277	0.038
20		3.249	2.910	0.339	0.20	0.139	0.019321	39	0.291	0.047
				Sum	0.06	-0.058	0.224296			
				Average	0.003	-0.003	0.0112			

Figure 9-5. Regional Analysis Computations for Mapping Errors.




Figure 9-6. Regional Map of Regression Errors.


- h. <u>Summary of Procedure</u>. A regional analysis of precipitation or flood-flow frequencies is generally accomplished by performing the following steps:
  - (1) Select long-record base stations within the region as required for extension of records at each of the short-record stations.
  - (2) Tabulate the maximum events of each station.
  - (3) Transform the data to logarithms and calculate  $\overline{X}$ , S and, if appropriate, G (Equations 3-1, 3-2 and 3-3) for each base station.
  - (4) Calculate  $\overline{X}$  and S for each other station and for the corresponding values of the base station, and calculate the correlation coefficient (Equation 3-16).
  - (5) Adjust all values of  $\overline{X}$  and S by use of the base station, (Equations 3-17 and 3-19). (If any base station is first adjusted by use of a longer-record base station, the longer-record statistics should be used for all subsequent adjustments.)
  - (6) Select meteorological and drainage basin parameters that are expected to correlate with  $\overline{X}$  and S, and tabulate the values for each drainage basin or representative area.
  - (7) Calculate the regression equations relating  $\overline{X}$  and S to the basin characteristics, using procedures explained in Section 9-2, and compute the corresponding determination coefficients.
  - (8) Eliminate variables in turn that contribute the least to the determination coefficient, recomputing the determination coefficient each time, and select the regression equation having the highest adjusted determination coefficient, or one with fewer variables if the adjusted determination coefficient is nearly the same.
  - (9) Compute the regression errors for each station, plot on a suitable map, and draw isopleths of the regression errors for the regression equations of  $\overline{X}$  (see Figures 9-5 and 9-6 for an example) and S considering the standard error for each computed, or adjusted,  $\overline{X}$  and S. Note that an alternate procedure is to add the regression constant to each error value and develop a map of this combined value. This procedure eliminates the need to keep the regression constant in the regression equation as the mapped value now includes the regression constant.
  - (10) A frequency curve can be computed for any ungaged basin in the area covered within the mapped region by using the adopted regression equations and appropriate map values to obtain X and S, and then using the procedures discussed in Section 3-2 to compute several points to define the frequency curve. (It may also be necessary to develop regional (generalized) values of the skew coefficient if the Pearson type III distribution is considered appropriate. The next section describes the necessary steps to compute a generalized skew coefficient.)
- i. Generalized Skew Determinations. Skew coefficients for use in hydrologic studies should be based on regional studies. Values based on individual records are highly unreliable. Figure 9-7 is a plot of skew coefficients sequentially recomputed after adding the annual peak for the given year. Note that, after 1950, the skew coefficient was at a at a minimum of about 0.5 in 1954 and maximum of about 1.9 in 1955, only one year

apart. The procedures for developing generalized skew values are generally set forth in Bulletin 17B (pages 10-15).

In summary, it is recommended that:

- (1) the stations used in the study have 25 or more years of data,
- (2) at least 40 stations be used in the analysis, or at least all stations surrounding the area within 100 miles should be included,
- (3) the skew values should be plotted at the centroid of the basins to determine if any geographic or topographic trends are present,
- (4) a prediction equation should be developed to relate the computed skew coefficients to watershed and climate variables,
- (5) the arithmetic mean of at least 20 stations, if possible, in an area of reasonably homogeneous hydrology should be computed, and
- (6) then select the method that provides the most accurate estimation of the skew coefficient (smallest mean-square error).

In addition to the above guidelines, care should be taken to select stations without significant man-made changes such as reservoirs, urbanization, etc.






Figure 9-7. Annual Peaks and Sequential Computed Skew by Year.

#### CHAPTER 10

### ANALYSIS OF MIXED POPULATIONS

10-1. <u>Definition</u>. The term mixed population, in a hydrologic context, is applied to data that results from two or more different, but independent, causative conditions. For example, floods originating in a mountainous area or the northern part of the United States at a given site could be caused by melting snow or by rain storms. Along the Gulf and Atlantic coasts, floods can be caused by general cyclonic storms or by intense tropical storms. A frequency curve representing the events caused by one of the climatic conditions may have a significantly different slope (standard deviation) than for the other condition. A frequency plot of the annual events, irrespective of cause, may show a rather sudden change in slope and the computed skew coefficient may be comparatively high. In these situations, a frequency curve derived by combining the frequency curves of each population can result in a computed frequency relation more representative of the observed events.

## 10-2. Procedure.

- a. The largest annual event is selected for each causative condition. As Bulletin 17B (46) cautions, "If the flood events that are believed to comprise two or more populations cannot be identified and separated by an objective and hydrologically meaningful criterion, the record shall be treated as coming from one population." Also, Bulletin 17B states, "Separation by calendar periods in lieu of separation by events is not considered hydrologically reasonable unless the events in the separated periods are clearly caused by different hydrometeorologic conditions."
- b. The frequency relations for each separate population can be derived by the graphical or analytical techniques described in Chapter 2 and then combined to yield the mixed population frequency curve. The individual annual frequency curves are combined by "probability of union." For two curves, the equation is:

$$P_{c} = P_{1} + P_{2} - P_{1}P_{2} \tag{10-1}$$

where:

- P<sub>c</sub> = Annual exceedance <u>probability</u> of combined populations for a selected magnitude.
- P<sub>1</sub> = Annual exceedance <u>probability</u> of same selected magnitude for population series 1.
- P<sub>2</sub> = Annual exceedance <u>probability</u> of same magnitude selected above for population series 2.
- c. Figure 10-1 illustrates a combined annual-event frequency curve derived by combining a hurricane event frequency curve with a nonhurricane event curve for the Susquehanna River at Harrisburg, PA. For more than two population series, n curves may be more easily combined by the following form:

$$P_{c} = 1 - (1-P_{1})(1-P_{2})...(1-P_{n})$$
 (10-2)

NOTE: The exceedance probability (percent chance exceedance divided by 100) must be used in the above equations.

d. If partial duration curves are to be added, the equation is simply  $P_c = P_1 + P_2$ . This assumes that the events in both series are hydrologically independent. When the combined curve is used in an economic analysis, the events in both series must also be economically independent.

## 10-3. Cautions.

- a. If annual flood peaks have been separated by causative factors, a generalized skew must be derived for each separate series to apply the log-Pearson Type III distribution as recommended by Bulletin 17B. Plate 1 of Bulletin 17B or any other generalized skew map based on the maximum annual event, irrespective of cause, will not be applicable to any of the separated series. Derivation of generalized skew relations for each series can involve much effort.
- b. Some series may not have an event each year. For example, tropical storms do not occur every year over most drainage areas in the United States, and quite often there are only a few flood events for the series. Extensive regionalization may be necessary to reduce the probable error in the frequency relations which results from small sample sizes.
- c. Sometimes frequency relations of particular seasons are of interest, i.e., quarterly or monthly, and the curves are combined to verify the annual series curve. The combined curve will very likely fit the annual curve only in the middle parts of the curve. The lower end of the curve will have a partial duration shape as many small events have been included in the analysis. Also, it is possible that the slope of the frequency relation will be higher at the upper end of the curve as the one season or month with the maximum event included in its series will likely have a higher slope than that of the annual series.
- d. A basic assumption of this procedure is that each series is independent of the other. Coincidental frequency analysis techniques must be used where dependance is a factor. For instance, the frequency curves of two or more tributary stations cannot be combined by the above equation to derive the frequency curve of a downstream site. This is because the downstream flow is a function of the summation of the coincident flows on each of the tributaries.




Figure 10-1. Nonhurricane, Hurricane, and Combined Flood Frequency Curves.

#### CHAPTER 11

### FREOUENCY OF COINCIDENT FLOWS

11-1. <u>Introduction</u>. In many cases of hydrologic design, it is necessary to consider only those events which occur coincidentally with other events. For example, a pump station is usually required to pump water only when interior runoff occurs at a time that the main river stage is above interior ponding levels. In constructing a frequency curve of interior runoff that occurs only at such times, data selected for direct use should be limited to that recorded during high river stages. In some cases, such data might not be adequate, but it is possible in these cases where the two types of events are not highly correlated to make indirect use of noncoincident data in order to establish a more reliable frequency curve of coincident events.

## 11-2. A Procedure for Coincident Frequency Analysis.

- a. Objective. Determine an exceedance-frequency relationship for a variable C. Variable C is a function of two variables, A and B.
- b. Selection of Dominant Variable. The variable that has the largest influence on variable C is designated as variable A; the less influential variable is designated as variable B. The significance of "influential" will be indicated by means of an example. Figure 11-1 shows water surface profiles along a tributary near the junction with a main river. Stage on the tributary (variable C) is a function of main river stage and tributary discharge. In Region I, main river stage, will tend to have the dominant influence on tributary stage, whereas in Region II, tributary discharge will tend to dominate. The boundary between Regions I and II cannot be precisely defined and will vary with exceedance frequency. Stage-frequency determinations will be least accurate in the vicinity of the boundary where both variables have a substantial impact on the combined result.

# c. Procedure.

- (1) Construct a duration curve for variable B. Discretize the duration curve with a set of "index" values of B. Index values should represent approximately equal ranges of magnitude of variable B. The area under the resulting discretized duration curve should equal the area under the original duration curve. The number of index values of B required for discretization depends on the range of variation of B and the sensitivity of variable C to B. Therefore, the number of points selected should adequately define the relationships.
- (2) For each of the index values of variable B, develop a relationship between variable A and the combined result C. In the illustration (Figure 11-1) the relationship linking variables A, B and C would be obtained with a set of water surface profile calculations for various combinations of main river stage and tributary discharge.
- (3) If variables A and B are independent of each other, construct an exceedance-frequency curve of variable A. If the variables are not independent,

construct a conditional exceedance-frequency curve of variable A for each index value of variable B.

- (4) Using the relationship developed in step (2) and frequency curve(s) developed in step (3), construct a conditional exceedance-frequency curve of variable C for each index value of variable B.
- (5) For a selected magnitude of variable C, multiply the exceedance-frequencies from each curve developed in step (4) by the corresponding proportions of time represented, and sum these products to obtain the exceedance-frequency of variable C. Repeat this step for other selected magnitudes of C until a complete exceedance-frequency curve for variable C is defined. This step is an application of the total probability theorem.
- d. <u>Seasonal Effects</u>. The duration of frequency curves from steps (1) and (3) are assumed to represent stationary processes. That is, it is assumed that probabilities and exceedance frequencies obtained from the curves do not vary with time. In order for this assumption to be reasonably valid, it is generally necessary to follow the above procedure on a seasonal basis. Once seasonal exceedance-frequency curves have been obtained (step e), they may be combined to obtain an all-season exceedance-frequency curve.
- e. Assumption of Independence. Although step (3) enables application of the procedure to situations where variables A and B are not independent, data is generally not available to establish the conditional exceedance frequency curves required by that step. Consequently, application of the procedure presented here is generally limited to situations where it is reasonable to assume that variables A and B are independent.




Figure 11-1. Illustration of Water Surface Profiles in Coincident Frequency Analysis.

### CHAPTER 12

### STOCHASTIC HYDROLOGY

# 12-1. Introduction.

- a. A stochastic process is one in which there is a chance component in each successive event and ordinarily some degree of correlation between successive events. Modeling of a stochastic process involves the use of the "Monte Carlo" method of adding a random (chance) component to a correlated component in order to construct each new event. The correlated component can be related, not only to preceding events of the same series, but also to concurrent and preceding events of series of related phenomena.
- b. Work in stochastic hydrology has related primarily to annual and monthly streamflows, but the results often apply to other hydrologic quantities such as precipitation and temperatures. Some work on daily streamflow simulation has been done.

# 12-2. Applications.

- a. Hydrologic records are usually shorter than 100 years in length, and most of them are shorter than 25 years. Even in the case of the longest records, the most extreme drought or flood event can be far different from the next most extreme event. There is often serious question as to whether the extreme event is representative of the period of record. The severity of a long drought can be changed drastically by adding or subtracting 1 year of its duration. In order that some estimate of the likelihood of more severe sequences can be made, the stochastic process can be simulated, and long sequences of events can be generated. If the generation is done correctly, the hypothetical sequence would have as equal likelihood of occurrence in the future as did the observed record.
- b. The design of water resource projects is commonly based on assumed recurrence of past hydrologic events. By generating a number of hydrologic sequences, each of a specified desired length, it is possible to create a much broader base for hydrologic design. While it is not possible to create information that is not already in the record, it is possible to use the information more systematically and more effectively. In selecting the number and length of hydrologic sequences to be generated, it is usually considered that 10 to 20 sequences would be adequate and that their length should correspond to the period of project amortization.
- c. It must be recognized that the more hydrologic events that are generated, the more chance there is that an extreme event or combination of events will be exceeded. Consequently, it is not logical that a design be based on the most extreme generated event, but rather on some consideration of the total consequences that would prevail for a given design if all generated events should occur. The more events that are generated, the less proportional weight each event is given. If a design is tested on 10 sequences of hydrologic events, for example, the benefits and costs associated with each sequence would be divided by 10 and added in order to obtain the "expected" net benefits.
- 12-3. <u>Basic Procedure</u>. Successful simulation of stochastic processes in hydrology has been based generally on the concept of multiple linear regression, where the regression

equation determines the correlated component, and the standard error of estimate determines the random component. Figure 12-1 illustrates the general nature of the process. In this case, a low degree of correlation is illustrated, in order to emphasize important aspects of the process. It can be seen that, if every estimate of the dependent variable is determined by the regression line (Figure 12-1a), the estimated points would be perfectly correlated with the independent variable and would have a much smaller range of magnitude than the actual observed values of the dependent variable. In order to avoid such unreasonable results, it is necessary to add a random component to each estimate (Figure 12-1b), and this random component should conform to the scatter of the observed data about the regression line.




Figure 12-1a. Data Estimation from Regression Line.




Figure 12-1b. Data Estimation with Addition of Random Errors.

## 12-4. Monthly Streamflow Model.

a. In accordance with the above basic procedure, a simulation model for generating values of a variable which can be defined only partially by a deterministic relation is:

$$Y = a + b_1 X_1 + b_2 X_2 + ZS_{\gamma} (1-R^2)^{\frac{1}{2}}$$
 (12-1)

where:

Y = dependent variable

a = regression constant

b<sub>1</sub>,b<sub>2</sub> = regression coefficients

 $X_1, X_2$  = independent variables

Z = random number from normal standard population with zero mean and unit variance

S<sub>v</sub> = standard deviation of dependent variable

R = multiple correlation coefficient

b. This type of simulation model can be used to generate related monthly streamflow values at one or more stations. Multiple linear regression theory is based on the assumed distribution of all variables in accordance with the Gaussian normal distribution. Therefore, mathematical integrity requires that each variable be transformed to a normal distribution, if it is not already normal. It has been found that the logarithms of streamflows are approximately normally distributed in most cases. For computational efficiency it is convenient to work with deviations from the mean which have been normalized by dividing by the standard deviation. This deviate is sometimes called the Pearson Type III deviate and can be computed as follows:

$$t_i = (X_{i,j} - \overline{X}_i)/S_i \tag{12-2}$$

where:

t = Pearson Type III deviate

i = month number

j = year number

X = logarithm of flow

 $\overline{X}$  = mean of flow logarithms

S = standard deviation of flow logarithms

EM 1110-2-1415 5 Mar 93

c. If these deviates exhibit a skewness, they can be further transformed, if necessary, to a distribution very close to normal by use of the following approximate Pearson Type III transform equation:

$$K_i = (6/G_i) \{ [(G_i t_i/2) + 1]^{1/3} + 1 \} + G_i/6$$
 (12-3)

where:

K = normal standard deviate

i = month number

G = skew coefficient

t = Pearson Type III deviate as defined in Equation 12-2

An equation for generating monthly streamflow is:

$$K_{i,k}' = \beta_1 K_{i,1}' + \beta_2 K_{i,2}' + \dots + \beta_{k-1} K_{i,k-1}' + \beta_k K_{i-1,k}'$$

$$+ \beta_{k+1} K_{i-1,k+1}' + \beta_n K_{i-1,n}' + Z_{i,k} (1 - R_{i,k}^2)^{k}$$
(12-4)

where:

K' = monthly flow logarithm, expressed as a normal standard deviate

 $\beta$  = beta coefficient, defined as  $b_{i,m}S_{i,m}/S_{i,k}$  where m is a station not equal to k and b is the regression coefficient.

i = month number for value being generated

k = station number for value being generated

n = number of interrelated stations

R = multiple correlation coefficient

Z = random number from normal standard population

For the case of a single station, this resolves to:

$$K_{i}' = R_{i,i-1} K_{i-1}' + Z_{i} (1 - R_{i,i-1}^{2})^{t_{i}}$$
 (12-5)

- d. Note that Equation 12-5 is very similar to Equation 12-1. The differences result from using normal standard deviates. When this is done, the regression constant, a, equals zero, the regression coefficients, b, become beta coefficients,  $\beta$ , and the standard deviation, S, does not appear in the random component since it equals 1. Note also that one of the independent variables is the flow for the preceding month in order to preserve the inherent serial correlation. The flow value in the original units is computed by reversing the transformation process, i.e., from normal standard deviate to Pearson Type III deviate, to logarithm of flow and finally flow value.
- e. A step-by-step procedure for generating monthly streamflows for a number of interrelated locations having simultaneous records is as follows:
  - (1) Compute the logarithm of each streamflow quantity. If a value of zero streamflow is possible, it is necessary to add a small increment, such as 0.1 percent of the mean annual flow, to each monthly quantity before taking the logarithm.
  - (2) Compute the mean, standard deviation and skew coefficient of the values for each location and each month, using equations given in Chapter 2.
  - (3) For each month and location, subtract the mean from each event and divide by the standard deviation (Equation 12-2).
  - (4) Transform these "standardized" quantities to a normal distribution by use of Equation 12-3.
  - (5) Arrange the locations in any sequence, and compute a regression equation for each location in turn for each month. In each case, the independent variables will consist of concurrent monthly values at preceding stations and preceding monthly values at the current and subsequent stations.
  - (6) Generate standardized variates for each location in turn for each month, starting with the earliest month of generated data. This is accomplished by computing a regression value and adding a random component. The random component, according to Equation 12-5, is a random selection from a normal distribution with zero mean and unit standard deviation, multiplied by the alienation coefficient which is  $(1 R^2)^n$ .
  - (7) Transform each generated value by reversing the transform of Equation 12-3 with the appropriate skew coefficient, multiplying by the standard deviation and adding to mean in order to obtain the logarithm of streamflow.
  - (8) Find the antilogarithm of the value determined in step (7) and subtract the small increment added in step (1). If a negative value results, set it to zero.

- f. It is obviously not feasible to accomplish the above computations without the use of an electronic computer. A computer program, HEC-4 Monthly Streamflow Simulation (51) can be used for this purpose.
- 12-5. <u>Data Fill In.</u> Ordinarily, periods of recorded data at different locations do not cover the same time span, and therefore, it is necessary to estimate missing values in order to obtain a complete set of data for analysis as described above. In estimating the missing values, it is important to preserve all statistical characteristics of the data, including frequency and correlation characteristics. To preserve these characteristics, it is necessary to estimate each individual value on the basis of multiple correlation with the preceding value at that location and with the concurrent or preceding values in all other locations. A random component is also required, as indicated in Equation 12-1.
- 12-6. Application In Areas of Limited Data. The streamflow generation models discussed so far have assumed that sufficient records were available to derive the appropriate statistics. For instance, the monthly streamflow model requires four frequency and correlation coefficients for each of the 12 months, or 48 values for one station simulation. A model has been developed (51) that combines the coefficients into a few generalized coefficients for the purpose of generating monthly streamflow at ungaged locations. (Procedures for determining generalized statistics for use in generating daily flows have not yet been developed.) The generalized model considers the following:
  - season of maximum runoff
  - lag to season of minimum runoff
  - average runoff
  - variation between maximum and minimum runoff
  - standard deviation of flows
  - interstation and serial correlations of flows

## 12-7. Daily Streamflow Model.

- a. Generation of daily streamflows can be accomplished in a manner very similar to the generation of monthly streamflow quantities. Although a computer program has been prepared for this purpose, it is capable only of generating flows at a single location and does not provide a totally satisfactory hydrograph. Since it is desired in many reservoir operation studies to use a monthly interval most of the time, and to perform daily operation computations for only a few critical periods, the program has been designed to generate daily flows after the monthly total runoff has been generated by another program. Flows for any particular day are correlated with flows for the preceding day and for the second antecedent day.
- b. A procedure that will give a reasonable shaped hydrograph, as well as coordinated hydrographs at many locations in a basin, would consist of (1) stochastic generation of

precipitation over the basin, and (2) using a precipitation-runoff model to derive the resulting streamflow.

12-8. <u>Reliability</u>. While the simulation of stochastic processes can add reliability in hydrologic design, the techniques have not yet developed to the stage that they are completely dependable. All mathematical models are simplified representations of the physical phenomena. In most applications, simplifying assumptions do not cause serious discrepancies. It is important at this "state of the art," however, to examine carefully the results of hydrologic simulation to assure that they are reasonable in each case.

### APPENDIX A

### SELECTED BIBLIOGRAPHY

### A. REFERENCES AND TEXTBOOKS

- 1. Beard, L. R., "Statistical Methods in Hydrology," U.S. Army Corps of Engineers, Sacramento, CA, January 1962.
- 2. Beard, L. R., "Flood Flow Frequency Techniques," Technical Report CRWR-119, Center for Research in Water Resources, Austin, TX, October 1974.
- 3. Benjamin, J. R. and C. A. Cornell, <u>Probability</u>, <u>Statistics</u>, and <u>Decision for Civil Engineers</u>, McGraw-Hill Book Co., New York, NY, 1970.
- 4. Crippen, J. R., "Composite Log-Type III Frequency-Magnitude Curve of Annual Floods," U.S. Geological Survey Open-File Report 78-352, Reston, VA, 1978.
- 5. Dalrymple, T., "Flood-Frequency Analysis," U.S. Geological Survey Water-Supply Paper 1543-A, GPO, Washington, D.C., 1960.
- 6. Dixon, W. J. and F. J. Massey, Jr., <u>Introduction to Statistical Analysis</u>, 3rd ed., McGraw-Hill Book Co., 1969.
- 7. Draper, N. R. and H. Smith, <u>Applied Regression Analysis</u>, John Wiley & Sons, Inc., 1966.
- 8. Ezekiel, M. and Karl A. Fox, Methods of Correlation and Regression Analysis, 3rd ed., John Wiley and Sons, 1959.
- 9. Frederick, R. H., et. al., "Five-To Sixty-Minute Precipitation Frequency for the Eastern and Central U.S.," NOAA Technical Memorandum NWS Hydro- 35, Silver Spring, MD, June 1977.
- Frederick, R. H., "Interduration Precipitation Relations for Storms-Southeast States," NOAA Technical Report NWS 21, Silver Springs, MD, March 1979.
- 11. Haan, C. T., Statistical Methods in Hydrology, The Iowa State University Press, Ames, IA, 1977.
- 12. Hardison, C. H., "Storage Analysis for Water Supply," Chapter B2 of Hydrologic Analysis and Interpretation, Techniques of Water-Resources Investigations, U.S. Geological Survey, GPO, Washington, D.C., 1973.
- 13. Hazen, A., "Storage to be Provided in Impounding Reservoirs for Municipal Water Supply", Trans. ASCE 77, p 1539-1559, 1914.
- 14. Hershfield, D. M., "Rainfall Frequency Atlas of the U.S.," Technical Paper No. 40, Weather Bureau, U.S. Department of Commerce, Washington, D.C., May 1961.

- 15. Inter-Agency Committee on Water Resources," Methods of Flow Frequency Analysis," Bulletin 13, Subcommittee on Hydrology, Washington, D.C., April 1966.
- 16. James, G. and R. C. James, Mathematics Dictionary, 3rd ed., D. Van Nostrand Co., Inc., Princeton, NJ, 1968.
- 17. Kite, G. W., "Flood Frequency and Risk," Inland Waters Directorate, Ottawa, Canada, 1974.
- 18. Langbein, W. B., and K. T. Iseri, General Introduction and Hydrologic Definitions, U.S. Geological Survey Water-Supply Paper 1541-A, GPO, Washington, D.C., 1960.
- 19. Massey, B. C. and E. E. Schroeder," Application of a Rainfall-Runoff Model in Estimating Flood Peaks for Selected Small Natural Drainage Basins in Texas," U.S. Geological Survey Open-File Report 77-792, Reston, VA, December 1977.
- 20. McCuen, R. H., et al., "Flood Flow Frequency for Ungaged Watersheds A Literature Evaluation," ARS, U.S. Department of Agriculture, Beltsville, MD, November 1977.
- 21. Miller, J. F., "Two- to Ten-Day Precipitation for Return Periods of 2 to 100 Years in the Contiguous U.S.," Technical Paper No. 49, Weather Bureau, U.S. Department of Commerce, Washington, D.C., 1964.
- 22. Miller, J. F., "Two- to Ten-Day Rainfall for Return Periods of 2 to 100 Years in the Hawaiian Islands," Technical Paper No. 51, Weather Bureau, U.S. Department of Commerce, Washington, D.C., 1965.
- 23. Miller, J. F., "Two- to Ten-Day Precipitation for Return Periods of 2 to 100 Years in Alaska," Technical Paper No. 52, Weather Bureau, U.S. Department of Commerce, Washington, D.C., 1965.
- 24. Miller, J. F., et al., "Precipitation-Frequency Atlas of the Western U.S.," NOAA Atlas
  2, Volume I. Montana: Volume II. Wyoming: Volume III. Colorado: Volume IV.
   New Mexico; Volume V. Idaho: Volume VI. Utah: Volume VII. Nevada:
  Volume VIII. Arizona; Volume IX. Washington: Volume X. Oregon: Volume XI.
   California: Silver Spring, MD, 1973.
- Owen, D. B., "Factors for One-Sided Tolerance Limits and for Variables Sampling Plans," Monogram SCR-607, Sandia Corporation, available from NTIS, Springfield, VA 22151, March 1963.
- 26. Riggs, H. C., "Frequency Curves," Chapture A2 of Hydrologic Analysis and Interpretation, Techniques of Water-Resources Investigations, U.S. Geological Survey, GPO, Washington, D.C., 1968.
- 27. Riggs, H. C., "Some Statistical Tools in Hydrology," Chapter A1 of Hydrologic Analysis and Interpretations, Techniques of Water-Resources Investigations, GPO, Washington, D.C., 1968.

- 28. Riggs, H. C., "Low-Flow Investigations," Chapture B1 of Hydrologic Analysis and Interpretation, Techniques of Water-Resources Investigations, U.S. Geological Survey, GPO, Washington, D.C., 1972.
- 29. Riggs, H. C., "Regional Analysis of Streamflow Characteristics," Chapter B3 of Hydrologic Analysis and Interpretation, Techniques of Water Resources Investigations, U.S. Geological Survey, GPO, Washington, D.C., 1973.
- 30. Sauer, V. B., W. O. Thomas, Jr., V. A. Stricker and K. V. Wilson, "Flood Characteristics of Urban Watersheds in the United States," U.S. Geological Survey Water Supply Paper 2207, GPO, Washington, D.C., 1983.
- 31. Searcy, J. K., and C. H. Hardison, "Double-Mass Curves," U.S. Geological Survey Water-Supply Paper 1541-B, GPO, Washington, D.C., 1960.
- 32. Searcy J. K., "Flow-Duration Curves," U.S. Geological Survey, Water-Supply Paper 1541-A, GPO, Washington, D.C., 1960.
- 33. Sokolov, A. A., et al., <u>Flood Flow Computation</u>, <u>Methods Compiled from World Experience</u>, The UNESCO Press, Paris, France, 1976.
- 34. U.S. Army Corps of Engineers, "Stream Flow Volume-Duration-Frequency Studies," CW-152 Technical Report No. 1, Washington District, Washington, D.C., June 1955.
- 35. U.S. Army Corps of Engineers," Frequency of New England Floods," CW-151 Research Note No. 1, Sacramento District, Sacramento, CA, July 1958.
- 36. U.S. Army Corps of Engineers, "Probability Estimates Based on Small Normal-Distribution Samples," CW-151 Research Note No. 2, Sacramento District, Sacramento, CA, March 1959.
- 37. U.S. Army Corps of Engineers, "Frequency Curves from Incomplete Samples," CW-151 Research Note No. 3, Sacramento District, Sacramento, CA, September 1959.
- 38. U.S. Army Corps of Engineers, "Characteristics of Low Flow Volume-Duration-Frequency Statistics," CW-152 Technical Bulletin No. 1, Washington District, Washington, D.C., June 1960.
- 39. U. S. Army Corps of Engineers, "Hydrologic Data Management, "Volume 2 of Hydrologic Methods for Water Resources Development, the Hydrologic Engineering Center, Davis, CA, April 1972.
- 40. U.S. Army Corps of Engineers, "Regional Frequency Study, Upper Delaware and Hudson River Basins, New York District," Hydrologic Engineering Center, Davis, CA, November 1974.
- 41. U.S Army Corps of Engineers, "Hydrologic Frequency Analysis," Volume 3 of Hydrologic Methods for Water Resources Development, the Hydrologic Engineering Center, Davis, CA, April 1975.
- 42. U.S. Army Corps of Engineers, "Reservoir Yield," Volume 8 of Hydrologic Engineering Methods for Water Resources Development, the Hydrologic Engineering Center, Davis, CA, June 1977.

- 43. U.S. Army Corps of Engineers, "Generalized Skew for State of New Jersey," Special Project Memo 480, Hydrologic Engineering Center, Davis, CA, December 1977.
- 44. U.S. Army Corps of Engineers, "Hydrologic Analysis of Ungaged Watersheds with HEC-1," Hydrologic Engineering Center, Davis, CA, April 1982.
- 45. U.S. Army Corps of Engineers, Engineering Manual EM 1110-2-1413, "Hydrologic Analysis of Interior Areas," January 1987.
- 46. Water Resources Council, "Guidelines for Determining Flood Flow Frequency," Bulletin 17B, Hydrology Committee, Washington, D.C., March 1982.
- 47. Water Resources Council, "A Uniform Technique for Determining Flood Flow Frequencies," Bulletin 15, Hydrology Committee, Washington, D.C., December 1967.
- 48. World Meteorological Organization, "International Glossary of Hydrology," First Edition, WMO No. 385, Geneva, Switzerland, 1974.
- 49. World Meteorological Organization, "Guide to Hydrometeorological Practices," WMO No. 168, Third Edition, Geneva, Switzerland, 1974.

### B. COMPUTER PROGRAMS

- 50. U.S. Army Corps of Engineers, "Multiple Linear Regression," Computer Program 704-G1-L2020, Hydrologic Engineering Center, Davis, CA, September 1970.
- 51. U.S. Army Corps of Engineers, "HEC-4, Monthly Streamflow Simulation," Computer Program 723-X6-L2340, Hydrologic Engineering Center, Davis, CA, February 1971.
- 52. U.S. Army Corps of Engineers, "Regional Frequency Computation," Computer Program 723-X6-L2350, Hydrologic Engineering Center, Davis, CA, July 1972.
- 53. U.S. Army Corps of Engineers, "Flood Flow Frequency Analysis, "Computer Program 723-X6-L7550, Hydrologic Engineering Center, Davis, CA, February, 1982.
- 54. U.S. Army Corps of Engineers, "Expected Annual Flood Damage Computation," Computer Program 761-X6-L7580, Hydrologic Engineering Center, Davis, CA, June 1977.
- 55. U.S. Army Corps of Engineers, "HEC-5, Simulation of Flood Control and Conservation Systems." Computer program 723-X6-L2500, Hydrologic Engineering Center, Davis, CA, April 1982
- U.S. Army Corps of Engineers, "HEC-1, Flood Hydrograph Package," Computer Program 723-X6-L2010, Hydrologic Engineering Center, Davis, CA, September 1981.

- 57. U.S. Army Corps of Engineers, "Storage, Treatment, Overflow, Runoff Model 'STORM'," Computer Program 723-58-L7520, Hydrologic Engineering Center, Davis, CA, August 1977.
- 58. U.S. Army Corps of Engineers, "Statistical Analysis of Time Series Data 'STATS'," under development, Hydrologic Engineering Center, Davis, CA, May 1987.

# APPENDIX B

# GLOSSARY

These definitions have been collected from four major sources: (1) Guidelines for Determining Flood Flow Frequency (17B), reference 46; (2) International Glossary of Hydrology (WMO), reference 48; (3) General Introduction and Hydrologic Definitions (USGS), reference 18; and (4) Mathematics Dictionary (MD), reference 16.

# **TERM**

# **DEFINITION**

Analytical Frequency Analysis	A predefined method of estimating the parameters that define a selected theoretical frequency distribution.
Annual Event	The most extreme event, either maximum or minimum, in the year. (17B)
Annual Series	A general term for a set of any kind of data in which each item is the maximum or minimum in a year. (17B)
Атгау	A list of data in order of magnitude; in flood- frequency analysis it is customary to list the largest value first, in a low-frequency analysis, the smallest first. (17B)
Autocorrelation	See "Serial Correlation."
Base Discharge	Usually refers to the discharge above which independent instantaneous peak flows are collected for a partial duration frequency analysis.
Biased	The expected value of a statistic obtained from random sampling is not equal to the parameter or quantity being estimated. (MD)
Broken Record	A systematic record which is divided into separate continuous segments because of deliberate discontinuation of recording for significant periods of time. (17B)
Chi-Square Distribution	The distribution of sample variances drawn from a normal distribution. Used to compute confidence intervals for the population variance estimated from a sample.
Class Interval	A convenient sized interval into which data may be grouped. The upper and lower bounds of the class interval are called "class limits." (MD)

Climatic Year A continuous 12-month period during which a complete annual

> cycle occurs, arbitrarily selected for the presentation of data relative to hydrologic or meteorologic phenomena. The climatic year is usually designated by the calendar year during which most

of the 12 months occur. See "Water Year." (USGS)

Coefficient of Skewness

A numerical measure or index of the lack of symmetry in a frequency distribution. Function of the third moment of magnitudes about their mean, a measure of asymetry. Also called

"coefficient of skew" or "skew coefficient." (17B)

Coefficient of Variation

Statistical parameter describing the change of a stochastic variable in time or space, expressed as the ratio of the standard deviation

to the mean. (WMO)

Confidence Limits Computed values on both sides of an estimate of a parameter that

show for a specified probability the range in which the true value

of the parameter lies. (17B)

Correlation The interdependence between two sets of numbers. (MD)

Covariance The first product moment of two variates normalized by their

respective mean values. (WMO)

Curve

Cumulative Frequency Relation of event magnitude to percentage of events exceeding (or

not exceeding) that magnitude.

Deviation The difference between the magnitude of an event and the mean

of all the events in the sample.

Depth-Duration-

Frequency

Curve showing the frequency relationship of precipitation depth

for a given storm duration.

Function describing the relative frequency with which events of Distribution

various magnitudes occur. (17B)

Double Mass Curve Plot of successive accumulated values of one variable against the

contemporaneous accumulated values of another variable. (WMO)

Drought A period of abnormally dry weather sufficiently prolonged for

the lack of precipitation to cause a serious hydrological imbalance.

(WMO)

**Duration Curve** A cumulative frequency curve that shows the percent of time that

specific values are equalled or exceeded. (USGS)

Error Variance Square of the standard error.

Exceedance Frequency See "Percent chance exceedance."

Exceedance Interval See "Recurrence interval." Exceedance Probability Probability that a random event will exceed a specified magnitude

in a given time period, usually one year unless otherwise

indicated. (17B)

**Expected Probability** 

The average of the true probabilities of all magnitude estimates for any specified flood frequency that might be made from

successive samples of a specified size. (17B)

F Distribution

The random sampling distribution of the ratio of two independent estimates of the variance of a normal distribution. (MD)

Flow-Duration Curve

See "Duration Curve."

Frequency

The number of events in a sample (or the population) that meet specified criteria.

Frequency Analysis

Procedure involved in interpreting a record of events in terms of future probabilities of occurrence. (WMO)

Frequency Curve

A graphical representation of a frequency distribution. Usually a cumulative frequency curve with the abscissa a probability grid and the ordinate the event magnitude.

Generalized Skew

A skew coefficient derived by a procedure which integrates values obtained at many locations. (17B)

Geometric Mean

The Nth root of the product of N values or the antilogarithm of the mean logarithm of a set of values.

Graphical Frequency

**Analysis** 

The development of a frequency curve by drawing a smooth curve through plotted points while considering known constraints. Plotting positions are computed based on the order number and the total number of values represented, and then plotted on the appropriate probability paper.

Histogram

Univariate frequency diagram with rectangles proportional in area to the class frequency, erected on a horizontal axis with width equal to the class interval. (WMO)

Historic Data

Information about significant events before or after the period of "systematic" data collection. (derived from 17B)

Homogeneity

Records (samples) from the same population. (17B)

Incomplete Record

A streamflow record in which some peak flows are missing because they were too low or high to record or the gage was out of operation for a short period because of flooding. (17B)

Level of Significance

The probability of rejecting a hypothesis when it is in fact true, At a "10-percent" level of significance the probability is 1/10.

(17B)

Log-Pearson Type III
Distribution

Application of the Pearson Type III distribution to the logarithms

of the data.

Mass Curve Curve of an accumulative quantity versus time. (WMO)

Mean The expected value of a random variable, the first moment. The

arithmic mean (or average) of a sample is an estimate of the

population mean.

Mean Daily The mean of daily values in a specified period, or the mean of

values within one day. (derived from WMO)

Median The value at which one-half of ordered observations lie on either

side. If there is no middle value, the median is the average of the

two middle values.

Method of Moments A standard statistical computation for estimating the moment of a

distribution from the data of a sample. (17B)

Mixed Populations A sample whose events have come from two or more different

populations, i.e., data not homogenous.

Mode The most frequent value of a set of numbers. (MD)

Non-Central t Distribution A distribution that combines the probable error in the mean and the standard deviation for samples from a normal distribution. Used in the development of confidence limit curves about a

frequency curve computed from sample statistics.

Nonstationary Not stationary with respect to time. See "Stationary Process."

Normal Distribution A probability distribution that is symmetrical about the mean,

median, and mode (bell shaped). It is the most studied

distribution in statistics, even though most data are not exactly normally distributed, because of its value in theoretical work and because many other distributions can be transformed into the normal. It is also known as Gaussian, the Laplacean, the

Gauss-Laplace, or the Laplace-Gauss distribution, or the Second

Law of Laplace. (17B)

Outlier Outliers (extreme events) are data points which depart from the

trend of the rest of the data. (17B)

Parameter A characteristic descriptor of the population, such as mean or

standard deviation. Parameter estimates are called statistics.

Parent Population See "Population".

Partial-Duration Series A list of flood peaks that exceed a chosen base stage or discharge,

regardless of the number of peaks occurring in a year. (USGS)

Pearson Type III Distribution

Family of asymmetrical, theoretical frequency distributions of which the normal distribution is a special case.

Percent Chance Exceedance

The probability, expressed as a percentage, with which values exceed a specified magnitude.

Percent Chance Non-Exceedance The probability, expressed as a percentage, with which values will not exceed a specified magnitude.

Plotting Position

Percent chance of exceedance (or non-exceedance) of an observed value estimated from its position in the array.

Population

The entire (usually infinite in hydrologic application) number of data from which a sample is taken or collected. For example, total number of past, present, and future floods at a location on a river is the population of floods for that location even if the floods are not measured or recorded. (17B)

Probability

The ratio of the number of random events with some particular size or other attribute to the total number of equally likely events.

Random

Any event in the population has an equal chance of being selected.

Recurrence Interval

The average time interval between actual occurrences of a hydrological event of a given or greater magnitude. In an annual flood series, the average interval in which a flood of a given size is exceeded as an annual maximum. In a partial duration series, the average interval between floods of a given size, regardless of their relationship to the year or any other period of time. The distinction holds even though for large floods, recurrence intervals are nearly the same for both series. (17B)

Regional Analysis

Extension of the results of the frequency analysis of point data to an area. (WMO)

Regression

An analytical procedure that derives estimation or prediction equations for a variable (dependent) based on given values of one or more other variables (independent). Commonly, the principle of minimum squared error (least squares) is used in the derivation.

Return Period

See "Recurrence Interval."

Risk

The probability of a potential outcome (success) being realized within a specified number of events (trials). In a hydrologic context, the probability that one or more events will exceed a given annual event, that has an assumed "true" percent chance exceedance, during a specified number of years. Risk is computed by the binomial distribution. (For contrast, see uncertainty.)

Sample

An element, part, or fragment of a "population." Every hydrologic record is a sample of a much longer record. (17B) EM 1110-2-1415 5 Mar 93

Distribution

Sampling Error The difference between a random sampling statistic and the

parameter of the population from which the random sample was

drawn. (MD)

Serial Correlation A measure of the interdependence between an observation at a

given time period and that of a preceeding time period. Also

called autocorrelation.

Skew Coefficient See "Coefficient of Skewness."

Stage The height of a water surface above an established datum plane.

(USGS)

Standard Deviation A measure of the dispersion or precision of a series of statistical

values such as precipitation or stream flow. It is the square root of the sum of squares of the deviations from the arithmetic mean divided by the number of values or events in the series. It is now standard practice in statistics to divide by the number of values minus one in order to get an unbiased estimate of the variance

from the sample data. (17B)

Standard Error Standard deviation of the sampling distribution of a statistical

parameter. (WMO)

Stationary Process All of the generating moments of the frequency distribution

remain fixed with respect to time.

Statistic An estimate of a population parameter obtained from a sample of

the population.

Stochastic Process Process in which both the probability and the sequence of

occurrence of the variables are taken into account. (WMO)

Student's t- A distribution used in evaluation of variables which involve

sample standard deviation rather than population standard deviation. (17B)

Systematic Record Information collected by a systematic data collection program.

(derived from 17B)

t-Distribution See "Student's t-Distribution."

Test of Significance A test mode to learn the probability that a result is accidental or

that a result differs from another result. For all the many types

of tests, there are standard formulae and tables. (17B)

Transformation The change of numerical values of data to make later

computations easier, to linearize a plot or to normalize a skewed distribution by making it more nearly a normal distribution. The

most common transformations are those changing ordinary

numerical values into their logarithms, square roots or cube roots;

many others are possible. (17B)

Trend A statistical term referring to the direction or rate of increase or

decrease in magnitude of the individual members of a time series of data when random fluctuations of individual members are

disregarded. (USGS)

Unbiased The expected value of a statistic obtained from random sampling

is equal to the parameter or quantity being estimated. (MD)

Uncertainty The inherent error in an analysis caused by not knowing either

the true model or the model parameters. In frequency analysis, model uncertainty comes from assuming a theoretical frequency distribution and parameter uncertainty comes from estimating the

parameters for the selected distribution by sample statistics.

Variance A measure of the amount of spread or dispersion of a set of

values around their mean, obtained by calculating the mean value of the squares of the deviations from the mean, and hence equal

to the square of the standard deviation. (17B)

Watershed The divide separating one drainage basin from another and in the

past has been generally used to convey this meaning. However, over the years, use of the term to signify drainage basin or catchment area has come to predominate, although drainage basin

is preferred. (USGS)

Water Year Continuous twelve-month period selected in such a way that all

solid and liquid precipitation runs off during this period. Thus, carryover is reduced to a minimum. (WMO) In U.S. Geological Survey reports, it is the twelve-month period. October 1 through September 30. The water year is designated by the calendar year

within which most of the twelve-months occur. (USGS)

#### APPENDIX C

## COMPUTATION PROCEDURE FOR EXTREME VALUE (GUMBEL) DISTRIBUTION

(Reproduced from reference 48.)

#### 5.2.6.1.2 Computational methods

It can be shown that most frequency functions applicable to hydrological analysis can take the form

$$X_{T_r} = \overline{X} + Ks_x \tag{5.1}$$

where  $\overline{X}$  is the mean value, and  $s_x$  is the standard deviation of the variable being studied. Value  $X_{T_r}$  denotes the magnitude of the event reached or exceeded on an average once in  $T_r$  years. K is the frequency factor. If X is not normally distributed, K depends on frequency and skewness coefficient. A commonly used distribution of extreme values (annual series) is the double exponential distribution, which has been widely applied by Gumbel (see Bibliography), and often bears his name. In this method

$$K = \frac{Y_{T_r} - \overline{Y}_n}{s_n} \tag{5.2}$$

where  $\overline{Y}_n$ , the reduced mean, and  $s_n$ , the reduced standard deviation, are functions only of sample size; and  $Y_{T_n}$ , the reduced variate, is related to return period by

$$Y_{T_r} = -\left(0.83405 + 2.30259 \log \log \frac{T_r}{T_r - 1}\right)$$
 (5.3)

Table 5.3 gives values of K computed by means of Eq. (5.2) using Gumbel's values for  $\overline{Y}_n$ ,  $s_n$ , and  $Y_{T_p}$ .

There are two basic methods for fitting data to the extreme value distribution. One consists in computation of  $X_{T_r}$  by means of Eq. (5.1), after a previous computation of the values of  $\overline{X}$  and  $s_x$  (Table 5.4). The other consists in plotting data on suitable graph paper, known as extreme probability paper, and drawing a line by inspection.

TABLE 5.3

Values of K based on Eq. (5.2)

Return period (years)								
n	2	5	10	25	50	100		
10	0.1355	1.0580	1.8483	2.8467	3.5874	4.3227		
11	<b></b> 0. <b>137</b> 6	1.0338	1.8094	2.7894	3.5163	4.2379		
12	0.1393	1.0134	1.7766	2.7409	3.4563	4.1664		
13	-0.1408	.9958	1.7484	2.6993	3.4048	4.1050		
14	-0.1422	.9806	1.7240	2.6632	3.3600	4.0517		
15	-0.1434	.9672	1.7025	2.6316	3.3208	4.0049		
16	-0.1444	.9553	1.6835	2.6035	3.2860	3.9635		
17	<b>—</b> 0. <b>1454</b>	.9447	1.6665	2.5784	3.2549	3.9265		
18	<b>0.1463</b>	.9352	1.6512	2.5559	3.2270	3.8932		
19	0.1470	.9265	1.6373	2.5354	3.2017	3.8631		
20	<b>—</b> 0. <b>147</b> 8	.9187	1.6247	2.5169	3.1787	3.8356		
21	<b>0.1484</b>	.9115	1.6132	2.4999	3.1576	3.8106		
22	0.1490	.9049	1.6026	2.4843	3.1383	3.7875		
23	<b>0.1496</b>	.8988	1.5929	2.4699	3.1205	3.7663		
24	<b>—</b> 0. <b>1501</b>	.8931	1.5838	2.4565	3.1040	3.7466		
25	-0.1506	.8879	1.5754	2.4442	3.0886	3.7283		
26	0.1510	.8830	1.5676	2.4326	3.0743	3.7113		
27	<b>—</b> 0. <b>151</b> 5	.8784	1.5603	2.4219	3.0610	3.6954		
28	<b>0.1518</b>	.8742	1.5535	2.4118	3.0485	3.6805		
29	0.1522	.8701	1.5470	2.4023	3.0368	3.6665		

(continued)

# 5.22

HYDROLOGICAL ANALYSIS

TABLE 5.3 (continued)

# Return period (years)

		1161	urn perioa (	yeurs)		
n	2	5	10	25	50	100
30	0.1526	.8664	1.5410	2.3934	3.0257	3.6534
31	-0.1529	.8628	1.5353	2.3850	3.0153	3.6410
32	-0.1532	.8594	1.5299	2.3770	3.0054	3.6292
33	<b></b> 0. <b>153</b> 5	.8562	1.5248	2.3695	2.9961	3.618 <b>1</b>
34	-0.1538	.8532	1.5199	2.3623	2.9873	3.6076
35	0.1540	.8504	1.5153	2.3556	2.9789	3.5976
36	-0.1543	.8476	1.5110	2.3491	2.9709	3.5881
37	0.1545	.8450	1.5068	2.3430	2.9633	3.5790
38	0.1548	.8425	1.5028	2.3371	2.9561	3.5704
39	-0.1550	.8402	1.4990	2.3315	2.9491	3.5622
40	-0.1552	.8379	1.4954	2.3262	2.9425	3.5543
41	-0.1554	.8357	1.4920	2.3211	2.9362	3.5467
42	0.1556	.8337	1.4886	2.3162	2.9301	3.5395
43	<b></b> 0. <b>1557</b>	.8317	1.4854	2.3115	2.9243	3.5325
44	0.1559	.8298	1.4824	2.3069	2.9187	3.5259
45	0.1561	.8279	1.4794	2.3026	2.9133	3.5194
46	0.1562	.8262	1.4766	2.2984	2.9081	3.5133
47	0.1564	.8245	1.4739	2.2944	2.9031	3.5073
48	-0.1566	.8228	1.4712	2.2905	2.8983	3.5016
49	<b>-</b> -0.1567	.8212	1.4687	2.2868	2.8937	3.4961
50	0.1568	.8197	1.4663	2.2832	2.8892	3.4908
51	-0.1570	.8182	1.4639	2.2797	2.8849	3.4856
52	-0.1571	.8168	1.4616	2.2763	2.8807	3.4807
53	<b>—</b> 0.1572	.8154	1.4594	2.2731	2.8767	3.4759
54	<b>—</b> 0.1573	.8141	1.4573	2.2699	2.8728	3.4712
	0.4555	0400	4 /550	0.000	0.000	2.400
<b>5</b> 5	0.1575	.8128	1.4552	2.2669	2.8690	3.4667
56	0.1576	.8116	1.4532	2.2639	2.8653	3.4623
57	-0.1577	.8103	1.4512	2.2610	2.8618	3.4581
58	-0.1578	.8092	1.4494	2.2583	2.8583	3.4540
59	<b>—</b> 0.1579	.8080	1.4475	2.2556	2.8550	3.4500
60	0.1580	.8069	1.4458	2.2529	2.8518	3.4461
61	0.1580 0.1581	.8058	1.4456 1.4440	2.2529	2.8486	3.4424
62	-0.1581 -0.1582	.8048	1.4424	2.2304	2.8455	3.4387
63	-0.1582 -0.1583	.8038	1.4407	2.2475	2.8426	3.4352
64	0.1583	.8028	1.4391	2.2433	2.8397	3.4317
04	0.1303	.0020	1.4031	4.4404	2.0031	0.4317

HYDROLOGICAL ANALYSIS	5.23

TABLE 5.3 (continued)

# Return period (years)

	Return perion (years)								
n	2	5	10	25	50	100			
65	0.1584	.8018	1.4376	2.2409	2.8368	3.4284			
66	<b>-0.1585</b>	.8009	1.4361	2.2387	2.8341	3.4251			
67	-0.1586	.8000	1.4346	2.2365	2.8314	3.4219			
68	-0.1587	.7991	1.4332	2.2344	2.8288	3.4188			
69	0.1587 0.1587	.7982	1.4318	2.2324	2.8263	3.4158			
03	-0.1367	.1302	1.4010	2.2021	2.0200	0.1200			
70	0.1588	.7974	1.4305	2.2304	2.8238	3.4128			
71	0.1589	.7965	1.4291	2.2284	2.8214	3.4099			
72	0.1590	.7957	1.4278	2.2265	2.8190	3.4071			
<b>7</b> 3	0.1590	.7950	1 4266	2.2246	2.8167	3.4044			
74	-0.1591	.7942	1.4254	2.2228	2.8144	3.4017			
75	0.1592	.7934	1.4242	2.2211	2.8122	3.3991			
76	0.1592	.7927	1.4230	2.2193	2.8101	3.3965			
77	0.1593	.7920	1.4218	2.2176	2.8080	3.3940			
<b>78</b>	<b>—</b> 0. <b>1593</b>	.7913	1.4207	2.2160	2.8059	3.3916			
79	-0.1594	.7906	1.4196	2.2143	2.8039	3.3892			
80	0.1595	.7899	1.4185	2.2128	2.8020	3.3868			
81	0.1595	.7893	1.4175	2.2112	2.8000	3.3845			
82	0.1596	.7886	1.4165	2.2097	2.7982	3.3823			
83	0.1596	.7880	1.4154	2.2082	2.7963	3.3801			
84	0.1597	.7874	1.4145	2.2067	2.7945	3.3779			
85	0.1597	.7868	1.4135	2.2053	2.7927	3.3758			
86	0.1598	.7862	1.4125	2.2039	2.7910	3.3738			
87	-0.1598	.7856	1.4116	2.2026	2.7893	3.3717			
88	-0.1599	.7851	1.4107	2.2012	2.7877	3.3698			
89	0.1599	.7845	1.4098	2.1999	2.7860	3.3678			
90	0.1600	.7840	1.4089	2.1986	2.7844	3.3659			
91	0.1600	.7834	1.4081	2.1973	2.7828	3.3640			
92	-0.1601	.7829	1.4072	2.1961	2.7813	3.3622			
93	0.1601	.7824	1.4064	2.1949	2.7798	3.3604			
94	-0.1602	.7819	1.4056	2.1937	<b>2.778</b> 3	3.3586			
05	0.4000	5047	4 (0/0	0.4005	2.7769	3.3569			
95	0.1602	.7814	1.4048	2.1925		3.3552			
96	0.1602	.7809	1.4040	2.1913	2.7754	3.3532 3.3535			
97	<b>0.1603</b>	.7804	1.4033	2.1902	2.7740				
98	-0.1603	.7800	1.4025	2.1891	2.7726	3.3519			
99	0.1604	.7795	1.4018	2.1880	2.7713	3.3503			
100	-0.1604	.7791	1.4010	2.1869	2.7700	3.3487			
200	V.2001								

#### 5.24

#### HYDROLOGICAL ANALYSIS

Extreme probability paper has a linear ordinate for the variable being studied, and the abscissa is a linear scale of the reduced variate [Eq. (5.3)]. For convenience in plotting, the warped scale of T<sub>r</sub> is also shown along the top of Fig. 5.9. Plotting positions are commonly determined by the formulae [16]:

$$T_r = \frac{n+1}{m} \tag{5.4}$$

or

$$T_{\rm r} = \frac{n + 0.4}{m - 0.3} \tag{5.5}$$

where n is the number of years of record (the number of items in the annual series) and m is the rank of the item on the series, m being 1 for the largest.

To illustrate the steps in numerical computation of the rainfall value for a given return period, hypothetical values of a series of annual rainfall maxima are given in the upper part of Table 5.4. Computations are illustrated in the lower part of the table for T<sub>r</sub> of 10. Rainfall depths for return periods other than 10 years can be computed in a similar manner.




Figure 5.9 - Example of extreme probability plot using data of Table 5.4.

Table 5.4

Computation of extreme values

Year	P	m	$\frac{n+1}{m}$	$P - \overline{P}$	$(P - \overline{P})^2$	P <sup>2</sup>
<b>19</b> 60	37	7	1.72	<b>— 9</b>	81	1,369
1961	20	11	1.09	<b>— 26</b>	676	400
1962	32	8	1.5	14	196	1,024
1963	60	3	4.0	+ 14	196	3,600
1964	<b>2</b> 5	9	1.33	<u> </u>	441	625
1965	52	4	3.0	+ 6	36	2,704
1966	46	6	2.0	0	0	2,116
1967	70	2	6.0	+ 24	576	4,900
1968	92	1	12.0	+ 46	2,116	8,464
1969	48	5	2.4	+2	4	2,304
1970	24	10	1.2	<del> 22</del>	484	576
Total	506				4,806	28,082

$$\bar{P} = \hat{\Sigma} P/n = \frac{506}{11} = 46.0$$

$$s_x$$
 by square of deviations: 
$$\sqrt{\frac{\sum_{n=1}^{\infty} (P)^2 - \overline{P} \sum_{n=1}^{\infty} P}{n-1}} = \sqrt{\frac{4806}{10}} = 21.92$$

s<sub>x</sub> by short cut: 
$$\sqrt{\frac{\sum\limits_{1}^{n}(P)^{2}-\overline{P}\sum\limits_{1}^{n}P}{n-1}}=\sqrt{\frac{4806}{10}}=21.92$$

For 
$$T_r = 2$$
 and  $n = 11$ ,  $K = -0.1376$  (from Table 5.3).

Substituting into Eq. (5.1):

$$P_{\bullet} = 46.0 - 0.1376 \times 21.92 = 43.0$$

Similarly, for 
$$T_r = 10$$
,  $K = 1.8094$ , and

$$P_{10} = 46.0 + 1.8094 \times 21.92 = 85.7$$

In Fig. 5.9 the two + 's show the above values for  $P_2$  and  $P_{10}$  and define the line shown.

To illustrate the graphical method of fitting data to the extreme-value distribution, reference is again made to Table 5.4 and Fig. 5.9. In the table, values of the plotting position are given, and in Fig. 5.9 the plotted points are given, with rainfall values for each plotting position. The curve shown could have been drawn by fitting the plotted points by inspection.

In this example, for convenience, a record of only 11 years is used. Such a record gives a fairly stable value for return periods of as much as five years, but for longer return periods the short record has a large sampling error and the computations should not be taken as precise estimates.

For some types of data, instead of using the extreme-value distribution, a better fit of the data, or a closer approach to linearity, may be obtained from one of several other types of distribution, such as the normal or lognormal Pearson Type III distribution. A commonly used distribution is one in which the magnitude scale is logarithmic and the probability or return-period scale is the normal distribution. This distribution and the plotting paper used with it are widely known as log-normal. For discussion of additional distributions and of additional methods for fitting distributions, reference may be made to textbooks, and periodical statistical literature [17, 18, 63-66].

An advantage of fitting data to a distribution is achievement of objectivity. This advantage has the corollary of standard treatment of data, so that a decision is based on differences in data rather than differences in subjective interpretation of data. A third advantage of linearity in plotting points, and of close fit to a particular distribution, is the facility for extrapolating beyond the range of the data. However, it should be remembered that extrapolation involves considerable sampling error.

For evaluation of the accuracy of the computed values  $X_{T_r}$  it would be desirable to compute the confidence interval with limits:

$$X_{T_r}$$
—  $t(\alpha) s_e$ ;  $X_{T_r} + t(\alpha) s_e$ 

within which, with given confidence levels, one may expect to find the true precipitation value  $X_{T_r}$ . Values of  $t(\alpha)$  for selected confidence levels are as follows:

$\alpha = 95 \%$	$t(\alpha) = 1.960$
$\alpha = 90 \%$	$t(\alpha) = 1.645$
$\alpha = 80 \%$	$t(\alpha) = 1.282$
$\alpha = 68 \%$	$t(\alpha) = 1.000$

In most cases, values of se, the standard error of estimate, can be computed by means of the formula

$$s_e = \beta_{T_p} \cdot \frac{s_x}{\sqrt{n}} \tag{5.6}$$

In particular, for the Gumbel distribution the following relation [19] exists:

$$\beta_{\rm T_r} = \sqrt{1 + 1.14 \, \text{K} + 1.10 \, \text{K}^2} \tag{5.7}$$

where K is the numerical value defined by Eq. (5.2) and readily obtainable from Table 5.3. However, for convenience in the use of Eq. (5.6) values of  $\beta_{T_r}/\sqrt{n}$  can be obtained directly from Table 5.5. Thus, in determining the 80 per cent confidence interval for  $P_{10} = 85.7$  in Table 5.4, for example,

$$t(a)s_e = 1.282 \times 0.7783 \times 21.92 = 21.9$$

The lower and upper limits of the confidence interval are therefore 85.7-21.9 and 85.7+21.9, respectively, which means that there is an 80 per cent probability that the true value of  $P_{10}$  lies between 63.8 and 107.6. Similarly, the lower and upper limits of the same confidence interval for  $P_2=43.0$  are 35.1 and 50.9, respectively, the value of  $\beta_{T_r}/\sqrt{n}$  being 0.2803 (Table 5.5).

Table 5.5

Values of  $\beta_{T_r}/\sqrt{n}$  for use in Eq. (5.6)

Return period (years)

	Return period (years)								
n	2	5	10	25	50	100			
10	.2942	.5863	.8285	1.1472	1.3873	1.6273			
11	.2803	.5522	.7783	1.0761	1.3007	1.5252			
12	.2681	.5232	.7358	1.0161	1.2275	1.4389			
13	.2574	.4982	.6992	.9645	1.1646	1.3648			
14	.2479	.4763	.6673	.9196	1.1100	1.3005			
15	.2393	.4569	.6392	.8801	1.0620	1.2439			
16	.2316	.4397	.6142	.8450	1.0193	1.1937			
17	.2246	.4242	.5918	.8136	.9811	1.1488			
18	.2182	.4102	.5716	.7853	.9467	1.1083			
19	.2123	.3974	.5532	.7596	.9155	1.0716			
20	.2068	.3857	.5365	.7361	.8871	1.0382			
21	.2018	.3750	.5211	.7146	.8610	1.0075			
22	.1971	.3651	.5069	.6948	.8370	.9793			
23	.1927	.3559	.4937	.6765	.8148	.9532			
24	.1886	.3473	.4815	.6595	.7942	.9290			
25	.1847	.3394	.4702	.6437	.7750	.9064			
26	.1811	.3319	.4595	.6289	.7571	.8854			
27	.1777	.3249	.4496	.6150	.7403	.8657			
28	.1745	.3183	.4402	.6020	.7245	.8472			
29	.1714	.3121	.4314	.5898	.7097	.8298			
30	.1685	.3062	.4230	.5782	.6957	.8134			
31	.1657	.3007	.4152	.5673	.6825	.7978			
32	.1631	.2954	.4077	.5569	.6699	.7831			
33	.1606	.2904	.4006	.5471	.6581	.7692			
34	.1582	.2856	.3938	.5377	.6468	.7559			
35	.1559	.2811	.3874	.5289	.6360	.7433			
36	.1537	.2767	.3813	.5204	.6257	.7313			
37	.1516	.2726	.3754	.5123	.6159	.7198			
38	.1496	.2686	.3698	.5045	.6066	.7088			
39	.1476	.2648	.3645	.4971	.5976	.6983			

(continued)

# 5.28

#### HYDROLOGICAL ANALYSIS

TABLE 5.5 (continued)

# Return period (years)

		Reli	urn period (y	iears j		
n	2	5	10	25	50	100
40	.1457	.2611	.3593	.4900	.5890	.6883
41	.1439	.2576	.3544	.4832	.5808	.6786
42	.1422	.2542	.3496	.4766	.5729	.6693
43	.1405	.2510	.3451	.4703	.5653	.6604
44	.1389	.2479	.3407	.4643	.5580	.6518
45	.1373	.2449	.3365	.4584	.5509	.6 <b>43</b> 6
45 46	.1373	.2419	.3324	.4528	.5441	.6356
47	.1344	.2391	.3284	.4326	.5375	.6279
47	.1344	.2364	.3246	.4474	.5312	.6205
					.5251	
49	.1316	.2338	.3209	.4370	.5251	.6133
50	.1303	.2312	.3174	.4321	.5192	.6064
51	.1290	.2288	.3139	.4274	.5134	.5996
52	.1277	.2264	.3106	.4228	.5079	.5931
53	.1265	.2241	.3073	.4183	.5025	.5868
54	.1253	.2218	.3042	.4140	.4973	.5807
55	.1242	.2196	.3012	.4098	.4922	.5748
<b>5</b> 6	.1230	.2175	.2982	.4057	.4873	.5690
57	.1219	.2155	.2953	.4018	.4825	.5635
58	.1209	.2135	.2925	.3979	.4779	.5580
59	.1198	.2115	.2898	.3942	.4734	.5527
60	.1188	.2096	.2872	.3905	.4690	.5476
61	.1179	.2078	.2846	.3870	.4647	.5426
62	.1179	.2078	.2821	.3836	.4647	.5377
63	.1160	.2042	.2796	.3802	.4565	.5330
64	.1150	.2025	.2772	.3769	.4525	.5284
65	.1142	.2008	.2749	.3737	.4487	.5239
66	.1133	.1992	.2726	.3706	.4449	.5195
67	.1124	.1976	.2704	.3676	.4413	.5152
68	.1116	.1960	.2683	.3646	.4377	.5110
69	.1108	.1945	.2661	.3617	.4342	.5069
70	.1100	.1930	.2641	.3589	.4208	.5029
71	.1092	.1916	.2621	.3561	.4274	.4990
$\frac{72}{72}$	.1084	.1902	.2601	.3534	.4242	.4952
73	.1077	.1888	.2582	.3507	.4210	.4914
74	.1070	.1874	.2563	.3481	.4179	.4878
		12017	.=000	.0401	.4110	. 4010

	HYDROLOGICAL ANALYSIS									
		Тав	LE 5.5 (cont	inued)						
Return period (years)										
n	2	5	i o	25	50	100				
75	.4062	.1861	.2544	.3456	.4148	.4842				
76	.1055	.1848	.2526	.3431	.4118	.4807				
77	.1048	.1835	.2508	.3407	.4089	.4773				
78	.1042	.1823	.2491	.3383	.4060	.4739				
79	.1035	.1810	.2474	.3360	.4032	.4706				
80	.1028	.1798	.2457	.3337	.4005	.4674				
81	.1022	.1786	.2441	.3315	.3978	.4643				
82	.1016	.1775	.2425	.3293	.3951	.4612				
83	.1010	.1764	.2409	.3271	.3925	.4581				
84	.1004	.1752	.2394	.3250	.3900	.4552				
85	.0998	.1742	.2379	.3229	.3875	.4522				
86	.0992	.1731	.2364	.3209	.3850	.4494				
87	.0986	.1720	.2349	.3189	.3826	.4466				
88	.0980	.1710	.2335	.3169	.3803	.4438				
89	.0975	.1700	.2321	.3150	.3780	.4411				
90	.0969	.1690	.2307	.3131	.3757	4384				
91	.0964	.1680	.2293	.3113	.3734	.4358				
92	.0959	.1670	.2280	.3094	.3712	.4332				
93	.0954	.1661	.2267	.3076	.3691	.4307				
94	.0948	.1652	.2254	.3059	.3670	.4282				
95	.0943	.1642	.2241	.3041	.3649	.4258				
96	.0939	.1633	.2229	.3024	.3628	.4234				
97	.0934	.1624	.2217	.3007	.3608	.4210				
98	.0929	.1616	.2204	.2991	.3588	.4187				
99	.0924	.1607	.2193	.2975	.3569	.4164				
100	.0919	.1599	.2181	.2959	.3549	.4142				

An example of the magnitude of error in extrapolation beyond the range of the data may be found in the record of maximum annual 24-hour rainfall at Hartford, Connecticut, U.S.A. Based on the 50 years of record through 1954, the 100-year value was found to be 155 mm. The maximum event during this period was 170 mm. In 1955 a hurricane produced 307 mm in 24 hours. The computation of 100-year 24-hour rainfall based on the 51 years of record through 1955 resulted in a new estimate of 218 mm, a 40 per cent increase. Even the 10-year value was increased substantially by this one event.

#### 5.30 HYDROLOGICAL ANALYSIS

It may happen, however, that during a definite period of  $T_r$  years, precipitation of the magnitude  $P \ge P_{T_r}$  does not occur at all, or that it occurs several times. The probability that, during a given period of t years, a respective phenomenon will occur n times, is equal to

$$Pr_{n/t} = \left(\frac{t!}{n!(t-n)!}\right) p^{n} (1-p)^{t-n}$$
 (5.8)

where  $p=1/T_r$ . Assuming, for example, that  $t=T_r=100$  years, then the probabilities for various values of n are:

n	0	1	2	3	4	5
$Pr_{n/100}$	0.366	0.370	0.185	0.061	0.015	0.003

The overall probability of  $P_{\mathrm{T_r}}$  or greater event occurring in t years is discussed in Sec. A.5.7.3.

#### APPENDIX D

#### HISTORIC DATA<sup>1</sup>

Flood information outside that in the systematic record can often be used to extend the record of the largest events to a historic period much longer than that of the systematic record. In such a situation, the following analytical techniques are used to compute a historically adjusted log-Pearson Type III frequency curve.

- 1. Historic knowledge is used to define the historically longer period of "H" years. The number "Z" of events that are known to be the largest in the historically longer period "H" are given a weight of 1.0. The remaining "N" events from the systematic record are given a weight of (H-Z)/(N+L) on the assumption that their distribution is representative of the (H-Z) remaining years of the historically longer period.
- 2. The computations can be done directly by applying the weights to each individual year's data using equations 6-1, 6-2a, 6-3a, and 6-4a. Figure 6-1 is an example of this procedure in which there are 44 years of systematic record and the 1897, 1919 and 1927 floods are known to be the three largest floods in the 77 year period 1897 to 1973. If statistics have been previously computed for the current continuous record, they can be adjusted to give the equivalent historically adjusted values using equations 6-1, 6-2b, 6-3b, and 6-4b, as illustrated in Figure 6-2.
- 3. The historically adjusted frequency curve is sketched on logarithmic-probability paper through points established by use of equation 6-5. The individual flood events should also be plotted for comparison. The historically adjusted plotting positions for the individual flood events are computed by use of equation 6-8, in which the historically adjusted order number of each event "m" is computed from equations 6-6 and 6-7. The computations are illustrated in Figures 6-1 and 6-2, and the completed plotting is shown in Figure 6-3.
- 4. The following example illustrates the steps in application of the historic peak adjustment only. It does not include the final step of weighting with the generalized skew. The historically adjusted skew developed by this procedure is appropriate to use in developing a generalized skew.

<sup>1</sup> Reproduction of Appendix 6 of Bulletin 17B.

#### DEFINITION OF SYMBOLS

- E = event number when events are ranked in order from greatest magnitude to smallest magnitude. The event numbers "E" will range from 1 to (Z + N).
- X = logarithmic magnitude of systematic peaks excluding zero flood events, peaks below base, high or low outliers
- X<sub>z</sub> = logarithmic magnitude of a historic peak including a high outlier
  that has historic information
- N = number of X's
- M = mean of X's
- m = historically adjusted mean
- = historically adjusted order number of each event for use in formulas to compute the plotting position on probability paper
- S = standard deviation of the X's
- = historically adjusted standard deviation
- G = skew coefficient of the X's
- F = historically adjusted skew coefficient
- K = Pearson Type III coordinate expressed in number of standard deviations from the mean for a specified recurrence interval or percent chance
- Q = computed flood flow for a selected recurrence interval or percent chance
- PP = plotting position in percent
- P = probability that any peak will exceed the truncation level (used in step 1, Appendix 5)
- Z = number of historic peaks including high outliers that have historic information
- H = number of years in historic period
- = number of low values to be excluded, such as: number of zeros, number of incomplete record years (below measurable base), and low outliers which have been identified
- a = constant that is characteristic of a given plotting position formula. For Weibull formula, a = 0; for Beard formula, a = 0.3; and for Hazen formula, a = 0.5
- W = systematic record weight

#### **EQUATIONS**

$$W = \frac{H - Z}{N + L} \tag{6-1}$$

$$\widetilde{M} = \frac{W \Sigma X + \Sigma X_{Z}}{H - WL}$$
 (6-2a)

$$\widetilde{M} = \frac{W \Sigma X + \Sigma X_z}{H - WL}$$

$$\widetilde{S} = \frac{W \Sigma (X - \widetilde{M})^2 + \Sigma (X_z - \widetilde{M})^2}{(H - WL - 1)}$$
(6-2a)

$$\tilde{G} = \frac{H-WL}{(H-WL-1)(H-WL-2)} \left[ \frac{W \Sigma (X - \tilde{M})^3 + \Sigma (X_z - \tilde{M})^3}{\tilde{S}^3} \right]$$
 (6-4a)

$$\tilde{M} = \frac{WNM + \sum X_{Z}}{H - WL}$$
 (6-2b)

$$\tilde{S}^{2} = \frac{W (N-1)S^{2} + WN (M-\tilde{M})^{2} + \Sigma (X_{z} - \tilde{M})^{2}}{(H-WL-1)}$$
(6-3b)

$$\tilde{G} = \frac{H-WL}{(H-WL-1) (H-WL-2)\tilde{S}^3} \left[ \frac{W(N-1) (N-2)S^3G}{N} + 3W (N-1) (M-\tilde{M})S^2 \right]$$

+ WN 
$$(M - \tilde{M})^3 + \Sigma (X_z - \tilde{M})^3$$
 (6-4b)

$$Log Q = \tilde{M} + K\tilde{S}$$
 (6-5)

$$\tilde{m} = E$$
; when:  $1 \le E \le Z$  (6-6)

$$\tilde{m}$$
 = WE - (W - 1) (Z + 0.5); when: (Z +1)  $\leq$  E  $\leq$  (Z + N+L) (6-7)

$$P\tilde{P} = \frac{\tilde{m} - a}{H + 1 - 2a} 100 \tag{6-8}$$

Figure 6-1. HISTORICALLY WEIGHTED LOG PEARSON TYPE III - ANNUAL PEAKS
Station: 3-6065, Big Sandy River at Bruceton, TN. D.A. 205 square miles
Record: 1897, 1919, 1927, 1930-1973 (47 years)
Historical period: 1897-1973 (77 years)
N = 44; Z = 3; H = 77

Year	Q (cfs) = Y	Log Y = X	Departure from mean log x = (X - M)	Weight = W	Event Number = E	Weighted order Number = m	Plotting position (Weibull) PP
1897	25,000	4.39794	0.68212	1.00	1	1.00	1.28
1919	21,000	4.32222	0.60640	1.00	2	2.00	2.56
1927	18,500	4.26717	0.55136	1.00	3	3.00	3.85
1935	17,000	4.23045	0.51464	1.68182	4	4.34	5.56
1937	13.800	4.13988	0.42407		5	6.02	7.72
1946	12,000	4.07918	0.36337	l	6	7.71	9.88
1972	12,000	4.07918	0.36337		ž	9.39	12.04
1956	11,800	4.07188	0.35607		a i	11.07	14.19
1942	10,100	4.00432	0.28851		9	12.75	16.35
1950	9,880	3.99475	0.27895		10	14.43	18.50
1930	9.100	3.95904	0.24323				
1967	9,060	3.95904 3.95713	0.24323		11 12	16.12 1 <b>7.8</b> 0	20.67
1932							22.82
1532	7,820	3. <b>8932</b> 1	0.17740		13	19.48	24.97
1973	7,640	3.88309	0.16728		14	21.16	27.13
1962	7,480	3.87390	0.15809		15	22.84	29.28
1965	7,180	3.85612	0.14031		16	24.53	31.45
1936	6,740	3.82866	0.11285	82	17	26.21	33.60
1948	6,130	3.78746	0.07165	- 3)/(44) - 1.68182	18	27.89	<b>35.76</b>
1939	5,940	3.77379	0.05798	7.	19	29.57	37.91
1945	5,630	3.75051	0.03470	<u>.</u>	20	31.25	40.06
1934	5,580	3.74663	0.03082	4	21	32.94	42.23
1955	5,480	3.73878	0.02297	<b>2</b>	22	34.62	44.38
1944	5,340	3.72754	0.01173	. 3	23	36.30	46.54
1951	5,230	3.71850	0.00269	(77)	24	37.98	48.69
1957	5,150	3.71181	-0.00400	ا ت <sup>ا</sup>	25	39.66	50.85
1971	5,080	3.70586	-0.00995	11	26	41.35	53.01
1953	5,000	3.69897	-0.01684	Z)N	27	43.03	55.17
1949	4,740	3.67578	-0.04003	(2)	28	44.71	57.32
1970	4,330	3,63649	-0.07932	Ħ	29	45.50	50.45
1938	4,270	3.63043	-0.07532	) I	30	46.39 48.07	59.47
1952	4.260	3.62941	-0.08538		30 j	48.07	61.62 63.79
1947	3,980	3.59988	-0.11593	<b>≱</b>	32	49.76 51.44	63.79 65.95
1943	3,780	3.57749	-0.11553 -0.13832	1	33	53.12	68.10
1961	3.770	3,57634	-0.13947		ا پ	54.80	70.25
1958	3,770	3.57634 3.52504	-0.13947 -0.19077	- 1 1	34	54.80   56.49	
1954	3,320	3.52504 3.52114	-0.19077 -0.19467		35	56.49 58.17	72.42
1933	3,320	3.52114 3.50786	-0.19467 -0.20795		36 37		74.58
1964	3,100	3.49136	-0.20795 -0.22445		37	69.85 61.53	76.73 78.88
]					1		
1968	3,080	3.48855	-0.22725		39	63.21	81.04
1969	2,800	3.44716	-0.26865		40	64.90	83.21
1963	2,740	3.43775	-0.27806		41	66.58	85.36
1959 1931	2,400 2,060	3.38021 3.31387	-0.33560 -0.40194	] ]	42 43	68.26 69.94	87.51 89.67
	2,000	J.J.1301	-0.9013-9		*	03.94	93.07
966	1,920	3.28330	-0.43251		44	71.62	91.82
940	1,680	3.22531	-0.49050		45	73.31	93.99
960	1,460	3.16435	-0.55146		46	74.99	96.14
941	1,200	3.07918	-0.63663	1.68182	47	76.67	98.29

Figure 6-1. HISTORICALLY WEIGHTED LOG PEARSON-TYPE III - ANNUAL PEAKS (Continued)

Solving (Eq. 6-2a)	Solving (Eq. 6-3a)
$\Sigma X = 162.40155$	$\Sigma x^2 = 3.09755$
ωΣx = 273.13018	$\mu \Sigma x^2 = 5.20952$
$\Sigma x_z = 12.98733$	$\Sigma x_{2}^{2} = 1.13705$
286.11751	6.34657
$\frac{M}{2}$ = 286.11751/77 = $\frac{3.71581}{1.000}$	$\tilde{S}^2 = 6.34657/(77 - 1) = 0.08351$
	$\frac{3}{5} = 0.28898$ $3^3 = 0.02413$
Solving (Eq. 6-4a)	
$\Sigma x^3 = -0.37648$	/77) (0.07405)
$W\Sigma x^3 = -0.63317$	$\widetilde{G} = \frac{(77) (0.07485)}{(76) (75) (0.02413)} = \frac{0.0418}{}$
$\sum x_2^3 = 0.70802$	(76) (75) (0.02413)
0.07485	
Solving (Eq. 6, Page 13)	
N = 77	
A = -0.33 + 0.08 (0.0418) = -0.32666	
B = 0.94 - 0.26 (0.0418) = 0.92913	
MSE <sub>G</sub> = 10[-0.32666 - 0.92913[0.88649]]	= 10 <sup>[-1.150325]</sup> = 0.07074
Solving (Eq. 9.5, Page 12)	
0.302(0.0418) + 0.07074(-0.2)	
.302 + 0.07074	= -0.00409
1000 : 0.010/7	

# Solving (Eq. 6-5)

z	G <sub>w</sub> = -0.00409	(S) (K) S = .28898	$\widetilde{M}$ + $(\widetilde{S})$ (K) = Log Q $\widetilde{M}$ = 3.71581	(ft <sup>3</sup> /s)
99	-2.32934	-0.67313	3.04269	1,103
95	-1.64599	-0.47566	3.24014	1,738
90	-1.28196	-0.37046	3.34535	2,215
80	-0.84141	-0.24315	3.47266	2,969
50	0.00067	0.00019	3.71600	5,200
20	0.84180	0.24326	3,95907	9,100
10	1.28110	0.37021	4.08602	12,190
4	1.74929	0.50551	4.22132	16,646
2	2.05159	0.59289	4.30868	20.355
i i	2.32340	0.67142	4,38723	24,391
i i i	3.08455	0.89138	4.60719	40,475
.01	3.71054	1.07227	4.78808	61,387

# Solving (Eq. 6-6) Solving (Eq. 6-7) Z = 3For E = 1; $\overline{m} = E = 1$ For E = 2; $\overline{m} = E = 2$ For E = 3; $\overline{m} = E = 3$ Solving (Eq. 6-8) For Weibull: A = 0. $\overrightarrow{PP} = (100)$ $(\overline{m})/(76)$

#### Figure 6-2. HISTORICALLY WEIGHTED LOG-PEARSON TYPE III - ANNUAL PEAKS

# Results of Standard Computation for the Current Continuous Record

Big Sandy River at Bruceton, TN. DA - 205 square miles #3-6065 (44 years)

N = number of observations used = 44

M = mean of logarithms = 3.69094

S = standard deviation of logarithms = 0.26721

 $S^2 = 0.07140$   $S^3 = 0.01908$ 

G = coefficient of skewness (logs) = -0.18746

#### Adjustment to Historically Weighted 77 Years

		Historic Peak	s (Z = 3 '	(ears)	
Year	$Y_z$ (ft <sup>3</sup> /s)	Log Y = Xz	X <sub>z</sub> - M	$(x_z - \widetilde{M})^2$	$(x_z - \widetilde{M})^3$
1897	25,000	4.39794	0.68213	0.46531	0.31740
1919	21,000	4.32222	0.60641	0.36774	0.22300
1927	18,500	4.26717	0.55136	0.30400	0.16762
Summatio	on	12.98733	1.83990	1.13705	0.70802

N = 44 Z = 3 H = 77

Solving (Eq. 6-1): W = (77-3)/44 = 1.68182

Solving (Eq. 6-2b):  $\widetilde{M} = \frac{(1.68182)(44)(3.69094) + (12.98733)}{77} = 3.71581$ 

Solving (Eq. 6-3b):


 $(M - \widetilde{M}) = -0.02487$ ,  $(M - \widetilde{M})^2 = 0.000619$ ;  $(M - \widetilde{M})^3 = -0.0000154$ 

 $\tilde{S}^2 = \frac{(1.68182)(43)(0.07140) + (1.60182)(44)(0.000619) + (1.13705)}{76} = 0.08351$ 

 $\tilde{S}^2 = 0.08351$   $\tilde{S} = 0.28898$   $\tilde{S}^3 = 0.02413$ 

Solving (Eq. 6-4b):

 $\tilde{G} = \frac{77}{(76)(75)(0.02413)} \left[ \frac{(1.68182)(43)(42)(0.01908)(-0.18746)}{44} + (3)(1.68182)(43)(-0.02487)(0.07140) + (1.68182)(44)(-0.0000154) + (0.70802) \right]$   $\tilde{G} = 0.0418$ 



D-7

#### APPENDIX E

#### EXAMPLES OF RELIABILITY TESTS FOR THE MEAN AND STANDARD DEVIATION

#### Mean

Analysis of 19 annual flood peaks indicates that  $\overline{X} = 3.8876$  and S = 0.4681. It is hypothesized on the basis of a regional analysis that the true mean is 3.7782. Sample means, where the population variance is unknown, are distributed like the t-distribution. If  $\mu = 3.7782$ , what is the probability of obtaining an X greater than 3.8876?

For N = 19 
$$\overline{X}$$
 = 3.8876 S = 0.4681  $\mu$  = 3.7782  

$$t = \frac{\overline{X} - \mu}{(S^2/N)^{\frac{1}{h}}} = \frac{3.8876 - 3.7782}{((0.4681)^2/19)^{\frac{1}{h}}}$$

Prob 
$$(\overline{X} > 3.8876) = \text{Prob } (t > 1.019)$$

From a table for the t-distribution (Appendix F-4), there is a 16.2% chance that a sample with 18 degrees of freedom will have an  $\overline{X}$  of 3.8876 or more.

#### Standard Deviation

Find the 90% confidence interval for the population variance from a sample for which  $S^2 = 14.4818$  and N = 20. Sample values of variance (standard deviation squared) are distributed like the Chi-square ( $\chi^2$ ) distribution. From a table (Appendix F-5) for the Chi-square distribution with 19 degrees of freedom:

Exceedance	
<b>Probability</b>	Chi-square
0.95	10.117
0.05	30.144

The 90% confidence interval is computed as:

$$\frac{(N-1) S^{2}}{x_{5}^{2}} < \sigma < \frac{(N-1) S^{2}}{x_{95}^{2}}$$

$$\frac{19(14.4918)}{30.144} < \sigma < \frac{19(14.14818)}{10.117}$$

$$9.128 < \sigma < 27.197$$

# APPENDIX F

# STATISTICAL TABLES

Table F-1

MEDIAN PLOTTING POSITIONS

Plotting Positions in Percent Chance Exceedance

rder					. Numb	er of V	Values i	n Array	(N) .					Orde
(m)	1	2	3	4	5	6	7		9	10	11	12	13	(m)
1	50.00	29.29	20.63	15.91	12.94	10.91	9.43	8.30	7.41	6.70	6.11	5.61	5.19	1
		70.71	50.00	38.64	31.47	26.55	22.95	20.21	18.06	16.32	14.89	13.68	12.66	2
52	98.68		79.37	61.36	50.00	42.18	36.48	32.13	28.71	25.94	23.66	21.75	20.13	3
51	96.77	98.65		84.09	68.53	57.82	50.00	44.04	39.35	35.57	32.44	29.82	27.60	4
50	94.86	96.70	98.62		87.06	73.45	63.52	55.96	50.00	45.19	41.22	37.89	35.06	5
49 48	92.95 91.04	94.76 92.81	96.64	98.60	00 57	89.09	77.05	67.87	60.65	54.81	50.00	45.96	42.53	6
47	89.13	90.87	94.65 92.67	96.57	98.57 96.50	98.54	90.57	79.79 91.70	71.29	64.43 74.06	58.78 67.56	54.04 62.11	50.00 57.47	7
46	87.22	88.92	90.68	94 . 55 92 . 52	94.43	96.43	98.50	91.70	81.94 92.59	83.68	76.34	70.18	64.94	8 9
45	85.31	86.97	88.70	90.50	92.37	94.32	96.35	98.47	32.35	93.30	85.11	78.25	72.40	10
44	83.40	85.03	86.72	88.47	90.30	92.21	94.19	96.27	98.44	55.55	93.89	86.32	79.87	11
43	81.50	83.08	84.73	86.45	88.23	90.10	92.04	94.06	96.18	98.40		94.39	87.34	12
42	79.59	81.14	82.75	84.42	86.17	87.98	89.88	91.86	93.93	96.10	98.36		94.81	13
41	77.68	79.19	80.76	82.40	84.10	85.87	87.73	89.56	91.68	93.79	96.00	98.32		
40	75.77	77.24	78.78	80.37	82.03	83.76	85.57	87.46	89.43	91.49	93.64	95.91	98.28	40
39	73.86	75.30	76.79	78.35	79.97	81.65	83.41	85.25	87.17	89.18	91.29	93.49	95.81	39
38	71.95	73.35	74.81	76.32	77.90	79.54	81.26	83.05	84.92	86.88	88.93	91.08	93.33	38
37	70.04	71.41	72.82	74.30	75.83	77.43	79.10	80.85	82.67	84.57	86.57	88.66	90.85	37
36	68.13	69.46	70.84	72.27	73.77	75.32	76.95	78.64	80.41	82.27	84.21	86.24	88.38	36
35	66.23	67.51	68.85	70.25	71.70	73.21	74.79	76.44	78.16	79.96	81.85	83.83	85.90	35
34 33	64.32	65.57	66.87	68.22	69.63	71.10	72.64	74.24	75.91	77.66	79.49	81.41	83.43	34
32	62.41 60.50	63.62 61.68	64.88 62.90	66.20	67.57	68.99	70.48	72.03	73.66	75.35	77.13	78.99	80.95	33
31	58.59	59.73	60.92	64.17 62.15	65.50 63.43	66.88 64.77	58.32 66.17	69.83 67.63	71.40 69.15	73.05 70.74	74.77 72.41	76.58 74.16	78.47 76.00	32 31
30	56.68	57.78	58.93	60.12	61.37	62.66	64.01	65.42	66.90	68.44	70.05	71.75	73.52	30
29	54.77	55.84	56.95	58.10	59.30	60.55	61.86	63.42	64.64	66.13	67.69	69.33	71.05	29
28	52.86	53.89	54.96	56.07	57.23	58.44	59.70	61.02	62.39	63.83	65.33	66.91	68.57	28
27	50.95	51.95	52.98	54.05	55.17	56.33	57.55	58.81	60.14	51.52	62.98	64.50	66.09	27
26	49.05	50.00	50.99	52.02	53.10	54.22	55.39	56.61	57.89	59.22	60.62	62.08	63.62	26
25	47.14	48.05	49.01	50.00	51.03	52.11	53.23	54.41	55.63	56.91	58.26	59.66	61.14	25
24	45.23	46.11	47.02	47.98	48.97	50.00	51.08	52.20	53.38	54.61	55.90	57.25	58.67	24
23	43.32	44.16	45.04	45.95	46.90	47.89	48.92	50.00	51.13	52.30	53.54	54.83	56.19	23
22	41.41	42.22	43.05	43.93	44.83	45.78	46.77	47.80	48.87	50.00	51.18	52.42	53.71	22
21	39.50	40.27	41.07	41.90	42.77	43.67	44.61	45.59	46.62	47.70	48.82	50.00	51.24	21
20	37.59	38.32	39.08	39.88	40.70	41.56	42.45	43.39	44.37	45.39	46.46	47.58	48.76	20
19	35.68	36.38	37.10	37.85	38.63	39.45	40.30	41.19	42.11	43.09	44.10	45.17	46.29	19
18 17	33.77 31.87	34.43 32.49	35.12 33.13	35.83 33.80	36.57	37.34	38.14	38.98	39.86	40.78	41.74	42.75	43.81	18
16	29.96	30.54	31.15	31.78	34.50 32.43	35.23 33.12	35.99 33.83	36.78 34.58	37.51	38.48 36.17	39.38 37.02	40.34 37.92	41.33	17 15
15	28.05	28.59	29.16	29.75	30.37	31.01	31.68	32.37	35.36 33.10	33.87	34.67	35.50	38.86 36.38	15
14	26.14	26.65	27.18	27.73	28.30	28.90	29.52	30.17	30.85	31.56	32.31	33.09	33.91	14
13	24.23	24.70	25.19	25.70	26.23	26.79	27.36	27.97	28.60	29.26	29.95	30.67	31.43	13
12	22.32	22.76	23.21	23.68	24.17	24.68	25.21	25.76	26.34	26.95	27.59	28.25	28.95	12
11	20.41	20.81	21.22	21.65	22.10	22.57	23.05	23.56	24.09	24.65	25.23	25.84	26.48	11
10	18.50	18.86	19.24	19.63	20.03	20.46	20.90	21.36	21.84	22.34	22.87	23.42	24.00	10
9	16.59	16.92	17.25	17.60	17.97	18.35	18.74	19.15	19.59	20.04	20.51	21.01	21.53	9
8	14.69	14.97	15.27	15.58	15.90	16.24	16.59	16.95	17.33	17.73	18.15	18.59	19.05	8
7	12.78	13.03	13.28	13.55	13.83	14.13	14.43	14.75	15.08	15.43	15.79	16.17	16.57	7
6	10.87	11.08	11.30	11.53	11.77	12.02	12.27	12.54	12.83	13.12	13.43	13.76	14.10	6
5	8.96	9.13	9.32	9.50	9.70	9.91	10.12	10.34	10.57	10.82	11.07	11.34	11.62	5
4	7.05	7.19	7.33	7.48	7.63	7.79	7.96	8.14	8.32	8.51	8.71	8.92	9.15	4
3	5.14	5.24	5.35	5.45	5.57	5.68	5.81	5.94	6.07	6.21	6.36	6.51	6.67	3
2	3.23 1.32	3.30	3.36 1.38	3.43	3.50	3.57	3.65	3.73	3.82	3.90	4.00	4.09	4.19	2
		1.35	1.38	1.40	1,43	1.46	1.50	1.53	1.56	1.60	1.64	1.68	1.72	
m)	52	51	50	49	48	47	46	45	44	43	42	41	40	(m)
der					Numbe	T OF V		n Array	(N)					Orde

Table F-1 (Cont)

# MEDIAN PLOTTING POSITIONS

# Plotting Positions in Percent Chance Exceedance

Order	٠				. Numb	er of V	/alues :	in Array	(N) .					Order
(m)	14	15	16	17	18	19	20	21	22	23	24	25	26	(m)
1	4.83	4 . 52	4.24	4.00	3.78	3.58	3.41	3.25	3.10	2.97	2.85	2.73	2.63	1
2	11.78	11.01	10.34	9.75	9.22	8.74	8.31	7.92	7.57	7.24	6.95	6.67	6.42	2
3	18.73	17.51	16.44	15.50	14.65	13.90	13.22	12.50	12.03	11.52	11.05	10.61	10.21	3
4	25.68	24.01	22.54	21.25	20.09	19.05	18.12	17.27	16.50	15.80	15.15	14.55	14.00	4
5 6	32.63	30.51	28.65	27.00	25.53	24.21	23.02	21.95	20.97	20.07	19.25	18,49	17.79	5
7	39.58	37.00	34.75	32.75	30.97	29.37	27.93	26.62	25.43	24.35	23.35	22.43	21.58	5
á	46.53 53,47	43.50 50.00	40.85	38.50	36.41	34.53	32.83	31.30	29.90	28.62	27.45	26.37	25.37	7
9	60.42	56.50	46.95 53.05	44.25 50.00	41.84 47.28	39.68 44.84	37.74 42.64	35.97 40.65	34.37 38.83	32.90	31.55	30.31	29.16	8
10	67.37	63.00	59.15	55.75	52.72	50.00	47.55	45.32	43.30	37.17 41.45	35.65 39.75	34.24	32.95	9
11	74.32	69.49	65.25	61.50	58.16	55.16	52.45	50.00	47.77	45.72	43.85	38.18 42.12	36.74 40.53	10 11
12	81.27	75.99	71.35	67.25	63.59	60.32	57.36	54.68	52.23	50.00	47.95	46.06	44.32	12
13	88.22	82.49	77.46	73.00	69.03	65.47	62.26	59.35	56.70	54.28	52.05	50.00	48.11	13
14	95.17	88.99	83.56	78.75	74.47	70.63	67.17	64.03	61.17	58.55	56.15	53.94	51.89	14
-		95.48	89.66	84.50	79.91	75.79	72.07	68.70	65.63	62.83	60.25	57.88	55.68	15
39	98.24	05.40	95.76	90.25	85.35	80.95	76.98	73.38	70.10	67.10	64.35	61.82	59.47	16
38	95.70	98.19	••••	96.00	90.78	86.10	81.88	78.05	74.57	71.38	68.45	65.76	63.26	17
37	93.16	95.59	98.14		96.22	91.26	86.78	82.73	79.03	75.65	72.55	69.69	67.05	18
36	90.62	92.98	95.47	98.09		96.42	91.69	87.40	83.50	79.93	76.65	73.63	70.84	19
35	88.08	90.38	92.79	95.34	98.04		96.59	92.08	87.97	84.20	80.75	77.57	74.63	20
34	85.54	87.77	90.12	92.60	95.21	97.98		96.75	92.43	88.48	84.85	81.51	78.42	21
33	83.01	85.17	87.45	89.85	92.39	95.07	97.92		96.90	92.76	88.95	85.45	82.21	22
32	80.47	82.56	84.77	87.10	89.56	92.17	94,93	97,86		97.03	93.05	89.39	86.00	23
31	77.93	79.96	82,10	84.35	86.74	89.26	91.93	94.77	97.79		97.15	93.33	89,79	24
30	75.39	77.35	79.42	81.60	83.91	86.35	88.94	91.68	94.60	97.72		97.27	93.58	25
29	72.85	74.75	76.75	78.86	81.08	83.44	85.94	88.59	91.42	94.43	97.64		97.37	26
28	70.31	72.14	74.07	76.11	78.26	80.53	82.95	85.51	88.23	91.13	94.24	97.55		
27	67.77	69.54	71.40	73.36	75.43	77.63	79.95	82.42	85.05	87.84	90.83	94.03	97.47	27
26	65.23	66.93	68.72	70.61	72.61	74.72	76.96	79.33	81.86	84.55	87.43	90.51	93.81	26
25	62,69	64.33	66.05	67.86	69.78	71.81	73.96	76.24	78.67	81.26	84.03	86.99	90.16	25
24	60.16	61.72	63.37	65.11	66.95	68.90	70.97	73.16	75.49	77.97	80.52	83.46	86.51	24
23	57.62	59.12	60.70	62.37	64.13	65.99	67.97	70.07	72.30	74.68	77.22	79.94	82.86	23
22	55.08	56.51	58.02	59.62	61.30	63.09	64,98	66.98	69.12	71.39	73.82	76.42	79.21	22
21	52.54	53.91	55.35	56.87	58.48	60.18	61.98	63.89	65.93	68.10	70.42	72.90	75.56	21
20	50.00	51.30	52.67	54.12	55.65	57.27	58.99	60.81	62.74	64.81	67.01	69.37	71.91	20
19	47.46	48.70	50.00	51.37	52.83	54.36	55.99	57.72	59.56	61.52	63.61	65.85	68.26	19
18	44.92	45.09	47.33	48.63	50.00	51.45	53.00	54.63	56.37	58.23	60.21	62.33	64.60	18
17	42.38	43.49	44.65	45.88	47.17	48.55	50.00	51.54	53.19	54.94	56.81	58.81	60.95	17
16 15	39.84 37.31	40.88 38.28	41.98 39.30	43.13	44.35	45.64	47.00	48.46	50.00	51.65	53.40	55.28	57.30	16
14	34.77	35.67	36.63	40.38 37.63	41.52 38.70	42.73 39.82	44.01	45.37	46.81	48.35	50.00	51.76	53.65	15
13	32.23	33.07	33.95	34.89	35.87	36.91	41.01 38.02	42.28	43.63	45.06	46.60	48.24	50.00	14
12	29.69	30.46	31.28	32.14	33.05	34.01	35.02	39.19 36.11	40.44	41.77 38.48	43.19 39.79	44.72 41.19	46.35 42.70	13 12
11	27.15	27.86	28.60	29.39	30.22	31.10	32.03	33.02	34.07	35.19	36.39	37.67	39.05	11
10	24.61	25.25	25.93	26.64	27.39	28.19	29.03	29.93	30.88	31.90	32.99	34.15	35.40	10
	22.07	22.65	23.25	23.89	24.57	25.28	26.04	26.84	27.70	28.61	29.58	30.63	31.74	9
8	19.53	20.04	20.58	21.14	21.74	22.37	23.04	23.76	24.51	25.32	26.18	27.10	28.09	8
7	16.99	17.44	17.90	18.40	18.92	19.47	20.05	20.67	21.33	22.03	22.78	23.58	24.44	7
6	14.46	14.83	15.23	15.65	16.09	16.56	17.05	17.58	18.14	18.74	19.38	20.06	20.79	6
5	11.92	12.23	12.55	12.90	13.26	13.65	14.06	14.49	14.95	15.45	15.97	16.54	17.14	5
4	9.38	9.62	9.88	10.15	10.44	10.74	11.06	11.41	11.77	12.16	12.57	13.01	13.49	4
3	6.84	7.02	7.21	7.40	7.61	7.83	8.07	8.32	8.58	8.87	9.17	9.49	9.84	3
2	4.30	4.41	4.53	4.66	4.79	4.93	5.07	5.23	5.40	5.57	5.76	5.97	6.19	2
1	1.76	1.81	1.86	1.91	1,96	2.02	2,08	2.14	2.21	2.28	2.36	2.45	2.53	1
<del></del>			•											
(m.)	39	38	37	36	35	34	33	32	31	30	29	28	27	(m)
der					Numb	er of V	alues i	n Array	(N)					Order

Table F-2

<u>DEVIATES FOR PEARSON TYPE-III DISTRIBUTION</u>

### Positive Skew

Skow													
Coefficie	mt					. Percent	Chance E	xceedence					
(G)	99.0	95.0	90,0	80.0	50.0	20.0	10.0	5.0	2.0	1.0	0.5	0.2	0.1
0.0	-2.32635	-1.64485	-1.28155	-0.84162	0.00000	0.84162	1.28155	1.64485	2.05375	2.32635	2,57583	2.87816	3.09023
0.1	-2.25258	-1.61594	-1.27037	-0.84611	-0.01662	0.83639	1.29178	1.67279	2.10697	2.39961	2.66965	2.99978	3.23322
0.2	-2.17840	-1.58607	-1.25824	-0.84986	-0.03325	0.83044	1.30105	1.69971	2.15935	2.47225	2.76321	3.12169	3.37703
0.3	-2.10394	-1.55527	-1.24516	-0.85285	-0.04993	0.82377	1.30936	1.72562	2.21081	2.54421	2.85636	3.24371	3.52139
0.4	-2.02933	-1.52357	-1.23114	-0.85508	-0.06651	0.81638	1.31671	1.75048	2.26133	2.61539	2.94900	3.36566	3.66608
0.5	-1.95472	-1.49101	-1.21618	-0.85653	-0.08302	0.80829	1.32309	1.77428	2.31084	2.68572	3.04102	3.48737	3.81090
0.6	-1.88029	-1.45762	-1.20028	-0.85718	-0. <b>0994</b> 5	0.79950	1.32850	1.79701	2.35931	2.75514	3.13232	3.60872	3.95567
0.7	-1.80621	-1.42345	-1.18347	-0.85703	-0.11578	0.79002	1.33294	1.81864	2.40670	2.82359	3.22281	3.72957	4.10022
0.8	-1.73271	-1.38855	-1.16574	-0.85607	-0.13199	0.77986	1.33640	1.83916	2.45298	2.89101	3.31243	3.84981	4.24439
0.9	-1.66001	-1.35299	-1.14712	-0.85426	-0.14807	0.76902	1.33889	1.85856	2.49811	2.95735	3.40109	3.96932	4.38807
									0.51000	2 2225	2 / 207/	4 00000	( 52112
1.0				-0.85161			1.34039	1.87683	2.54206	3.02256	3.48874	4.08802 4.20582	4.53112 4.67344
1.1				-0.84809		0.74537	1.34092	1.89395	2.58480	3.14944	3.66073	4.32263	4.81492
1.2 1.3				-0.84369 -0.83841		0.73257 0.71915	1.33904	1.92472	2.66657	3.21103	3.74497	4.43839	4.95549
1.4				-0.83223		0.70512	1.33665	1.93836	2.70556	3.27134	3.82798	4.55304	5.09505
1.5				-0.82516		0.69050	1.33330	1.95083	2.74325	3.33035	3.90973	4.66651	5.23353
1.6				-0.81720		0.67532	1.32900	1.96213	2.77964	3.38804	3.99016	4.77875	5.37087
1.7				-0.80837		0.65959	1.32376	1.97227	2.81472	3.44438	4.06926	4.88971	5.50701
1.8				-0.79868		0.64335	1.31760	1.98124	2.84848	3.49935	4.14700	4.99937	5.64190
1.9				-0.78816			1.31054		2.88091	3.55295	4.22336	5.10768	5.77549
1.5	1.03083	-0.50001	0.31300	0.70010	0.25445	0.02002	1.52054	1.50500	2.0001	0.53233	4.22550	3.20.00	5.775
2.0	-0.98995	-0.94871	-0.89464	-0.77686	-0.30685	0.60944	1.30259	1.99573	2.91202	3.60517	4.29832	5.21461	5.90776
2.1	-0,94607	-0.91458	-0.86938	-0.76482	-0.31872	0.59183	1.29377	2.00128	2.94181	3.65600	4.37186	5.32014	6.03865
2.2	-0.90521	-0.88156	-0.84422	-0.75211	-0.32999	0.57383	1.28412	2.00570	2.97028	3.70543	4.44398	5.42426	6.16816
2.3	-0.86723	-0.84976	-0.81929	-0.73880	-0.34063	0.55549	1.27365	2.00903	2.99744	3.75347	4.51467	5.52694	6.29626
2.4	-0.83196	-0.81927	-0.79472	-0.72495	-0.35062	0.53683	1.26240	2.01128	3.02330	3.80013	4.58393	5.62818	6.42292
2.5	-0.79921	-0.79015	-0.77062	-0.71067	-0.35992	0.51789	1.25039	2.01247	3.04787	3.84540	4.65176	5.72796	6.54814
2.6	-0.76878	-0.76242	-0.74709	-0.69602	-0.36852	0.49872	1.23766	2.01263	3.07116	3.88930	4.71815	5.82629	6.67191
2.7	-0.74049	-0.73610	-0.72422	-0.68111	-0.37640	0.47934	1.22422	2.01177	3.09320	3.93183	4.78313	5.92316	6.79421
2.8	-0.71415	-0.71116	-0.70209	-0.66603	-0.38353	0.45980	1.21013	2.00992	3.11399	3,97301	4.84669	6.01858	6.91505
2.9	-0.68959	-0.68759	-0.68075	-0.65086	-0.38991	0.44015	1.19539	2.00710	3.13356	4.01286	4.90884	6.11254	7.03443
3.0	-0.66663	-0.66532	-0.66023	-0.63569	-0.39554	0.42040	1.18006	2.00335	3.15193	4.05138	4.96959	6.20506	7.15235

Source: Appendix 3, Bulletin 17B, reference (46).

# Table F-2 (Cont)

# DEVIATES FOR PEARSON TYPE-III DISTRIBUTION

# Negative Skew

Skow													
Coefficie	mt					Percent	Chance I	broodence					
(G)	99.0	95.0	90.0	80.0	50.0	20.0	10.0	5.0	2.0	1.0	0.5	0.2	0.1
0.0	-2.32535	-1.64485	-1.28155	-0.84162	0.00000	0.84162	1.28155	1.64485	2.05375	2.32635	2.57583	2.87816	3.09023
-0.1	-2.39961	-1.67279	-1.29178	-0.83639	0.01662	0.84611	1.27037	1.61594	1.99973	2.25258	2.48187	2.75706	2.94834
-0.2	-2.47226	-1.69971	-1.30105	-0.83044	0.03325	0.84986	1.25824	1.58607	1.94499	2.17840	2.38795	2.63672	2.80786
-0.3	-2.54421	-1.72562	-1.30936	-0.82377	0.04993	0.85285	1.24516	1.55527	1.88959	2.10394	2.29423	2.51741	2.66915
-0.4	-2.61539	-1.75048	-1.31671	-0.81638	0.06651	0.85508	1.23114	1.52357	1.83361	2.02933	2.20092	2.39942	2.53261
-0.5	-2.68572	-1.77428	-1.32309	-0.80829	0.08302	0.85653	1.21618	1.49101	1.77716	1.95472	2.10825	2.28311	2.39867
-0.6	-2.75514	-1.79701	-1.32850	-0.79950	0.09945	0.85718	1.20028	1.45762	1.72033	1.88029	2.01644	2.16884	2.26780
-0.7	-2.82359	-1.81864	-1.33294	-0.79002	0.11578	0.85703	1.18347	1.42345	1.66325	1.80621	1.92580	2.05701	2.14053
-0.8	-2.89101	-1.83916	-1.33640	-0.77 <b>98</b> 6	0.13199	0.85607	1.16574	1,38855	1.60604	1.73271	1.83660	1.94806	2.01739
-0.9	-2.95735	-1.85856	-1.33889	-0.7 <b>690</b> 2	0.14807	0.85426	1.14712	1.35299	1.54886	1.66001	1.74919	1.84244	1.89894
-1.0	-3.02256	-1.87 <b>68</b> 3	-1.34039	-0.75752	0.16397	0.85161	1.12762	1.31684	1.49188	1.58838	1.66390	1.74062	1.78572
-1.1	-3.0 <b>866</b> 0	-1.89395	-1.34092	-0.74537	0.17968	0.84809	1.10726	1.28019	1.43529	1.51808	1.58110	1.64305	1.67825
-1.2	-3.14944	-1.90992	-1.34047	-0.73257	0.19517	0.84369	1.08608	1.24313	1.37929	1.44942	1.50114	1.55016	1.57695
-1.3	-3.21103	-1.92472	-1.33904	-0.71915	0.21040	0.83841	1.06413	1.20578	1.32412	1.38267	1.42439	1.46232	1.48216
-1.4	-3.27134	-1.93836	-1.33665	-0.70512	0.22535	0.83223	1.04144	1.16827	1.26999	1.31815	1.35114	1.37981	1.39408
-1.5	-3.33035	-1.95083	-1.33330	-0.69050	0.23996	0.82515	1.01810	1.13075	1.21716	1,25611	1.28157	1.30279	1.31275
-1.6	-3.38804	-1.96213	-1.32900	-0.67532	0.25422	0.81720	0.99418	1.09338	1.16584	1.19680	1.21618	1.23132	1,23805
-1.7	-3.44438	-1.97227	-1.32376	-0.65959	0.26808	0.80837	0.96977	1.05631	1.11628	1.14042	1.15477	1.16534	1.16974
-1.8	-3.49935	-1.98124	-1.31760	-0.64335	0.28150	0.79868	0.94496	1.01973	1.06864	1.08711	1.09749	1.10465	1.10743
-1.9	-3.5 <b>529</b> 5	-1.96906	-1.31054	-0.62662	0.29443	0.78816	0.91968	0.98381	1.02311	1.03695	1.04427	1.04898	1.05068
-2.0	-3.60517	-1.99573	-1.30259	-0.60944	0.30685	0.77686	0.89464	0.94871	0.97980	0.98995	0.99499	0.99800	0.99900
-2.1	-3.65600	-2.00128	-1.29377	-0.59183	0.31872	0.76482	0.86938	0.91458	0.93878	0.94607	0.94945	0.95131	0.95188
-2.2	-3.70543	-2.00570	-1.28412	-0.57383	0.32999	0.75211	0.84422	0.88156	0.90009	0.90521	0.90742	0.90854	0.90885
-2.3	-3.75347	-2.00903	-1.27365	-0.55549	0.34063	0.73880	0.81929	0.84976	0.86371	0.86723	0.86863	0.86929	0.86945
-2.4	-3.80013	-2.01128	-1.26240	-0.53683	0.35062	0.72495	0.79472	0.61927	0.82959	0.83196	0.83283	0.83320	0.83328
-2.5	-3.84540	-2.01247	-1.25039	-0.51789	0.35992	0.71067	0.77062	0.79015	0.79765	0.79921	0.79973	0.79994	0.79998
-2.6	-3.88930	-2.01263	-1.23766	-0.49872	0.36852	0.69602	0.74709	0.76242	0.76779	0.76878	0.76909	0.76920	0.76922
-2.7	-3.93183	-2.01177	-1.22422	-0.47934	0.37640	0.68111	0.72422	0.73610	0.73987	0.74049	0.74067	0.74073	0.74074
-2.8	-3.97301	-2.00992	-1.21013	-0.45980	0.38353	0.66603	0.70209	0.71116	0.71377	0.71415	0.71425	0.71428	0.71428
-2.9	-4.01286	-2.00710	-1.19539	-0.44015	0.38991	0.65086	0.68075	0.68759	0.68935	0.68959	0.68964	0.68965	0.68965
-3.0	05120	0.00005	-1 10006	-0.42040	0.2055/	0 63560	0 66023	0 66633	0 66640	0 00000	0 66666		0.66667

Source: Appendix 3, Bulletin 17B, reference (46).

Table F-3

NORMAL DISTRIBUTION

Percent Chance Exceedance for Given Normal Standard Deviate (K)

						K in Col				
<u>K</u>		.01	. 02	. 03	. 04	. 05	.06	. 07	. 08	.09
. 0	50.00	49.60	49.20	48.80	48.40	48.01	47.61	47.21	46.81	46.41
. 1	46.02	45.62	45.22	44.83	44.43	44.04	43.64	43.25	42.86	42.47
. 2	42.07	41.68	41.29	40.90	40.52	40.13	39.74	39.36	38.97	38.59
. 3	38.21	37.83	37.45	37.07	36.69	36.32	35.94	35.57	35.20	34.83
. 4	34.46	34.09	33.72	33.36	33.00	32.54	32.28	31.92	31.56	31.21
. 5	30.85	30.50	30.15	29.81	29.46	29.12	28.77	28.43	28.10	27.76
. 6	27.43	27.09	26.76	26.43	26.11	25.78	25.46	25.14	24.83	24.51
.7	24.20	23.89	23.58	23.27	22.96	22.66	22.36	22.06	21.77	21.48
. 8	21.19	20.90	20.61	20.33	20.05	19.77	19.49	19.22	18.94	18.67
. 9	18.41	18.14	17.88	17.62	17.36	17.11	16.85	16.60	16.35	16.11
1.0	15.87	15.62	15.39	15.15	14.92	14.69	14.46	14.23	14.01	13.79
1.1	13.57	13.35	13.14	12.92	12.71	12.51	12.30	12.10	11.90	11.70
1.2	11.51	11.31	11.12	10.93	10.75	10.56	10.38	10.20	10.03	9.85
1.3	9.68	9.51	9.34	9.18	9.01	8.85	8.69	8.53	8.38	8.23
1.4	8.08	7.93	7.78	7.64	7.49	7.35	7.21	7.08	6,94	6.81
1.5	6.68	6.55	6.43	6.30	6.18	6.06	5.94	5.82	5.71	5.59
1.6	5.48	5.37	5,26	5.16	5.05	4.95	4.85	4.75	4.65	4.55
1.7	4.46	4.36	4.27	4.18	4.09	4.01	3.92	3.84	3.75	3.67
1.8	3.59	3.51	3.44	3.36	3.29	3.22	3.14	3.07	3.01	2.94
1.9	2.87	2.81	2.74	2.68	2.62	2.56	2.50	2.44	2.39	2.33
2.0	2.28	2.22	2.17	2.12	2.07	2.02	1.97	1.92	1.88	1.83
2.1	1.79	1.74	1.70	1.66	1.62	1.58	1.54	1.50	1.46	1.43
2.2	1.39	1.36	1.32	1.29	1.25	1.22	1.19	1.16	1.13	1.10
2.3	1.072	1.044	1.017	. 990	. 964	. 939	. 914	. 889	. 866	. 842
2.4	. 820	. 798	. 776	. 755	.734	.714	. 695	. 676	. 657	. 639
2.5	. 621	. 604	. 587	. 570	. 554	. 539	. 523	. 508	. 494	.480
2.6	. 466	. 453	. 440	. 427	.415	.402	. 391	. 379	.358	.357
2.7	. 347	.336	. 326	.317	.307	.298	. 289	. 280	. 272	. 254
2.8	. 256	.248	. 240	. 233	. 226	.219	.212	. 205	. 199	. 193
2.9	. 187	.181	. 175	. 169	. 164	. 159	. 154	. 149	.144	. 139
.0	. 135	. 131	. 126	. 122	.118	. 114	. 111	. 107	. 104	.100
1.1	. 0968	.0936	.0904	. 0874	.0845	.0816	.0789	.0762	.0736	.0711
.2	. 0687	.0664	.0641	.0619	.0598	.0577	.0557	.0538	.0519	.0501
1.3	.0483	.0467	. 0450	.0434	.0419	.0404	.0390	.0376	.0362	.0350
4	. 0337	.0325	.0313	.0302	. 0291	.0280	.0270	. 0260	.0251	. 0242
. 5	. 0233	.0224	.0216	. 0208	. 0200	.0193	.0185	.0179	.0172	.0165
. 6	.0159	.0153	.0147	.0142	.0136	.0131	.0126	.0121	.0117	.0112
1.7	.01078	.01037	.0099	. 00958	.00920	.00884	.00850	.00817	.00784	.0075
. 8	.00724	.00695	.00667	.00641	.00615	.00591	. 00567	.00544	.00522	.0050
. 9	.00481	.00462	.00443	. 00425	.00408	.00391	.00375	.00360	.00345	. 0033
.0	.00317	.00304	.00291	.00279	. 00267	.00256	. 00245	.00235	.00225	.0021
.0	. 0 <sup>4</sup> 2867									
. 0	. 0 <sup>7</sup> 987									

Note - Values have been generated by use of computer routines for the normal distribution.

Table F-4

PERCENTAGE POINTS OF THE ONE-TAILED t-DISTRIBUTION

							Exceedance	Probabi	lity					
DF	0.40	0.30	0.20	0.10	0.05	0.04	0.02	0,01	0,005	0,002	0.001	0.0005	0.0002	0.0001
1	.325	.727	1.376	3.078	6.314	7.916	15.895	31.821	63,657	159.153	318,309	635,619	1591.549	3183.099
2	.289	.617	1.061	1.886	2.920	3.320	4.849	6.965	9.925	15.764	22.327	31.599	49.985	70.700
3	.277	. 584	. 979	1.638	2.353	2.605	3.482	4.541	5.841	8.053	10,215	12,924	17,598	22.204
4	.271	. 569	.941	1.533	2.132	2.333	2.999	3.747	4.604	5.951	7.173	8.610	10.915	13.034
5	. 267	. 559	.920	1.476	2.015	2.191	2.757	3.365	4.032	5.030	5.893	6.869	8.353	9.678
6	.265	. 553	, 906	1.440	1.943	2.104	2.612	3.143	3.708	4.525	5.208	5.959	7.074	8.025
7	. 263	.549	. 896	1.415	1.895	2.046	2.517	2.998	3.500	4.207	4.786	5.408	6.311	7.063
8	. 262	. 546	. 889	1.397	1.860	2.004	2.449	2.896	3.355	3.991	4.501	5.042	5.812	6.442
9	.261	. 543	. 883	1.383	1.833	1.973	2.398	2.821	3.250	3.835	4.297	4.781	5.461	6.011
10	.260	. 542	. 879	1.372	1.812	1.948	2.359	2.764	3.169	3.716	4.144	4.587	5.202	5.694
11	. 260	. 540	. 876	1.363	1.796	1.928	2.328	2.718	3.106	3.624	4.025	4.437	5.004	5.453
12	. 259	. 539	. 873	1.356	1.782	1.912	2.303	2.681	3.055	3.550	3.930	4.318	4.847	5.263
13	.259	. 538	. 870	1.350	1.771	1.899	2.282	2.650	3.012	3.489	3.852	4.221	4.721	5.111
14	.258	. 537	. 868	1.345	1.761	1.887	2.264	2.624	2.977	3.438	3.787	4.140	4.616	4.985
15	. 258	. 536	. 866	1.341	1.753	1.878	2.249	2.602	2.947	3.395	3.733	4.073	4.528	4.880
16	.258	. 535	.865	1.337	1.746	1.869	2,235	2.583	2.921	3.358	3,686	4.015	4.454	4.791
17	.257	. 534	. 863	1.333	1.740	1.862	2.224	2.567	2.898	3.325	3.646	3.965	4.390	4.714
18	.257	. 534	.862	1.330	1.734	1.855	2.214	2.552	2.878	3.298	3.510	3.922	4.334	4.648
19	.257	. 533	.861	1.328	1.729	1.850	2.205	2.539	2.861	3.273	3.579	3.883	4.285	4,590
20	.257	. 533	. 860	1.325	1.725	1.844	2.197	2.528	2.845	3.251	3.552	3.850	4.241	4 . 539
21	.257	. 532	. 859	1.323	1.721	1.840	2.189	2.518	2.831	3.231	3,527	3.819	4.203	4.493
22	.256	. 532	. 858	1.321	1.717	1.835	2.183	2.508	2.819	3.214	3.505	3.792	4.168	4.452
23	.256	. 532	. 858	1.319	1.714	1.832	2.177	2.500	2.807	3.198	3.485	3.768	4.137	4.415
24	.256	. 531	. 857	1.318	1.711	1.828	2.172	2.492	2.797	3.183	3.467	3.745	4.109	4.382
25	.256	.531	. 856	1.316	1.708	1.825	2.167	2.485	2.787	3.170	3.450	3.725	4.083	4.352
26	.256	. 531	. 856	1.315	1.706	1.822	2.152	2.479	2.779	3.158	3.435	3.707	4.060	4.324
27	.256	.531	. 855	1.314	1.703	1.819	2.158	2.473	2.771	3.147	3.421	3.590	4.038	4.299
28	.256	. 530	. 855	1.313	1.701	1.817	2,154	2.467	2.763	3.136	3.408	3.674	4.018	4.275
29	.256	. 530	. 854	1.311	1.699	1.814	2.150	2.462	2.756	3.127	3,396	3.659	4.000	4.254
30	.256	. 530	. 854	1.310	1.697	1.812	2.147	2.457	2.750	3,118	3.385	3,646	3.983	4.234
40	.255	.529	. 851	1.303	1.684	1.796	2.123	2.423	2.704	3.055	3.307	3.551	3.864	4,094
50	.255	. 528	. 849	1.299	1.676	1.787	2.109	2.403	2.678	3.018	3.261	3.496	3.795	4.014
60	.254	. 527	.848	1.295	1.671	1.781	2.099	2.390	2.660	2.994	3.232	3.460	3.750	3.962
70	.254	. 527	.847	1.294	1.667	1.776	2.093	2.381	2.648	2.977	3.211	3.435	3.719	3.926
80	.254	. 526	. 846	1.292	1.664	1.773	2.088	2.374	2.639	2.964	3.195	3.416	3,696	3.899
90	.254	. 526	.846	1.291	1.662	1.771	2.084	2.368	2.632	2.954	3.183	3,402	3.678	3.878
100	.254	. 525	.845	1.290	1.660	1.769	2.081	2.364	2.626	2.946	3.174	3.390	3.664	3.862
110	.254	. 526	.845	1.289	1.659	1.767	2.078	2.361	2.621	2.940	3.166	3.381	3.652	3.848
120	.254	. 526	.845	1.289	1.658	1.766	2.076	2.358	2.517	2.935	3.160	3.373	3.642	3.837
INF	.253	. 524	. 842	1.282	1.645	1.751	2.054	2.325	2.576	2.878	3.090	3.291	3.540	3.719
	-								2.2.3	_, _, _				/-

Note - Values have been generated by use of computer routines for the inverse t-distribution. A few values for exceedance probabilities of 0.005 and less may differ plus or minus 0.001 from published tables.

Table F-5

VALUES OF CHI-SOUARE DISTRIBUTION

					Exceeden	ce Probabil	ity				
_DF	0.99	0.95	0,90	0.75	0.50	0.25	0,10	0.05	0.01	0.005	0.001
1	.0 <sup>3</sup> 157	.00393	.0158	. 102	.455	1.323	2.706	3.841	6.635	7.879	10.828
2	.020	. 103	.211	. 575	1.386	2.773	4.605	5.991	9.210	10.597	13.816
3	.115	.352	. 584	1.213	2.366	4.108	6.251	7.815	11.345	12.838	16.256
4	.297	.711	1.064	1.923	3.357	5.385	7.779	9.488	13,277	14.860	18.467
5	. 554	1.145	1.610	2.675	4.351	6.626	9.236	11.070	15.086	16.750	20.515
6	. 872	1.635	2.204	3.455	5.348	7.841	10.645	12.592	16.812	18.548	22,458
7	1.239	2.167	2.833	4.255	6.346	9.037	12.017	14.067	18,475	20.278	24.322
8	1.646	2.733	3,490	5.071	7.344	10.219	13.362	15,507	20,090	21.955	26.125
9	2.088	3.325	4.168	5.898	8.343	11.389	14.684	16.919	21.666	23.589	27.877
10	2.558	3.940	4.865	6.737	9.342	12.549	15.987	18.307	23.209	25.188	29.588
11	3.053	4.575	5.578	7.584	10.341	13.701	17.275	19.675	24.725	26.757	31.264
12	3.571	5.226	6.304	8.438	11.340	14.845	18.549	21.026	26,217	28.299	32.909
13	4.107	5,892	7.042	9.299	12.340	15.984	19.812	22.362	27,688	29.819	34.528
14	4.660	6.571	7.790	10.165	13.339	17.117	21.064	23.685	29,141	31.319	36.123
15	5.229	7.261	8.547	11.037	14.339	18.245	22.307	24.996	30.578	32.801	37.697
16	5.812	7.962	9.312	11.912	15.338	19.369	23.542	25.296	32,000	34.257	39.252
17	6.408	8.672	10.085	12,792	16.338	20.489	24.759	27.587	33,409	35.719	40.790
18	7.015	9.390	10.865	13,675	17.338	21.605	25,969	28,869	34.805	37.156	42.312
19	7.633	10.117	11.651	14.562	18.338	22.718	27,204	30.144	36.191	38.582	43.820
20	8.260	10.851	12.443	15.452	19.337	23.828	28.412	31.410	37. <b>566</b>	39.997	45.315
21	8.897	11.591	16.240	13.344	20.337	24.935	29.615	32.671	38.932	41.401	46.797
22	9.542	12.338	14.041	17.240	21.337	26.039	30.813	33.924	40.289	42.796	48.258
23	10.196	13.091	14.848	18.137	22.337	27,141	32.007	35.172	41.638	44.181	49.728
24	10.856	13.848	15.659	19.037	23.337	28.241	33.196	36.415	42,980	45.559	51.179
25	11.524	14.611	16.473	19.939	24.337	29.339	34.382	37.652	44.314	46.928	52.620
26	12.198	15.379	17.292	20.843	25.336	30.435	35.563	38.885	45.642	48.290	54.052
27	12.879	16.151	18.114	21.749	26.336	31,528	36.741	40.113	46.963	49.645	55.476
28	13. <i>5</i> 65	16.928	18.939	22.657	27.336	32.621	37.915	41.337	48.278	50.993	56.892
29	14.256	17.708	19.758	23.567	28.336	33.711	39.087	42.557	49.588	52.336	58.302
30	14.953	18.493	20.599	24.478	29.336	34.800	40.256	43.773	50.892	53.672	59.703
40	22.164	25.509	29.051	33,660	39.335	45.616	51.805	55.759	63.691	66.766	73.402
50	29.707	34.764	37.689	42,942	49.335	56.334	63.167	67.505	76.154	79.490	86.661
60	37.485	43.188	46.459	52.294	59.335	66.981	74.397	79.082	88.379	91.952	99.607
70	45.442	51.739	55.329	61.698	69.334	77.577	85.527	90.531	100.425	104.215	122.317
80	53.540	60.392	64.278	71.145	79.334	88.130	96.578	101.879	112.329	116.321	124.839
90	61.754	69.126	73,291	80.625	89.334	98.650	107.565	113.145	124.116	128.299	137.208
100	70.065	77.930	82.358	90.133	99.334	109.141	118,498	124.342	135,807	140.169	149.449

From Table 26.8, Percentage Points of the  $\chi^2$ -Distribution, <u>Handbook of Mathematical Functions</u>, National Bureau of Standards Applied Mathematical Series 55, U.S. Government Printing Office, Washington, D.C., 1972, page 984 and 985.

Table F-6

VALUES OF THE F DISTRIBUTION

F Distribution Values for Upper 5% ( $\alpha = .05$ )

					Degre	es of Fre	edom for	Numerator					
DF	11	2	3	4	5	6		12	15	20	30	60	INF
1	161.4	199.5	215.7	224.6	230.2	234.0	238.9	243.9	245.9	248.0	250.1	252.2	254.3
2	18.51	19.00	19.16	19.25	19.30	19.33	19.37	19.41	19.43	19.45	19.46	19.48	19.5
3	10.13	9.55	9.28	9.12	9.01	8.94	8.85	8.74	8.70	8.66	8.62	8.57	8.5
4	7.71	6.94	6.59	6.39	5.26	6.15	6.04	5.91	5.86	5.80	5.75	5.69	5.6
5	6.61	5.79	5.41	5.19	5.05	4.95	4.82	4.68	4.62	4.56	4.50	4.43	4.3
6	5.99	5.14	4.76	4.53	4.39	4.28	4.15	4.00	3.94	3.87	3.81	3.74	3.
7	5.59	4.74	4.35	4.12	3.97	3.87	3.73	3.57	3.51	3.44	3.38	3.30	3.:
8	5.32	4.46	4.07	3.84	3.69	3.58	3.44	3.28	3.22	3.15	3.08	3.01	2.
9	5.12	4.26	3.86	3.63	3.48	3.37	3.23	3.07	3.01	2.94	2.86	2.79	2.
10	4.96	4.10	3.71	3.48	3.33	3.22	3.07	2.91	2.85	2.77	2.70	2.62	2.
11	4.84	3.98	3.59	3.36	3.20	3.09	2.95	2.79	2.72	2.65	2.57	2.49	2.
12	4.75	3.89	3.49	3.26	3.11	3.00	2.85	2.69	2.62	2.54	2.47	2.38	2.
L3	4.67	3.81	3.41	3.18	3.03	2.92	2.77	2.60	2.53	2.46	2.38	2.30	2.:
14	4.60	3.74	3.34	3.11	2.96	2.85	2.70	2.53	2.46	2.39	2.31	2.22	2.
<b>ک</b> ا	4.54	3,68	3.29	3.06	2.90	2.79	2.64	2.48	2.40	2.33	2.25	2.16	2.1
16	4.49	3.63	3.24	3.01	2.85	2.74	2.59	2.42	2.35	2.28	2.19	2.11	2.
17	4.45	3.59	3.20	2.96	2.81	2.70	2.55	2.38	2.31	2.23	2.15	2.06	1.
18	4.41	3.55	3.15	2.93	2.77	2.56	2.51	2.34	2.27	2.19	2.11	2.02	1.
19	4.38	3.52	3.13	2.90	2.74	2.53	2.48	2.31	2.23	2.16	2.07	1.98	1.
20	4.35	3.49	3.10	2.87	2.71	2.60	2.45	2.28	2.20	2.12	2.04	1.95	1.
21	4.32	3.47	3.07	2.84	2.68	2.57	2.42	2.25	2.18	2.10	2.01	1.92	1.
22	4.30	3.44	3.05	2.82	2.66	2.55	2.40	2.23	2.15	2.07	1.98	1.89	1.
ಚ	4,28	3.42	3.03	2.60	2.64	2.53	2.37	2.20	2.13	2.05	1.96	1.86	1.
24	4.26	3.40	3.01	2.78	2.62	2.51	2.36	2.18	2.11	2.03	1.94	1.84	1.
25	4.24	3.39	2.99	2.76	2.60	2.49	2.34	2.16	2.09	2.01	1.92	1.82	1.
26	4.23	3.37	2.98	2.74	2.59	2.47	2.32	2.15	2.07	1.99	1.90	1.80	1.
.7	4.21	3.35	2.96	2.73	2.57	2.46	2.31	2.13	2.06	1.97	1.88	1.79	1.
8	4.20	3.34	2.95	2.71	2.56	2.45	2.29	2.12	2.04	1.96	1.87	1.77	1.
<b>19</b>	4.18	3.33	2.93	2.70	2.55	2.43	2.28	2.10	2.03	1.94	1.85	1.75	1.
Õ	4.17	3.32	2.92	2.69	2.53	2.42	2.27	2.09	2.01	1.93	1.84	1.74	1.
0	4.08	3.23	2,84	2.61	2.45	2.34	2.18	2.00	1.92	1.84	1.74	1.64	1.
iO	4.00	3.15	2.76	2.53	2.37	2.25	2.10	1.92	1.84	1.75	1.65	1.53	1.
20	3.92	3.07	2.68	2.45	2.29	2.17	2.02	1.83	1.75	1.66	1,55	1.43	1.
F	3.84	3.00	2.60	2.37	2.21	2.10	1.94	1.75	1.67	1.57	1.46	1.32	1.

From Table 26.9, Percentage Points of the F-Distribution, <u>Handbook of Mathematical Functions</u>, National Bureau of Standards Applied Mathematical Series 55, U.S. Government Printing Office, Washington, D.C., 1972, page 987.

Table F-7

DEVIATES FOR THE EXPECTED PROBABILITY ADJUSTMENT

							. Percen	t Chance !	Doceadano	·				
N	40	30.	20.	10.	5.	4.	2.	1.	0.5	0.2	0.1	0,05	0.02	0.01
2	.398	. 890	1.686	3.769	7.733	9.695	19.467	38.972	77.963	194.922	389.847	779.696	1949.242	3898.484
3	. 333	.713	1.225	2.177	3.372	3.833	5. <b>599</b>	8.042	11.460	18.203	25.781	36,487	57.718	81.637
4	.309	. 653	1.094	1.831	2.631	2.913	3.893	5.077	6.530	9.003	11.420	14.449	19.675	24.825
5	. 297	. 623	1.031	1.680	2.335	2.556	3.285	4.105	5.044	6.519	7.858	9.432	11.957	14.278
6	.289	. 604	.993	1.594	2.177	2.367	2.978	3.635	4.355	5.433	6.366	7.419	9.034	10.453
7	.283	. 592	. 968	1.539	2.077	2.250	2.793	3.360	3.964	4.837	5.567	6.370	7.562	8.579
8	.279	. 582	. 950	1.501	2.010	2.170	2.669	3.180	3.712	4.463	5.076	5.736	6.694	7.492
9	.276	. 575	.937	1.472	1.960	2.113	2.581	3.053	3.537	4.207	4.744	5.314	6.126	6.790
10	.274	. 570	.927	1.451	1.923	2.069	2.516	2.959	3.408	4.022	4.507	5.014	5.728	6.304
11	.272	. 566	.918	1.433	1.893	2.035	2.464	2.887	3.310	3.881	4.328	4.791	5.434	5.947
12	.270	.562	.911	1.419	1.869	2.007	2.423	2.829	3.233	3.772	4.189	4.618	5.208	5.676
13	. 269	. 559	.906	1.407	1.850	1.985	2.390	2.782	3.170	3.684	4.078	4.481	5.030	5.462
14	.268	. 556	.901	1,398	1.833	1.966	2.362	2,743	3.118	3.611	3.987	4.369	4.886	5.290
15	. 267	. 554	. 897	1.389	1.819	1.949	2.338	2.711	3.074	3.551	3.912	4.276	4.768	5.149
16	.266	. 552	.893	1.382	1.807	1.936	2.318	2.683	3.037	3.499	3.848	4.198	4.668	5.030
17	.265	. 551	.890	1.376	1.796	1.923	2.300	2.658	3,005	3.455	3,793	4.131	4.583	4.930
18	.264	.549	.887	1.370	1.787	1.913	2.285	2.637	2.978	3.417	3.746	4.074	4.510	4.844
19	.264	. 548	. 884	1.365	1.779	1.904	2.271	2.619	2.953	3.384	3.704	4.024	4.445	4.769
20	.263	. 546	. 882	1.361	1.772	1.895	2.259	2.602	2.932	3.354	3. <b>668</b>	3.979	4.391	4.703
21	. 263	.545	. 880	1.357	1.765	1.888	2.248	2.587	2.912	3.328	3.635	3.940	4.341	4.645
22	. 262	. 544	. 878	1.353	1.759	1.881	2.239	2.574	2.895	3.304	3.606	3.905	4.297	4.594
23	. 262	. 544	. 877	1.350	1.754	1.875	2.230	2.562	2.879	3.283	3.580	3.874	4.258	4.548
24	.262	. 543	. 875	1.347	1.749	1.869	2.222	2.551	2.865	3.254	3.557	3.845	4.222	4.506
25	. 261	. 542	. 874	1.344	1.745	1.864	2.215	2.542	2.852	3.246	3.535	3.820	4.190	4.469
26	.261	.541	. 873	1.341	1.741	1.860	2.208	2.532	2.841	3.230	3.516	3,796	4.161	4.435
27	.261	.541	. 871	1.339	1.737	1.855	2.202	2.524	2.830	3.216	3,498	3.775	4.134	4.403
28	.260	. 540	. 870	1.337	1.733	1.851	2.196	2.516	2.820	3,202	3.482	3.755	4.110	4.375
29	.260	. 539	. 869	1.335	1.730	1.848	2.191	2.509	2.811	3.190	3,466	3,737	4.087	4.349
30	.260	. 539	. 868	1.333	1.727	1.844	2.186	2.503	2.802	3.178	3.452	3.720	4.066	4.324
40	.258	.535	.862	1.320	1.706	1.820	2.151	2.456	2.742	3.097	3.354	3.602	3.921	4.156
50	.257	.533	. 857	1.312	1.693	1.806	2.131	2.429	2.707	3.051	3.298	3.535	3.838	4.061
60	.257	. 532	. 855	1.307	1.685	1.796	2.118	2.411	2.684	3.020	3.261	3.492	3.785	3,999
70	.256	. 531	. 853	1.303	1.679	1.790	2.108	2.399	2.668	2.999	3.235	3.462	3.748	3.957
80	.256	. 530	. 851	1.300	1.675	1.785	2.101	2.389	2.656	2.984	3.217	3.439	3.721	3.925
90	.255	. 529	. 850	1.298	1.671	1.781	2.096	2.382	2.647	2.971	3.202	3.422	3.700	3.90
.00	.255	. 529	.849	1.297	1.669	1.778	2.092	2.376	2.640	2.962	3.190	3.408	3.683	3.882
10	.255	. 528	.849	1.295	1.666	1.775	2.088	2.372	2.634	2.954	3.181	3.397	3.670	3.867
20	.255	. 528	.848	1.294	1.665	1.773	2.085	2.368	2.629	2.948	3.173	3.388	3.658	3.854
æ	.253	. 524	. 842	1.282	1.645	1.751	2.054	2.326	2.576	2.878	3.090	3.291	3.540	3.719

Note - Values have been generated by use of computer routines for the inverse t-distribution. This table is based on samples drawn from a normal distribution. The above values (after adjustment for skew) may be used as approximate adjustments to Pearson type-III distributions having small skew coefficients.

Table F-8

PERCENTAGES FOR THE EXPECTED PROBABILITY ADJUSTMENT

					eedance	Chance Exc	Percent							
0.0	0.02	0.05	0.1	0.2	0.5	1.	2.	4.	5.	10.	20.	30.	40.	N
		44 040												
10.12	10.602	11.342	12.011	12.81	14.13	15.43	17.12	19.43	20.37	24.3	30.8	37.1	43.5	2
4.219	4.598	5.212	5.793	6.51	7.77	9.08	10.86	13.44	14.52	19.1	27.1	34.7	42.3	3
2.242	2.531	3.018	3.496	4.11	5.23	6.45	8.18	10.77	11.88	16.7	25.3	33.6	41.8	4
1.370	1.596	1.990	2.389	2.92	3.92	5.05	6.70	9.26	10.38	15.3	24.3	<b>32</b> .9	41.4	5
. 919	1.101	1.427	1.768	2.23	3.14	4.19	5.78	8.30	9.41	14.4	23.6	32.4	41.2	6
. 658	. 809	1.086	1.384	1.80	2.63	3.62	5.16	7.63	8.74	13.8	23.1	32.1	41.0	7
. 49	.623	. 863	1.127	1.50	2.28	3.22	4.70	7.14	8.24	13.3	22.7	31.8	40.9	8
. 388	.498	.710	.947	1.29	2.02	2.92	4.36	6.77	7.86	12.9	22.4	31.6	40.8	9
.313	. 409	. 599	. 816	1.13	1.82	2.69	4.09	6.47	7. <b>56</b>	12.6	22.1	31.5	40.7	10
.259	.345	. 516	.716	1.01	1.67	2.50	3.88	6.23	7.32	12.4	22.0	31.3	40.7	11
. 219	.296	. 453	. 638	.92	1.54	2.36	3.71	6.04	7.12	12.2	21.8	31.2	40.6	12
. 188	.258	. 403	.577	.84	1.44	2.23	3.56	5.87	6,95	12.0	21.7	31.1	40.6	13
. 164	.228	.363	. 526	.78	1.36	2.13	3.44	5.73	6.80	11.9	21.5	31.0	40.5	14
. 145	.204	.330	. 485	.73	1.29	2.04	3.33	5.61	6.68	11.8	21.4	31.0	40.5	15
. 129	. 184	.303	. 450	. 58	1.23	1.97	3.24	5.50	6.57	11.6	21.3	30.9	40.5	16
. 116	.168	.280	.421	.65	1.18	1.90	3.16	5.41	6.47	11.5	21.3	30.9	40.4	17
. 106	. 154	.261	.396	.61	1.13	1.85	3.09	5.33	6.39	11.5	21.2	30.8	40.4	18
. 097	. 143	.244	.374	.59	1.09	1.80	3.03	5.26	6.31	11.4	21.1	30.8	40.4	19
.089	. 133	.230	.355	.56	1.06	1.75	2.98	5.19	6.25	11.3	21.1	30.7	40.4	20
.083	. 124	.217	.339	. 54	1.02	1.71	2.93	5.13	6.19	11.2	21.0	30.7	40.4	21
.07	. 117	.206	.324	.52	1.00	1.67	2.88	5.08	6.13	11.2	21.0	30.7	40.3	22
.072	.110	. 197	.311	.50	.97	1.64	2.84	5.03	6.08	11.1	20.9	30.6	40.3	23
.068	. 104	. 188	.299	.49	.95	1.61	2.80	4,99	6.03	11.1	20.9	30.6	40.3	24
.06	.099	. 180	.289	.47	.93	1.59	2.77	4.95	5.99	11.0	20.9	30.6	40.3	25
.06	.094	.173	.279	.46	.91	1,56	2.74	4.91	5.95	11.0	20.8	30.6	40.3	26
.050	.090	. 167	.271	.45	.89	1.54	2.71	4.87	5.82	11.0	20.8	30.5	40.3	27
.05	.086	. 161	.263	.44	.88	1.52	2.68	4.84	5.88	10.9	20.8	30.5	40.3	28
.05	.083	.156	.255	.43	.86	1.50	2,66	4.81	5.85	10.9	20.7	30.5	40.3	29
.05	.080	.151	.249	.42	.85	1.48	2.63	4.78	5.82	10.9	20.7	30.5	40.2	30
.03	.060	.119	.204	.35	.75	1.35	2,47	4.58	5.61	10.7	20.5	30.4	40.2	40
.02	.049	. 102	.179	.32	.70	1.28	2.37	4.47	5.49	10.5	20.4	30.3	40.1	50
.02	.043	.092	.164	.30	.66	1.23	2.31	4.39	5.41	10.4	20.4	30.2	40.1	60
. 02	.039	.085	.154	.28	.64	1.19	2.25	4.33	5.35	10.4	20.3	30.2	40.1	70
.02	.036	.080	.146	.27	.62	1.17	2.23	4.29	5.30	10.3	20.3	30.2	40.1	80
.01	.034	.076	. 141	.26	.61	1.15	2.20	4.26	5.27	10.3	20.2	30.2	40.1	90
.01	.032	.073	.136	.26	.59	1.13	2.18	4.23	5.24	10.3	20.2	30.1	40.1	100
.01	.031	.071	.132	.25	.59	1.12	2.17	4.21	5.22	10.2	20.2	30.1	40.1	110
.01	.030	.069	. 130	.25	.58	1.11	2.15	4.19	5.20	10.2	20.2	30.1	40.1	120
.01	.020	.050	.100	.20	.50	1.00	2.00	4.00	5.00	10.2	20.0	30.0	40.0	DEF

Note - Values have been generated by use of computer routines for the inverse normal and inverse t-distributions. This table is based on samples drawn from a normal distribution. The above values may be used as approximate adjustments to Pearson type-III distributions having small skew coefficients.

Table F-9
CONFIDENCE LIMIT DEVIATES FOR NORMAL DISTRIBUTION

99% and 98% Limits

Sample	•					_	_						
Size							hance Exc						
<u> </u>	<b>99</b> .0	95.0	90.0	80,0	50.0	20.0	10,0	5.0	2.0	1,0	5	.2	.1
						Confide	nce Level	= .005					
10	-1.232	731	436	027	1.028	2.490	3.367	4.121	4.991	5.581	6.126	6.790	7.258
15	-1.385	866	569	175	.769	1.996	2.718	3.336	4,048	4.530	4.975	5.517	5.898
20	-1.483	951	651	259	.640	1.768	2.423	2.982	3.624	4.059	4.460	4.948	5.292
25	-1.554	-1.012	708	317	. 559	1.532	2.249	2,774	3.378	3.785	4.161	4.618	4.940
30	-1.608	-1.058	751	359	. 503	1.539	2.132	2.636	3.214	3.603	3.962	4.399	4.707
40	-1.688	-1.125	813	419	. 428	1.421	1.983	2.460	3.005	3.372	3.710	4.122	4.412
50	-1.744	-1.172	857	460	.379	1.346	1.890	2.350	2.875	3.229	3.555	3.951	4.229
60	-1.787	-1.207	890	492	. 344	1.294	1.825	2.273	2.785	3.129	3.446	3.832	4.103
70	-1.822	-1.236	916	516	.317	1.254	1.776	2.216	2.719	3.056	3.366	3.744	4.009
80	-1.850	-1.259	937	535	.295	1.224	1.738	2.172	2.666	2.998	3.304	3.675	3.936
90	-1.874	-1.279	955	552	.277	1.199	1.708	2.136	2.624	2.952	3.254	3.620	3.878
100	-1.894	-1.295	970	<b>56</b> 5	.263	1.177	1.682	2.106	2.589	2.914	3.212	3.574	3.829
						Comfide	nce Level	<b>=</b> .995					
10	-5.581	-4.121	-3,367	-2,490	-1.028	.027	. 436	.731	1.038	1.232	1.405	1.611	1.754
15	-4.530	-3.336	-2.718	-1.996	769	.175	.569	.866	1.182	1.385	1.567	1.785	1.936
20	-4.059	-2.982	-2.423	-1.768	640	.259	.651	.951	1.274	1.483	1.671	1.897	2.054
25	-3.785	-2.774	-2.249	-1.632	559	.317	.708	1.012	1.340	1.554	1.747	1.979	2.140
30	-3.603	-2.636	-2.132	-1.539	503	.359	.751	1.058	1.391	1.608	1.804	2.040	2.205
40	-3.372	-2.460	-1.983	-1.421	428	.419	. 813	1.125	1.464	1.688	1.890	2.132	2.302
50	-3.229	-2.350	~1.890	-1.346	379	. 460	.857	1.172	1.518	1.744	1.950	2.198	2.371
60	-3.129	-2.273	-1.825	-1.294	344	.492	. 890	1.207	1.558	1.787	1.996	2.248	2.424
70	-3.056	-2.216	-1.776	-1.254	317	. 516	. 916	1.236	1.590	1.822	2.033	2.288	2.466
80	-2.998	-2.172	-1.738	-1.224	295	. 535	.937	1.259	1.515	1.850	2.063	2.320	2.500
90	-2.952	-2.136	-1.708	-1.199	277	. 552	. 955	1.279	1.637	1.874	2.089	2.348	2.529
100	-2.914	-2.106	-1.682	-1.177	263	. 565	.970	1.295	1.656	1.894	2.110	2.371	2.554
						Confide	nce Level	010					
10	-1.314	804	508	107	. 892	2.243	3.048	3.738	4.535	5.074	5.572	6.178	6,605
15	-1.458	929	629	236	.678	1.841	2.521	3.102	3.770	4.222	4.639	5.147	5.504
20	-1.550	-1.008	705	313	. 568	1.651	2.276	2,808	3,419	3.832	4.212	4.675	5.001
25	-1.616	-1.064	757	364	.498	1.536	2.129	2.633	3.211	3.601	3.960	4.398	4.706
30	-1.667	-1.107	797	403	.450	1.457	2.030	2.515	3.071	3.447	3.792	4.212	4.508
40	-1.741	-1.169	854	457	.384	1.355	1.902	2.364	2.893	3.249	3.577	3.975	4.255
50	-1.793	-1.212	894	496	.340	1.290	1.821	2.269	2.781	3.125	3.442	3.826	4.097
60	-1.833	-1.245	924	524	.309	1.244	1.764	2.202	2.702	3.038	3.347	3.723	3.987
70	-1.865	-1.272	948	545	.285	1.210	1.722	2.153	2.644	2.974	3.278	3.647	3.906
80	-1.891	-1.293	968	563	.265	1.183	1.688	2.114	2.599	2.924	3.223	3.587	3.842
90 100	-1.913 -1.932	-1.311	984 000	578 501	.250 .236	1.160	1.661	2.082	2.561	2.883	3.179	3.538	3.791
100	-1.832	-1.326	998	<b>591</b>	.230	1.142	1.639	2.056	2.531	2.850	3.143	3.498	3.748
						Confide	nce Level	990					
10	-5.074	-3.738	-3.048	-2.243	892	. 107	.508	.804	1.115	1.314	1.492	1.704	1.851
15	-4.222	-3.102	-2.521	-1.841	678	.236	.629	. 929	1.251	1.458	1.645	1.868	2.024
20	-3.832	-2.808	-2.276	-1.651	568	.313	.705	1,008	1.336	1.550	1.743	1.974	2.135
25	-3.601	-2.633	-2,129	-1.536	498	.364	.757	1.064	1.399	1.616	1.813	2.050	2.215
30	-3.447	-2.515	-2.030	-1.457	450	.403	. 797	1.107	1.446	1.667	1.857	2.109	2.277
40	-3.249	-2.364	-1.902	-1.355	384	.457	.854	1.169	1.515	1.741	1.946	2.194	2.367
50	-3.125	-2.269	-1.821	-1.290	340	.496	. 894	1.212	1.563	1.793	2.002	2.255	2.431
60	-3.038	-2.202	-1.764	-1.244	309	. 524	. 924	1.245	1.600	1.833	2.045	2.301	2.480
70	-2.974	-2.153	-1.722	-1.210	285	.545	.948	1.272	1.630	1.865	2.079	2.338	2.519
80	-2.924	-2.114	-1.688	-1.183	265	.563	.968	1.293	1.653	1.891	2.107	2.368	2.551
90	-2.883	-2.082	-1.661	-1.160	250	. 578	.984	1.311	1.674	1.913	2.131	2.394	2.578
100	-2.850	-2.056	-1.639	-1.142	236	. 591	.998	1.326	1.691	1.932	2.151	2.416	2.601
								·					

Table F-9 (Cont)

# CONFIDENCE LIMIT DEVIATES FOR NORMAL DISTRIBUTION

# 95% and 90% Limits

Sampl												<del></del>	
Size N	99,0	 95.0	90.0	 80.0							<u>.</u> .		:
	99,0	95.0	90.0	80.0	50.0	20.0	10.0	5.0	2.0	1.0		.2_	1
							ence Leve						
10	-1.442	915	615	220	.715	1.931	2.647	3.259	3.964	4.440	4.879	5.414	5.791
15 20	-1.572	-1.026	721	328	.554	1.638	2.264	2.797	3.409	3.822	4.203	4.667	4.993
25	-1.654 -1.713	-1.095 -1.145	786 831	392 436	.468	1.494	2.079 1. <b>96</b> 6	2.576	3.145	3.529	3.883	4.313	4.616
30	-1.757	-1.143	866	-,456 -,468	.413 .373	1.405 1.344	1.889	2.442 2.351	2.986 2.878	3.353 3.233	3.691	4.101	4.390
40	-1.823	-1.236	916	515	.320	1.263	1.789	2.232	2.738	3.078	3.560 3.391	3.957 3.772	4.237 4.039
50	-1.869	-1.274	950	547	.284	1.211	1.724	2.156	2.649	2.980	3.284	3.654	3.914
60	-1.903	-1.303	976	571	.258	1.174	1.679	2.103	2.586	2.911	3.209	3.571	3.826
70	-1.931	-1.325	997	590	.238	1.146	1.645	2.063	2.540	2.859	3.153	3.510	3.761
80	-1.954	-1.344	-1.014	605	.223	1.124	1.618	2.032	2.502	2.819	3.109	3.462	3.710
90	-1.973	-1.360	-1.028	618	. 209	1.106	1.596	2.006	2,473	2.786	3.073	3.423	3.668
100	-1.969	-1.373	-1.040	629	. 198	1.091	1.578	1.985	2.449	2.759	3.044	3.391	3.634
							nce Leve						
10	-4.440	-3.259	-2.647	-1.931	715	.220	.615	.915	1.235	1.442	1.628	1.850	2.005
15	-3.822	-2.797	-2.264	-1.638	554	. 328	.721	1.026	1.357	1.572	1.766	1.999	2.161
20 25	-3. <b>529</b> -3.353	-2.576	-2.079	-1.494	468	.392	.786	1.095	1.433	1.654	1.854	2.093	2.251
30	-3.333 -3.233	-2.442 -2.351	-1.966 -1.889	-1.405 -1.344	413 373	. 435	.831	1.145	1.488	1.713	1.917	2.162	2.333
40	-3.078	-2.232	-1.789	-1.263	320	.468 .515	. <b>86</b> 6 . 916	1.182 1.236	1.529 1.590	1.757	1.964	2.214	2.388
50	-2.980	-2.156	-1.724	-1.211	284	.547	.950	1.274	1.633	1.823 1.869	2.034 2.084	2.289 2.343	2.467 2.524
60	-2.911	-2.103	-1.679	-1.174	258	.571	.976	1.303	1.664	1.903	2.120	2.382	2.566
70	-2.859	-2.063	-1.645	-1.146	238	. 590	.997	1.326	1.690	1.931	2.150	2.415	2.600
80	-2.819	-2.032	-1.618	-1.124	223	.605	1.014	1.344	1.711	1.954	2.175	2.441	2.628
80	<b>-2.786</b>	-2.006	-1.596	-1.106	209	.618	1.028	1.360	1.728	1.973	2.195	2.464	2.652
100	-2.759	-1.985	-1.578	-1.091	198	. 629	1.040	1.373	1.744	1.989	2.213	2.483	2.672
						Confide	nce Level	050					
10	-1.563	-1.017	712	317	. 580	1.702	2.355	2.911	3.549	3.981	4.379	4.862	5.203
15	-1.677	-1.114	802	406	.455	1.482	2.068	2.566	3.136	3.520	3.874	4.304	4.607
20	-1.749	-1.175	858	460	.387	1.370	1.926	2.396	2.934	3.295	3.628	4.033	4.318
25 30	-1.801 -1.840	-1.217 -1.250	898 928	497	.342	1.301	1.838	2.292	2.809	3.158	3.478	3.868	4.142
40	-1.896	-1.297	970	525 565	.310	1.252	1.777	2.220	2.724	3.064	3.376	3.755	4.022
50	-1.936	-1.329	-1.000	592	. <b>266</b> . <b>23</b> 7	1.188 1.146	1.697 1.646	2.125 2.065	2.613 2.542	2.941 2.862	3.242	3.608	3.865
60	-1.966	-1.354	-1.022	612	.216	1.116	1.609	2.022	2.492	2.807	3.157 3.096	3.515 3.448	3.766 3.695
70	-1.990	-1.374	-1.040	629	. 199	1.093	1.581	1.990	2.454	2.765	3.051	3.399	3.643
80	-2.010	-1.390	-1.054	642	. 186	1.076	1.559	1.964	2.425	2.733	3.016	3.360	3.601
90	-2.026	-1.403	-1.066	652	.175	1.061	1.542	1.944	2.400	2,706	2.987	3.328	3.567
100	-2,040	-1.414	-1.077	662	. 166	1.049	1.527	1.927	2.380	2.684	2.963	3.301	3.539
						Confide	nce Level	950					
10	-3,981	-2.911	-2.355	-1.702	580	.317	.712	1.017	1.348	1.563	1.757	1.989	2.151
15	-3.520	-2.566	-2.068	-1.482	455	.406	. 802	1.114	1.454	1.677	1.878	2.121	2.290
20	-3.295	-2.396	-1.926	-1.370	387	.460	. 858	1.175	1.522	1.749	1.955	2.204	2.378
25 30	-3.158 -3.064	-2.292	-1.838	-1.301	342	.497	.898	1.217	1.569	1.801	2.011	2.264	2.441
30 40	-3.064 -2.941	-2.220 -2.125	-1.777 -1.697	-1.252 -1.188	310	.525	.928	1.250	1.605	1.840	2.053	2.310	2.489
50	-2.862	-2.065	-1.646	-1.166 -1.146	266 237	. 565 . 592	.970	1.297	1.657	1.896	2.113	2.375	2.558
60	-2.807	-2.022	-1.609	-1.116	237 216	.592 .612	1.000 1.022	1.329 1.354	1.694	1.936 1.966	2.156	2.421	2.607
70	-2.765	-1.990	-1.581	-1.093	199	.629	1.040	1.374	1.722 1.745	1.990	2.188 2.214	2.456 2.484	2.644
80	-2.733	-1.964	-1.559	-1.076	186	.642	1.054	1.390	1.762	2.010	2.235	2.507	2.673 2.697
90	-2.706	-1.944	-1.542	-1.061	175	.652	1.066	1.403	1.778	2.026	2.252	2.526	2.718
100	-2.684	-1.927	-1.527	-1.049	166	.662	1.077	1.414	1.791	2.040	2.257	2.542	2.735
	**********												

Table F-9 (Cont)

# CONFIDENCE LIMIT DEVIATES FOR NORMAL DISTRIBUTION

# 80% and 50% Limits

Sample	-							**				*	
Size	·					Percent (					<u>.</u> .		
<u> </u>	99,0	95.0	90,0	50.0	50.0	20.0	_10.0	5.0	2.0	1.0		.2_	1
						Confid	ence Leve	1 = .100					
10	-1.715	-1.144	828	429	. 437	1.474	2.066	2.568	3.144	3.532	3.889	4.324	4.629
15	-1.808	-1.222	901	499	.347	1.320	1.867	2.329	2.857	3.212	3.539	3.936	4.215
20	-1.867	-1.271	946	541	. 297	1.240	1.765	2.208	2.712	3.052	3.364	3.743	4.009
25	-1.908	-1.306	978	~.570	. 264	1.190	1.702	2.132	2.623	2.952	3.255	3.623	3.882
30	-1.940	-1.332	-1.002	593	.239	1.154	1.657	2.080	2.561	2.884	3.181	3.541	3.794
40	-1.986	-1.369	-1.036	624	.206	1.106	1.598	2.010	2.479	2.793	3.082	3.433	3.679
50 60	-2.018	-1.396	-1.059	645	.184	1.075	1.559	1.965	2.426	2.735	3.019	3.363	3.605
70	-2.042 -2.061	-1.415	-1.077	662	.167	1.052	1.532	1.933	2.389	2.694	2.974	3.313	3.552
80	-2.001	-1.431	-1.091 -1.103	674 - 694	.155	1.035	1.511	1.909	2.360	2.662	2.940	3.275	3.513
90	-2.090	-1.444 -1.454	-1.103	684 693	.144 .135	1.021 1.010	1.495 1.481	1.890 1.874	2.338 2.319	2.638	2.913	3.247	3.482
100	-2.101	-1.463	-1.120	701	. 129	1.001	1.470	1.861	2.305	2.618 2.601	2. <b>89</b> 1 2.873	3.223 3.203	3.456 3.435
	0.101	1.400	1.120	.,,	. 420	1.001	1.470	1.001	2.505	2.001	2.0/3	3.203	3.403
10	-3.532	-2.568	-2.066	-1.474	437	Confide .429	nce Level		1.489	1 716	1 010	2	2 22-
15	-3.212	-2.329	-1.867				. 828	1.144		1.715	1.919	2.165	2.337
20	-3.212 -3.052	-2.208	-1.765	-1.320 -1.240	~.347 297	.499 .541	.901 .946	1.222 1.271	1. <i>5</i> 76 1.630	1.808 1.867	2.019 2.082	2.273 2.342	2.451 2.523
25	-2.952	-2.132	-1.702	-1.190	264	.570	.978	1.306	1.669	1.908	2.126	2.390	2.574
30	-2.884	-2.080	-1.657	-1.154	239	.593	1.002	1.332	1.696	1.940	2.160	2.425	2.612
40	-2.793	-2.010	-1.598	-1.106	206	.624	1.035	1.369	1.740	1.986	2.209	2.479	2.668
50	-2.735	-1.965	-1.559	-1.075	-, 184	.645	1.059	1.396	1.770	2.018	2.244	2.517	2.708
60	-2.694	-1.933	-1.532	-1.052	167	.662	1.077	1.415	1.792	2.042	2.269	2.544	2.737
70	-2.662	-1.909	-1.511	-1,035	155	.674	1.091	1.431	1.810	2.061	2.290	2.567	2.761
80	-2.538	-1.890	-1.495	-1.021	144	.684	1.103	1.444	1.824	2.077	2.307	2.585	2.780
90	-2.618	-1.874	-1.481	-1.010	136	. 693	1.112	1.454	1.836	2.090	2.321	2.500	2.796
100	-2.601	-1.861	-1.470	-1.001	129	.701	1.120	1.463	1.847	2.101	2.333	2.613	2.810
						Confide	nce Level	250					
10	-2.008	-1.382	-1.043	625	.222	1.155	1.671	2.104	2.596	2,927	3.231	3.599	3.858
15	-2.055	-1.422	-1.081	661	.179	1.083	1.577	1.991	2.450	2.775	3.064	3.415	3.661
20	-2.085	-1.448	-1.104	683	.154	1.045	1.528	1.932	2.390	2.697	2.978	3.320	3.560
25	-2.106	-1.466	-1, 121	599	. 137	1.020	1.497	1.895	2.346	2.648	2.925	3.261	3.497
30	-2.123	-1.479	-1.133	710	.125	1.002	1.475	1.869	2.315	2.614	2.888	3.220	3.453
40	-2.147	-1.499	-1.151	726	.108	.978	1.445	1.834	2.274	2.568	2.838	3.165	3.395
50 60	-2.163	-1.513	-1.164	738	.096	.962	1.425	1.811	2.247	2.538	2.805	3.129	3.357
70	-2.176 -2.186	-1.523 -1.532	-1.173 -1.181	747	.088	.950	1.411	1.795	2.227	2.517	2.783	3.105	3.331
80	-2.194	-1.532	-1.187	753 759	.081 .076	.942 .935	1.401 1.392	1.782	2.213 2.202	2.501	2.765	3.085	3.310
90	-2.201	-1.544	-1.192	763	.071	.929	1.382	1.772 1.764	2.192	2.489 2.478	2.7 <b>5</b> 2 2.740	3.070 3.058	3.294 3.281
100	-2.207	-1.549	-1.196	767	.068	.925	1.380	1.758	2.184	2.470	2.731	3.048	3.270
									0.20	2.470	2.701	5.540	0.270
10	-2.927	-2.104	-1.671	-1,155	222	Confide .625	nce Level 1.043	<u>750</u>	1.759	2.008	2.235	2.508	2.700
15	-2.775	-1.991	-1.577	-1.083	222 179	.661	1.043	1.422	1.803	2.008	2.235	2.562	2.756
20	-2.697	-1.932	-1.528	-1.045	154	.683	1.104	1.448	1.831	2.085	2.317	2.597	2.793
25	-2.648	-1.895	-1.497	-1.020	137	.699	1.121	1.466	1.851	2.106	2.339	2.621	2.819
30	-2.614	-1.869	-1.475	-1.002	- 125	.710	1.133	1.479	1.867	2.123	2.357	2.641	2.839
40	-2.568	-1.834	-1.445	978	108	.726	1.151	1.498	1.888	2.147	2.383	2.668	2.868
50	-2.538	-1.811	-1.425	962	096	.738	1.164	1.513	1.903	2.163	2.400	2.688	2.889
60	-2.517	-1.795	-1.411	950	088	.747	1.173	1.523	1.916	2.176	2.414	2.702	2.904
70	-2.501	-1.782	-1.401	942	081	.753	1.181	1.532	1.925	2.186	2.425	2.714	2.917
80	-2.489	-1.772	-1.392	935	076	.759	1.187	1.538	1.932	2.194	2.434	2.724	2.927
90	-2.478	-1.764	-1.386	929	071	. 763	1.192	1.544	1.938	2.201	2.441	2.731	2.935
100	-2.470	-1.758	-1.380	925	068	. 767	1.196	1.549	1.944	2.207	2.447	2.739	2.943

Table F-9 (Cont)

# CONFIDENCE LIMIT DEVIATES FOR NORMAL DISTRIBUTION

# 50% Confidence Level

Sample Size						Percent C	hance Exc	eedance .					
<u>N</u>	99,0	95.0	90.0	80.0	50.0	20.0	10.0	5.0	2,0	1.0	5	.2	1_
						Confide	nce Level	= .500					
10	-2.410	-1.702	-1.324	868	.000	.868	1.324	1.702	2.126	2.410	2.670	2.984	3.205
15	-2.379	-1.681	-1.309	858	.000	. 858	1.309	1.681	2.100	2.379	2.635	2.945	3.153
20	-2.365	-1.671	-1.301	854	.000	.854	1.301	1.671	2.087	2.365	2.619	2.927	3,143
25	-2.357	-1.666	-1.297	851	,000	.851	1.297	1.666	2.080	2.357	2.610	2.917	3.132
30	-2.352	-1.662	-1.294	850	,000	.850	1.294	1.662	2.076	2.352	2,605	2.910	3,125
40	-2.345	-1.658	-1.291	847	.000	.847	1.291	1.658	2.070	2.345	2.597	2.902	3.116
50	-2.341	-1.655	-1.289	846	.000	.846	1.289	1.655	2.066	2.341	2.592	2.897	3.111
60	-2.339	-1.653	-1.288	846	.000	.846	1.288	1.653	2.064	2.339	2.590	2.894	3,107
70	-2.337	-1.652	-1.287	845	.000	.845	1.287	1.652	2.063	2.337	2.588	2.892	3.105
80	-2.336	-1.651	-1.286	845	.000	.845	1.286	1.651	2.062	2.336	2.587	2.890	3.103
						.845	1.286	1.650	2.061	2.335	2.585	2.888	3.101
90	-2.335	-1.650	-1.286	845	.000							2.887	3.101
100	-2.334	-1.650	-1.285	844	.000	. 844	1.285	1.650	2.060	2.334	2.584	4.00/	5.100

Source: Owen, D. B., reference (25).

Table F-10

MEAN-SQUARE ERROR OF STATION SKEW COEFFICIENT

Station			F	lecord Ler	gth, in	ears (N c	or H)			
Skew (G)	10	20	30	40	50	60	70	80	90	100
0.0	0.468	0.244	0.167	0.127	0.103	0.087	0.075	0.066	0.059	0.054
0.1	0.476	0.253	0.175	0.134	0.109	0.093	0.080	0.071	0.064	0.058
0.2	0.485	0.262	0.183	0.142	0.116	0.099	0.086	0.077	0.069	0.063
0.3	0.494	0.272	0.192	0.150	0.123	0.105	0.092	0.082	0.074	0.068
0.4	0.504	0.282	0.201	0.158	0.131	0.113	0.099	0.089	0.080	0.073
0.5	0.513	0.293	0.211	0.167	0.139	0.120	0.106	0.095	0.087	0.079
0.6	0.522	0.303	0.221	0.176	0.148	0.128	0.114	0.102	0.093	0.086
0.7	0.532	0.315	0.231	0.186	0.157	0.137	0.122	0.110	0.101	0.093
0.8	0.542	0.326	0.243	0.196	0.167	0.146	0.130	0.118	0.109	0.100
0.9	0.552	0.338	0.254	0.207	0.177	0.156	0.140	0.127	0.117	0.109
1.0	0.603	0.376	0.285	0.235	0.202	0.178	0.160	0.147	0.135	0.126
1.1	0.646	0.410	0.315	0.261	0.225	0.200	0.181	0.166	0.153	0,143
1.2	0.692	0.448	0.347	0.290	0.252	0.225	0.204	0.187	0.174	0.163
1.3	0.741	0.488	0.383	0.322	0.281	0.252	0.230	0.212	0.197	0,185
1.4	0.794	0.533	0.422	0.357	0.314	0.283	0.259	0.240	0.224	0.211
1.5	0.851	0.581	0.465	0.397	0.351	0.318	0.292	0.271	0.254	0.240
1.6	0.912	0.623	0.498	0.425	0.376	0.340	0.313	0.291	0.272	0.257
1.7	0.977	0.667	0.534	0.456	0.403	0.365	0.335	0.311	0.292	0.275
1.8	1.047	0.715	0.572	0.489	0.432	0.391	0.359	0.334	0.313	0.295
1.9	1.122	0.766	0.613	0.523	0.463	0.419	0.385	0.358	0.335	0.316
2.0	1.202	0.821	0.657	0.561	0.496	0.449	0.412	0.383	0.359	0.339
2.1	1.288	0.880	0.704	0.601	0.532	0.481	0.442	0.410	0.385	0.363
2.2	1.380	0.943	0.754	0.644	0.570	0.515	0.473	0.440	0.412	0.389
2.3	1.479	1.010	0.808	0.690	0.610	0.552	0.507	0.471	0.442	0.417
2.4	1.585	1.083	0.866	0.739	0.654	0.592	0.543	0.505	0.473	0.447
2.5	1.698	1.160	0.926	0.792	0.701	0.634	0.582	0.541	0.507	0.479
2.6	1.820	1.243	0.994	0.849	0.751	0.679	0.624	0.580	0.543	0.513
2.7	1.950	1.332	1.066	0.910	0.805	0.728	0.669	0.521	0.582	0.550
2.8	2.089	1.427	1.142	0.975	0.862	0.780	0.716	0.666	0.624	0.589
2.9	2.239	1.529	1.223	1.044	0.924	0.836	0.768	0.713	0.669	0.631
3.0	2.399	1.638	1.311	1.119	0.990	0.895	0.823	0.764	0.716	0.676

Note - Values computed from Equation 6 in Bulletin 17B, reference (46).

Table F-11

OUTLIER TEST K VALUES (10 PERCENT SIGNIFICANCE LEVEL)

Sample	Outlier	Sample	Outlier	Sample	Outlier	Sample	Outlier
Size	K Value	Size	K Value	Size	K Value	Size	K Value
10	2 036	, =	0 707	80	2.940	115	2 0//
11	2.036 2.088	45 46	2.727 2.736	80 81	2.940	115	3.064
12	2.088	46 47	2.736	82	2.943	116	3.067
13	2.134	48	2.753	83	2.949	117 118	3.070 3.073
14	2.213	48 49	2.760	84	2.957	119	3.075
14	2.213	47	2.700	04	2.337	119	3.073
15	2.247	50	2.768	85	2.961	120	3.078
16	2.279	51	2.775	86	2.966	121	3.081
17	2.309	52	2.783	87	2.970	122	3.083
18	2.335	53	2.790	88	2.973	123	3.086
19	2.361	54	2.798	89	2.977	124	3.089
20	2.385	55	2.804	90	2.981	125	3.092
21	2.408	56	2.811	91	2.984	126	3.095
22	2.429	57	2.818	92	2.989	127	3.097
23	2.448	58	2.824	93	2.993	128	3.100
24	2.467	59	2.831	94	2.996	129	3.102
25	2.486	60	2.837	95	3.000	130	3.104
26	2.502	61	2.842	96	3.003	131	3.104
27	2.519	62	2.849	97	3.006	132	3.107
28	2.534	63	2.854	98	3.011	133	3.112
29	2.549	64	2.860	99	3.014	134	3.114
30	2.563	65	2.866	100	3.017	135	3.116
31	2.577	66	2.871	101	3.021	136	3.119
32	2.591	67	2.877	102	3.021	137	3.122
33	2.604	68	2.883	103	3.024	138	3.124
34	2.616	69	2.888	104	3.030	139	3.126
	2.020	0,	2.000	104	3.030	13,	3.120
35	2.628	70	2.893	105	3.033	140	3.129
36	2.639	71	2.897	106	3.037	141	3.131
37	2.650	72	2.903	107	3.040	142	3.133
38	2.661	73	2.908	108	3.043	143	3.135
39	2.671	74	2.912	109	3.046	144	3.138
40	2.682	75	2.917	110	3.049	145	3.140
41	2.692	76	2.922	111	3.052	146	3.142
42	2.700	77	2.927	112	3.055	147	3.144
43	2.710	78	2.931	113	3.058	148	3.146
44	2.719	79	2.935	114	3.061	149	3.148

Note - Table contains one sided 10% significance level deviates for the normal distribution. Source: Appendix 4, Bulletin 17B, reference (46).

Table F-12

BINOMIAL RISK TABLES

Tables are probabilities of binomial risk for various exceedance frequencies and record lengths.

		10	0.0 Perce	ent Chane	ce Excee	dance Eve	ent	
Number of			<del>-</del>	th of Per				
Exceedances	10	20	30	40	50	60	80	100
0	. 3487	.1216	.0424	.0148	.0052	.0018	.0002	.0000
1	. 3874	. 2702	.1413	.0657	.0286	.0120	.0019	.0003
2	.1937	. 2852	. 2277	. 1423	.0779	.0393	.0085	.0016
3	. 0574	. 1901	.2361	. 2003	.1386	. 0844	.0246	.0059
4	.0112	. 0898	.1771	. 2059	.1809	.1336	.0527	.0159
5	.0015	.0319	.1023	.1647	.1849	.1662	.0889	.0339
6	.0001	.0089	.0474	. 1068	.1541	.1693	.1235	.0596
7	.0000	.0020	.0180	.0576	.1076	. 1451	.1451	.0889
8	.0000	.0004	.0058	.0264	.0643	.1068	.1471	.1148
9	.0000	.0001	.0016	.0104	.0333	.0686	.1308	.1304
10	.0000	.0000	. 0004	.0036	.0152	.0389	. 1032	.1319

			5.0 Perc	ent Chan	ce Excee	dance Eve	ent	
Number of					riod in			
Exceedances	10	20	30	40	50	_60	80	100
0	. 5987	. 3585	. 2146	. 1285	. 0769	.0461	.0165	.0059
1	.3151	. 3774	. 3389	. 2706	. 2025	. 1455	.0695	.0312
2	.0746	.1887	. 2586	. 2777	.2611	. 2259	.1446	.0812
3	.0105	.0596	.1270	.1851	.2199	.2298	.1978	.1396
4	.0010	.0133	.0451	.0901	.1360	.1724	. 2004	.1781
5	.0001	.0022	.0124	.0342	. 0658	.1016	.1603	.1800
6	.0000	.0003	.0027	.0105	.0260	.0490	.1055	. 1500
7	.0000	.0000	.0005	.0027	.0086	.0199	. 0587	.1060
8	.0000	.0000	.0001	.0006	.0024	.0069	.0282	.0649
9	.0000	.0000	.0000	.0001	.0006	.0021	.0119	.0349
10	.0000	.0000	.0000	.0000	.0001	.0006	. 0044	.0167

Table F-12 (Cont)

# **BINOMIAL RISK TABLES**

# Tables are probabilities of binomial risk for various exceedance frequencies and record lengths.

			2.0 Perc	<u>ent Chan</u>	<u>ce Excee</u>	<u>dance Ev</u>	ent	
Number of			Leng	th of Pe	riod in	Years		
Exceedances	10	20	30	40_	50	60	80	10
0	.8171	.6676	. 5455	. 4457	. 3642	. 2976	. 1986	.13
1	.1667	. 2725	. 3340	.3638	.3716	. 3644	. 3243	. 27
2	.0153	. 0528	. 0988	.1448	.1858	.2194	.2614	. 27
3	.0008	.0065	.0188	.0374	.0607	.0865	.1387	.18
4	.0000	. 0006	.0026	.0071	.0145	.0252	. 0545	. 09
5	.0000	.0000	.0003	.0010	.0027	.0058	.0169	.03
6	.0000	.0000	. 0000	.0001	. 0004	.0011	.0043	.01
7	.0000	.0000	.0000	.0000	.0001	.0002	.0009	.00
8	.0000	.0000	.0000	.0000	.0000	.0000	.0002	.00
9	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.00
10	.0000	.0000	.0000	.0000	.0000	.0000	.0000	. 00

Number				ent Chan				
of			Leng	th of Per	riod in '	Years		
Exceedances	10	20	30	40	50	60	80	10
0	. 9044	. 8179	. 7397	. 6690	. 6050	. 5472	. 4475	. 36
1	.0914	.1652	. 2242	. 2703	.3056	.3316	.3616	. 36
2	.0042	.0159	.0328	.0532	.0756	.0988	.1443	. 18
3	.0001	.0010	.0031	.0068	.0122	.0193	.0379	. 06
4	.0000	.0000	.0002	.0006	.0015	.0028	.0074	.01
5	.0000	.0000	.0000	.0000	.0001	.0003	.0011	.00
6	.0000	.0000	.0000	.0000	.0000	.0000	.0001	.00
7	.0000	. 0000	. 0000	.0000	.0000	.0000	.0000	. 00
8	.0000	. 0000	.0000	.0000	.0000	.0000	.0000	.00
9	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.00
10	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.00

Table F-12 (Cont)

# **BINOMIAL RISK TABLES**

Tables are probabilities of binomial risk for various exceedance frequencies and record lengths.

			.5 Perce	ent Chan	ce Excee	<u>dance Eve</u>	ent	
Number of			Leng	th of Per	riod in	Years		
Exceedances	10	20	30	40	50	60	80	100
0	.9511	. 9046	. 8604	.8183	.7783	.7403	. 6696	. 6058
1	.0478	. 0909	.1297	.1645	.1956	.2232	. 2692	. 3044
2	.0011	. 0043	. 0095	.0161	.0241	.0331	.0534	.0757
3	.0000	.0001	. 0004	.0010	.0019	.0032	.0070	.0124
4	.0000	.0000	.0000	.0000	.0001	.0002	.0007	.0015
5	.0000	. 0000	.0000	.0000	.0000	.0000	.0001	.0001
6	. 0000	. 0000	.0000	.0000	. 0000	.0000	.0000	.0000
7	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
8	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
9	. 0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
10	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000

Number of	Length of Period in Years							
0	. 9802	. 9608	. 9417	. 9230	. 9047	. 8868	. 8520	. 8186
1	.0196	.0385	. 0566	.0740	.0907	.1066	.1366	.1640
2	.0002	.0007	.0016	.0029	. 0045	.0063	.0108	.0163
3	.0000	.0000	.0000	.0001	.0001	.0002	.0006	.0011
4	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0001
5	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
6	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
7	.0000	.0000	.0000	.0000	. 0000	.0000	.0000	.0000
8	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
9	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000
10	.0000	.0000	.0000	.0000	.0000	.0000	.0000	.0000