

OPERATOR'S MANUAL
MEDIUM GIRDER BRIDGE






Table of Contents
Page i



Equipment Data
Page 1-2



Bridge Tables
Page 2-1

Index
Page Index-1

This copy is a reprint which
includes current pages from
Change 1.

INCLUDING

BRIDGE SET

NSN 5420-00-172-3520

BRIDGE ERECTION SET

NSN 5420-00-172-3519

LINK REINFORCEMENT SET

NSN 5420-01-139-1503

DISTRIBUTION STATEMENT A: Approved for public release;
distribution is unlimited.

*This manual supersedes TM 5-5420-212-12, dated 18 April
1985, including all changes

HEADQUARTERS, DEPARTMENT OF THE
ARMY AND HEADQUARTERS U.S. MARINE
CORPS

29 JANUARY 1993

ARMY TM 5-5420-212-10-2
MARINE CORPS TM 08676A-10/1-2
C 1

CHANGE HEADQUARTERS
NO. 1 DEPARTMENT OF THE ARMY
AND HEADQUARTERS U.S.
MARINE CORPS
WASHINGTON, D.C., 30 July 1993

Operator's Manual
Medium Girder Bridge
Including
Bridge Set
NSN 5420-00-172-3520
Bridge Erection Set
NSN 5420-00-172-3519
LINK REINFORCEMENT SET
NSN 5420-01-139-1503

DISTRIBUTION STATEMENT A: Approved for
public release; distribution is unlimited.

TM 5-5420-212-10-2, dated 29 January 1993,
is changed as follows:

ARMY TM 5-5420-212-10-2
MARINE CORPS TM 08676A-10/1-2

C 1

1. Remove and insert pages as indicated below. New or changed text material is indicated by a vertical bar in the margin. An illustration change is indicated by a miniature pointing hand.

Remove pages

Insert pages

1-1 through
1-14

1-1 through
1-14


2. Retain this sheet in front of manual for reference purposes.

ARMY TM 5-5420-212-10-2
MARINE CORPS TM 08676A-10/1-2
C 1

**By order of the secretaries of the Army and Navy
(including the Marine Corps):**

GORDON R. SULLIVAN
General, United States Army
Chief of Staff

Official:



MILTON H. HAMILTON
Administrative Assistant to the
Secretary of the Army
05097

DAVID E. BOTTORFF
Rear Admiral, CEC, US Navy
Commander
Navy Facilities Engineering
Command

RONALD D. ELLIOTT
Executive Director
Marine Corps Systems Command

DISTRIBUTION:

To be distributed in accordance with DA Form 12-25-E,
block no. 6019. requirements for TM 5-5420-212-10-2.

WARNING

Death or severe injury to personnel and damage to property may result if personnel fail to observe safety precautions.

Use extreme caution when connecting bridge bays. Make sure of secure footing to prevent severe injury or death to personnel.

During bridge assembly and disassembly, before removing captive pins to change heights, a panel pin must be placed through the nose roller and launching nose to prevent the nose from rolling.

Personnel will not use carrying bars to boom the bridge. Carrying bars can forcefully strike/crush personnel if the bridge were to run out of control into the gap.

A vehicle is always required for launching and de-launching. Launching/delaunching by hand can result in personnel losing control and the bridge crashing into the gap.

Personnel must be down off the bridge and out of the bridge interior during booming, launching and de-launching.

Use caution when connecting bridge bays. Do not put fingers or hands into pin holes or between components being moved or connected. Make sure of secure footing and use correct lifting procedures.

Never raise or lower one end of bridge unless the other end is fixed on locked rollers, on the ground, or secured to a vehicle (when on capsill or front roller beams).

a/(b blank)

REPORTING ERRORS AND RECOMMENDING IMPROVEMENTS

You can help improve this manual. If you find any mistakes or if you know of a way to improve these procedures, please let us know. Mail your letter or DA Form 2028 (Recommended Changes to Publications and Blank Forms), or DA Form 2028-2 directly to: Commander, US Army Aviation and Troop Command, ATTN: AMSAT-I-MTS, 4300 Goodfellow Blvd., St. Louis, MO 63120-1798.

Marine Corps - By NAVMC Form 10772 directly to: Commander, Marine Corps Logistics Base, ATTN: Code 850, Albany, GA 31704-5000.

A reply will be furnished directly to you.

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

TABLE OF CONTENTS

	PAGE
CHAPTER 1 INTRODUCTION	1-1
1-1 SCOPE	1-1
1-2 EQUIPMENT DATA	1-2
CHAPTER 2 BRIDGE TABLES	2-1

*This manual supersedes TM 5-5420-212-12, dated 18 April 1985, including all changes

Table	Page
2-1 Building and Boom Table 4 through 8 Bay Single Story (Normal site)	2-2
2-2 Building and Boom Table 9 through 12 Bay Single Story (Normal Site)	2-4
2-3 Building and Boom Table 9 through 12 Bay Single Story (Restricted Site)	2 6
2-4 Delaunch Table 4 through 8 Bay Single Stay (Normal Site)	2-6
2-5 Delaunch Table 9 through 12 Bay Single Story (Normal Site)	2-10
2-6 Delaunch Table 9 through 12 Bay Single Story (Restricted Site)	2-12
2-7 Building and Boom Table 2E + 1 through 2E + 6 Bay Double Story (Normal Site)	2-14
2-8 Building and Boom Table 2E + 7 through 2E + 12 Bay Double Story (Normal Site)	2-16
2-9 Building and Boom Table 2E + 13 through 2E + 17 Bay Double Story (w/o LRS) (Normal Site)	2-18

Table	Page
2-10 Building and Boom Table 2E + 18 through 2E + 22 bay Double Story (w/o LRS) (Normal Site)	2-20
2-11 Building and Boom Table 2E + 1 through 2E + 3 Bay Double Story (Restricted Site)	2-22
2-12 Building and Boom Table 2E + 4 through 2E + 6 Bay Double Story (Restricted Site)	2-24
2-13 Building and Boom Table 2E + 7 through 2E + 9 Bay Double Story (Restricted site)	2-26
2-14 Building and Boom Table 2E + 10 through 2E + 12 Bay Double Story (Restricted site)	2-28
2-15 Delaunch Table 2E + 1 through 2E + 6 Bay Double Story (Normal site)	2-30
2-16 Delaunch Table 2E + 7 through 2E + 12 Bay Double Story (Normal Site).....	2-32
2-17 Delaunch Table 2E + 13 through 2E + 17 Bay Double Story (w/o LRS) (Normal Site)	2-34
2-18 Delaunch Table 2E + 18 through 2E + 22 Bay Double Story (w/o LRS) (Normal Site).....	2-38

Table	Page
2-19 Delaunch Table 2E + 1 through 2E + 6 Bay Double Story (Normal Site - Original Far Bank)	2-38
2-20 Delaunch Table 2E + 7 through 2E + 12 Bay Double Story (Normal Site - Original Far Bank)	2-40
2-21 Delaunch Table 2E + 13 through 2E + 17 Bay Double Story (w/o LRS) (Normal Site - Original Far Bank)	2-42
2-22 Delaunch Table 2E + 18 through 2E + 22 Bay Double Story (w/o LRS) (Normal Site - Original Far Bank)	2-44
2-23 Delaunch Table 2E + 1 through 2E + 4 Bay Double Story (Restricted Site)	2-46
2-24 Delaunch Table 2E + 5 through 2E + 6 Bay Double Story (Restricted Site)	2-48
2-25 Delaunch Table 2E + 7 through 2E + 9 Bay Double Story (Restricted Site)	2-50
2-26 Delaunch Table 2E + 10 through 2E + 12 Bay Double Story (Restricted Site)	2-52
2-27 Delaunch Table 2E + 1 through 2E + 5 Bay Double Story (Restricted Site - Original Far Bank)	2-54

Table	Page
2-28 Delaunch Table 2E + 6 through 2E + 9 Bay Double Story (Restricted Site -Original Far Bank)	2-56
2-29 Delaunch Table 2E + through 2E + 12 Bay Double Story (Restricted Site - Original Far Bank)	2-59
2-30 Building and Boom Table 2E + 13 through 2E + 17 Bay Link Reinforced (Normal Site)	2-62
2-31 Building and Boom Table 2E + 18 through 2E + 22 Bay Link Reinforced (Normal Site)	2-64
2-32 Delaunch Table 2E + 13 through 2E + 17 Bay Link Reinforced (Normal Site)	2-67
2-33 Delaunch Table 2E + 18 through 2E + 22 Bay Link Reinforced (Normal Site)	2-69
2-34 Delaunch Table 2E + 13 through 2E + 17 Bay Link Reinforced (Normal Site - Original Far Bank)	2-72
2-35 Delaunch Table 2E + 18 through 2E + 22 Bay Link Reinforced (Normal Site - Original Far Bank)	2-75
2-36 V Distance 2E + 1 through 2E + 6 Bay Double Story Bridges (Normal and Restricted Sites).	2-78

Table	Page
2-37 V. Distance 2E + 7 through 2E + 12 Bay Double Story Bridges (Restricted Sites).	2-78
2-38 V. Distance 2E + 13 through 2E + 17 Bay Double Story Bridges (w/o LRS) - Normal and Restricted Sites.	2-79
2-39 V. Distance 2E + 18 through 2E + 22 Bay Double Story Bridges (w/o LRS) (Normal and Restricted Sites).	2-79
2-40 V. Distance 2E + 13 through 2E + 17 Bay Double Story Bridges (w/LRS) (Normal Site)	2-80
2-41 V. Distance 2E + 18 through 2E + 22 Bay Double Story Bridges (w/LRS) (Normal Site).	2-80
INDEX	Index-1

HOW TO USE THIS MANUAL.

The information in this manual is for the experienced MGB user. Component size, weight and quantities per set details are found in equipment data (Chapter 1), which is in alphabetical order for easy reference. The bridge tables (Chapter 2) are in two categories, build and boom (for assembly) and delaunch (for disassembly).

Once the type of bridge, bridge length and type of site have been determined, use the table of contents to find the appropriate table. Each table is presented so that the user reads vertically downwards under the bridge length column. In most cases the table is complete on facing pages for ease of use. In the tables, boom and launch are defined as

boom - moving the bridge to the RRB

launch - moving the bridge to the FRB (or CRB)

Abbreviations used in this manual are defined in TM 5-5420-212-10-1 Operator's Manual.

CHAPTER 1

INTRODUCTION

1-1	SCOPE
------------	--------------

This manual is for use by the experienced user during the assembly and disassembly of MGB. The equipment data (Chapter 1) provides useful component information. The bridge table (Chapter 2) are a summary of the stop by step procedures. It is important that the user is fully experienced and familiar with the standard drills and detailed procedures in Operator's Manual TM 5-5420-212-10-1. Do not attempt to use the tables until the standard drills and step by step procedures have been practiced a number of times.

Adjustable Support

Length 5 ft 5 in
(1.65 m)
Width 7 in (0.16 m)
Height 3 ft 8 in
(1.12 m)
weight 143 lb (65 kg)
Carried by 2 personnel
No. in set 6 (erection)
2 (link)

Anchor Assembly (AA)

Length 10 ft 9-1/2 in
(3.29 m)
Width 2 ft 3-5/8 in
(0.70 m)
Height 11-3/16 in
(0.28 m)
Weight 362 lb (164 kg)
Carried by 4 personnel
No. in set 5 (link)

Anchorage Pin Assembly

Length 2 ft 9-7/8 in
(0.88 m)
Diameter 1-3/4 in
(0.04 m)
Weight 26 lb (11.8 kg)
Carried by 1 person
No. in set 10 (link)

Anti-Flutter Tackle (AF)

Length 9 ft 10 in
(3.00 m)
Weight 4.4 lb (2 kg)
Carried by 1 person
No. in set 5 (link)

Bankseat Beam (BSB)

Length 13 ft 3-1/2 in
(4.06 m) overall
Width 1 ft 6 in
(0.48 m) overall
Height 1 ft 9-3/8 in
(0.54 m) overall
Weight 570 lb (256 kg)
Carried by 6 personnel
No. in set 7 (bridge)

Baseplate (Single Story)

Length 2 ft 3/8 in
(0.62 m)
Width 1 ft 5-1/4 in
(0.44 m)
Height 7-3/4 in
(0.20 m)
weight 32 lb (14.5 kg)
Carried by 1 person
No. in set 7 (erection)
4 (link)

Baseplate (Double Story)

Length 5 ft 4 in (1.63 m)
Width 1 ft 11 in
(0.58 m)
Height 6-3/4 in
(0.17 m)
Weight 93 lb (42 kg)
Carried by 2 personnel
No. in set 6 (erection)
4 (link)

Bottom Panel (BP)

Length 6 ft 5 in
(1.96 m) overall
6 ft (1.83 m)
effective
Width 2 ft 3 in
(0.69 m) overall
Height 3 ft 7-3/8 in
(1.1 m)
Weight 435 lb (197 kg)
Carried by 4 personnel
No. in set 26 (bridge)

Bracing Pin

Length 7-1/4 in
(0.18 m)
Diameter 1 in (2.54 cm)
Weight 1-1/2 lb
(0.68 kg)
68 (bridge)
Carried by 1 person
No. in set 8 (erection)
22 (link)

Bridge Marker Guide

Length 4 ft 5 in
(1.35 m) min.
5 ft 11 in
(1.80 m) max.
Weight 5-1/4 lb (2.4 kg)
Carried by 1 person
No. in set 24 (bridge)

Building Pedestal (BP)

Length 2 ft 1/2 in
(0.82 m)
Width 1 ft 7 in (0.48 m)
Height 1 ft 4 in (0.41 m)
Weight 16 lb (7.25 kg)
Carried by 1 person
No. in set 7 (erection)

Capsill

Length 15 ft 5-7/16 in
(4.71 m)
Width 2 ft 6 in (0.376 m)
Height 1 ft 2-5/8 in
(0.37 m)
weight 400 lb (181 kg)
Carried by 6 to 8 personnel
No. in set 1 (link)

Capsill Pin

Length 1 ft 8-1/2 in
(0.52 m)
Diameter 1-1/2 in
(0.04 m)
Weight 10 lb (4.5 kg)
carried by 1 person
No. in set 3 (link)

Change 1 1-3

Carrying Bar

Length 2 ft 4-1/2 in
(0.72 m)
Diameter 1-3/4 in
(0.04 m)
weight 4 lb (1.8 kg)
Carried by 1 person
No. in set 46 (erection)

Carrying Handle

Length 1 ft 3/8 in
(0.31 m)
Width 5-1/2 in
(0.14 m)
weight 1.25 lb (0.56 kg)
Carried by 1 person
No. in set 46 (erection)

Curb

Length 5 ft 11 in (1.8 m)
Width 5-3/8 in
(0.14 m)
Height 1 ft 1-1/2 in
(0.34 m)
Weight 70 lb (32 kg)
Carried by 1 person
No. inset 42 (bridge)

Davit Post Assembly

Length 9 ft 5-7/8 in
(2.89 m)
Width 5 ft 5-3/16 in
(1.66 m)
Height 11-7/8 in
(0.30 m)
Weight 192 lb (87 kg)
Carried by 4 personnel
No. in set 2 (link)

Deck

Length 9 ft 1 in
(2.77 m) overall
Width 1 ft 5-1/4 in
(0.44 m) overall
Height 6-7/8 in
(0.17 m)
Weight 163 lb (74 kg)
Carried by 2 personnel
No. in set 74 (bridge)

End Taper Panel (ETP)

Length 13 ft 2-5/8 in
(4.03 m) overall
Width 2 ft 4 in (0.71 m)
Height 1 ft 5-3/4 in
(0.45 m)
Weight 600 lb (272 kg)
Carried by 6 personnel
No. in set 5 (bridge)

Equipment Bag

Length 1 ft 2 in (0.36 m)
Width 10 in (0.25 m)
Weight 5/8 lb (0.28 kg)
Carried by 1 person
No. in set 8 (bridge)
2 (erection)
2 (link)

Equipment Basket

Length 4 ft 9 in (1.45 m)
Width 1 ft 3 in (0.38 m)
Height 1 ft (0.30 m)
Weight 62 lb
(28 kg) (empty)
Carried by 2 personnel
No. in set 14 (bridge)
6 (erection)
4 (link)

Extractor Cable

Length 20 ft (6.10 m)
Weight 22 lb (10 kg)
Carried by 1 person
No. in set 1 (erection)

Fixed Support

Length 1 ft 4-1/2 in
(0.42 m)
Width 1 ft (0.3 m)
Height 9-1/2 in
(0.24 m)
Weight 14 lb (6.35 kg)
Carried by 1 person
No. in set 7 (erection)

Footwalk

Length 5 ft 11-7/8 in
(1.83 m)
Width 2 ft 2-7/8 in
(0.68 m)
Depth 2-11/16 in
(0.07 m)
Weight 54 lb (2405 kg)
Carried by 1 person
No. in set 5 (link)

Footwalk Bearer

Length 5 ft 3/8 in
(1.53 m)
Width 2-3/4 in
(0.07 m)
Depth 7-3/4 in
(0.20 m)
Weight 17 lb (7.7 kg)
Carried by 1 person
No. in set 10 (link)

Change 1 1-5

Footwalk Post

Length 4 ft 3/8 in
(1.23 m)
Width 3-13/16 in
(0.94 m)
Depth 2-15/16 in
(0.75 m)
Weight 2.6 lb (1.2 kg)
Carried by 1 person
No. in set 8 (link)



Frame Cross Girder

Length 14 ft 3-1/4 in
(4.35 m)
Width 1 ft 8 in (0.51 m)
Height 1 ft 3 in (0.36 m)
Weight 171 lb (77.5 kg)
Carried by 2 personnel
No. in set 3 (erection)



Guard Rope

Length 30 ft (9.14 m)
Weight 2 lb (0.9 kg)
Carried by 1 person
No. in set 4 (link)



Hammer

weight 1.5 lb (0.7 kg)
Carried by 1 person
No. in set 6 (link)



Headless Panel Pin

Length 2 ft 5 in (0.74 m)
Diameter 1-3/4 in
(4.44 in)
Weight 19 lb (6.62 kg)
Carried by 1 person
No. in set 5 (bridge)
1 (link)



Hydraulic Jack 15T

Height 1 ft 7 in (0.48 m)
minimum
2 ft 8 in (0.81 m)
extended
Weight 47 lb (21 kg)
Carried by 1 person
No. in set 7 (erection)



Hydraulic Jack 20T

Height 1 ft 6-1/2 in
(0.47 m)
minimum
2 ft 6-1/2 in
(0.76 m)
extended
Weight 47 lb (21 kg)
Carried by 1 person
No. in set 2 (link)



Jack Post

Length 2 ft 10-3/4 in
(0.66 m)
Width 6 in (0.15 m)
Height 11 in (0.26 m)
Weight 43 lb (19.5 kg)
Carried by 1 person
No. in set 4 (erection)

Jack Seat

Length 9-1/4 in
(0.23 m)
Width 1 ft (0.3 m)
Height 5 in (0.13 m)
Weight 6 lb (2.7 kg)
Carried by 1 person
No. in set 5 (erection)
2 (link)

Jack Support

Length 1 ft 3 in (0.38 m)
Width 9 in (0.23 m)
Height 10-1/2 in
(0.26 m)
Weight 12 lb (5.5 kg)
Carried by 1 person
No. in set 5 (erection)

Jacking Bracket

Length 4 ft 8-1/2 in
(1.44 m)
width 1 ft 2-7/16 in
(0.36 m)
Height 1 ft 6 in (0.46 m)
Weight 135 lb (61.2 kg)
Carried by 2 personnel
No. in set 3 (link)

Junction Panel (JP)

Length 3 ft 5-1/4 in
(1.05 m) overall
3 ft (0.91 m)
effective
width 2 ft 1-1/2 in
(0.66 m)
Height 5 ft 3/4 in
(1.54 m)
Weight 478 lb (217 kg)
Carried by 4 personnel
No. in set 5 (bridge)

Landing Roller (LR)

Length 1 ft 4 in (0.4 m)
Width 1 ft 10-1/2 in
(0.57 m)
Height 11 in (0.26 m)
Weight 61 lb (27.7 kg)
Carried by 1 person
No. in set 4 (erection)
1 (link)

**Landing Roller Pedestal
Mk 1 (LRP)**

Length 5 ft 7 in (1.7 m)
Width 2 ft 6-5/8 in
(0.6 m)
Height 1 ft 2-1/2 in
(0.37 m)
Weight 215 lb (97.5 kg)
Carried by 4 personnel
No. in set 2 (erection)

**Landing Roller Pedestal
Mk 2 (LRP)**

Length 5 ft 7 in (1.7 m)
Width 2 ft 6-5/8 in
(0.78 m)
Height 1 ft 2-1/2 in
(0.37 m)
Weight 218 lb (99 kg)
Carried by 4 personnel
No. in set 3 (link)

**Launching Nose Cross
Girder (LNCG)**

Length 8 ft 7-1/2 in
(2.63 m)
Width 10-1/4 in
(0.26 m)
Height 1 ft 6 in (0.46 m)
Weight 157 lb (71 kg)
Carried by 2 personnel
No. in set 2 (erection)

**Launching Nose Cross
Girder Post**

Length 5 ft 10 in (1.8 m)
Width 4 in (0.1 m)
Height 7-1/4 in
(0.16 m)
Weight 32 lb (14.5 kg)
Carried by 1 person
No. in set 4 (erection)

**Launching Nose Heavy
(LNH)**

Length 10 ft 4-3/4 in
(3.17 m) overall
10 ft (3.05 m)
effective
Width 1 ft 6 in (0.46 m)
Height 2 ft 1 in (0.63 m)
Weight 386 lb (175 kg)
carried by 4 personnel
No. in set 8 (erection)
6 (link)

**Launching Non Link
(LNL)**

Length 2 ft 7 in (0.79 m)
Width 6 in (0.15 m)
Carried by 1 person
No. in set 3 (link)

Launching Nose Pin

Length 1 ft 5-1/8 in
(0.44 m)
Diameter 1-1/4 in
(0.03 m)
Weight 6 lb (2.72 kg)
Carried by 1 person
No. in set 23 (bridge)
40 (link)

Launching Nose Roller (LNR)

Height 2 ft 9-3/4 in
(0.66 m)
Width 2 ft in (0.64 m)
Depth 7 in (0.16 m)
Weight 62 lb (28 kg)
Carried by 1 person
No. in set 2 (erection)

Lifting Sling

Length 16 ft (4.88 m)
Weight 150 lb (68 kg)
Canted by 2 personnel
No. in set 1 (erection)

Light Launching Nose Front (LLNF)

Length 10 ft (3.05 m)
Width 1 ft 1-1/4 in
(0.34 m)
Height 8-1/4 in
(0.21 m)
Weight 97 lb (44 kg)
Carried by 2 personnel
No. in set 5 (erection)

Light Launching Nose Rear (LLNR)

Length 10 ft 5 in
(3.17 m) overall
10 ft (3.05 m)
T e x t
Width 1 ft 1-1/4 in
(0.34 m)
Height 2 ft (0.61 m)
Weight 148 lb (67 kg)
Carried by 2 personnel
No. in set 5 (erection)

Light Tackle (LT)

Length 25 ft (7.62 m)
Weight 2 lb (0.9 kg)
Carried by 1 person
No. in set 20 (link)

Long Ramp

Length 14 ft 1/2 in
(4.28 m) overall
14 ft (4.27 m)
effective
Width 1 ft 10 in
(0.58 m) overall
Height 1 ft (0.3 m)
Weight 400 lb (181 kg)
carried by 4 personnel
No. inset 15 (bridge)

Change 1 1-9

Long Reinforcing Link

Length 12 ft 3-1/2 in
(3.75 m)
Width 1 ft 2-1/16 in
(0.36 m)
Depth 3-15/16 in
(0.10 m)
Weight 125 lb (57 kg)
Carried by 2 personnel
No. in set 20 (link)



Longitudinal Girder

Length 14 ft 4-1/2 in
(4.38 m)
Width 1 ft 7-3/4 in
(0.50 m) overall
Height 5-1/4 in
(0.13 m)
Weight 109 lb (49 kg)
Carried by 2 personnel
No. in set 3 (erection)



Packing Timber

(For use under bridge as

packing to increase
Dim'ns 3 in x 8 in x 36 in
(0.06 x 0.2 x
0.9 m)
Weight 20 lb (9.1 kg)
No. in set 144 (erection)



(For use in packing skid
when constructing bridges
with LRS)

Dim'ns 3 in x 8 in x 84 in
(0.08 x 0.2 x
2.13 m)
Weight 50 lb (22.7 kg)
No. in set 4 (link)



Pallet

Length 14 ft 3 in
(4.34 m) overall
14 ft (4.27 m)
effective
Width 6 ft 9-1/4 in
(2.08 m) overall
6 ft 4 in (1.93 m)
effective
Height 1 ft (0.30 m)
Weight 710 lb (322 kg)
Carried by 8 personnel
(minimum)
No. in set 11 (bridge)
3 (erection)
2 (link)



Pallet Adapter

Length	9 ft 1 in (2.77 m)
Width	4 ft 10 in (1.47 m)
Height	10 in (0.25 m)
Weight	400 lb (181 kg)
Carried by	4 personnel
No. in set	12 (Midge) 1 (link)

Panel Erection Aid

Length	7 ft (2.1 m)
Width	1 ft 11-3/4 in (0.60 m)
Height	1 ft (0.30 m)
Weight	69 lb (31.3 kg)
Carried by	2 personnel
No. in set	3 (erection)

Panel Pin

Length	2 ft 4-1/2 in (0.72 m)
Diameter	1-3/4 in (4.44 cm)
Weight	19 lb (8.62 kg)
Carried by	1 person
No. in set	92 (bridge) 20 (erection)

Post Tensioning Assembly (PT)

Length	9 ft 4-1/16 in (2.65 m)
Width	2 ft 3-3/4 in (0.71 m)
Height	2 ft 10-1/16 in (0.87 m)
Weight	657 lb (298 kg)
Carried by	6 personnel
No. in set	4 (link)

Puller

Length	1 ft 10-1/2 in (0.57 m)
Weight	33 lb (15 kg)
Carried by	1 personnel
No. in set	2 (link) (for davit posts and jacking brackets)

Push Bar Adapter

Length	4 ft 3 in (1.30 m)
width	1 ft 3/4 in (0.32 m)
Height	3-1/4 in (0.08 m)
Weight	100 lb (45 kg)
Carried by	2 personnel
No. in set	2 (erection)

**Push Bar cross Girder
(PBCG)**

Length 9 ft 3-1/4 in
(2.63 m)
Width 6 in (0.15 m)
Depth 10 in (0.25 m)
Weight 86 lb (39 kg)
Carried by 2 personnel
No. in set 2 (erection)

Push Bar Long (PB)

Length 15 ft 8-3/16 in
(4.78 m)
Width 4-5/8 in
(0.12 m)
Depth 4-1/16 in
(0.10 m)
Weight 119 lb (54 kg)
Carried by 2 personnel
No. in set 2 (link)

Push Bar Short (PB)

Length 10 ft 7-1/4 in
(3.23 m)
Width 4 in (0.1 m)
Depth 4 in (0.1 m)
weight 95 lb (43 kg)
Carried by 2 personnel
No. in set 2 (erection)

Ratchet Wrench 3/4 in

Length 1 ft 10-1/2 in
(0.57 m)
Weight 5 lb (2.3 kg)
Carried by 1 person
No. in set 3 (link)

Retainer Clip

Length 4-118 in (0.1 m)
Weight (bag of 50)
2 lb (0.91 kg)
Carried by 1 person
No. in set 200 (bridge)
56 (erection)
150 (link)

Rocking Roller

Length 2 ft 1-9/16 in
(0.65 m)
Width 2 ft 11-7/16 in
(0.90 m)
Height 1 ft 1-11/16 in
(0.35 m)
Weight 235 lb (107 kg)
Carried by 4 personnel
No. in set 3 (link)

Roller Beam (RB)

Length 15 ft 5-1/2 in
(4.71 m)
Width 11 in (0.28 m)
Height 1 ft 5-7/8 in
(0.45 m)
Weight 320 lb (145 kg)
Carried by 4 personnel
No. in set 4 (erection)

Rubber Bumper

Weight 86 lb (39 kg)
carried by 1 person
No. in set 25 (erection)
2 (link)
11 (bridge)

Short Ramp

Length 10 ft 1/2 in
(3.06 m) overall
10 ft (3.05 m)
effective
Width 1 ft 10 in
(0.56 m) overall
Height 9-1/4 in
(0.24 m)
Weight 264 lb (120 kg)
Carried by 4 personnel
No. in set 29 (bridge)

Short Reinforcing Link

Length 6 ft 3-1/2 in
(1.92 m)
Width 1 ft 2-1/16 in
(0.36 m)
Depth 3-15/16 in
(0.10 m)
weight 77.5 lb (35 kg)
Carried by 2 personnel
No. in set 4 (link)

Strap, 5,000 lb

Length 21 ft 8 in
(6.60 m)
Weight 4 lb (1.81 kg)
Carried by 1 person
No. in set 8 (bridge)
8 (link)
8 (erection)

Strap, 10,000 lb

Length 23 ft (7.01 m)
Weight 6 lb (2.72 kg)
Carried by 1 person
No. in set 18 (bridge)
18 (link)
18 (erection)

Sway Brace

Length 10 ft 1-3/4 in
(3.09 m)
Diameter 3-3/8 in
(8.57 cm)
Weight 36 lb (18 kg)
Carried by 1 person
No. in set 19 (bridge)

Tie-Down Lug

Length 7-1/4 in
(0.18 m)
Width 4 in (0.91 m)
Weight 2 lb (1 kg)
Carried by 1 person
No. in set 12 (bridge)
12 (link)
12 (erection)

Top panel

Length 6 ft in (1.93 m)
overall
6 ft (1.83 m)
effective
Width 2 ft 1-1/2 in
(0.65 m) overall
Height 1 ft 9-5/8 in
(0.55 m)
Weight 385 lb (175 kg)
Carried by 4 personnel
No. in set 34 (bridge)

CHAPTER 2
BRIDGE TABLES



**TABLE 2-1 Building and Boom Table - 4 through 8 Bay
Single Story (Normal site)**

Bridge ft. Length m.	26 7.9	32 9.8	38 11.6	44 13.4	50 15.2
Bays	4	5	6	7	8
L/Nose	LLN	LLN	LLN	LLN	LLN
Build	Notes a, b, c, d	Notes a, b, c, d	Notes a, b, c, d	Notes a, b, c, d	Notes a, b, c, d
Boom Add	1p2 3	1p2 3	1p2 3	1p2 3	1p2 3
Boom Add	1p7 4	1p7 4	1p7 4	1p7 4	1p7 4
Boom Add	2p3 BSB	2p3 5	2p3 5	2p3 5	2p3 5
Boom Add		2p7 BSB	2p7 6	2p7 6	2p7 6
Boom Add			3p3 BSB [5D]	3p3 7	3p3 7
Boom Add				3p7 [8]	3p7 8
Boom Add				4p3 [BSB, 4D]	4p3 [9]
Boom Add					4p7 [10]

Bays	4	5	6	7	8
Boom Add					5p3 [BSB, 5D]
Launch Add	(2p7) LR^	(3p3) LR^	(4p2) LR^	(5p2) LR^	(6p2) LR^
Launch				7p7 Notes g, h	8p7 Notes g, h
Launch				Note e	Note e
Complete by	Notes e, f, i	Notes e, f, i	Notes e, f, i	Note i	Note i

NOTES:

- a. Build BSB. LLN. Bay 1 and jackpost on BP and RB.
 - b. Boom to center hole of BSB over RB.
 - c. Put BP under 1p7
 - d. Add Bay 2 and put BP under 2p4.
 - e. Launch until far bank end of bridge is 9 in (23 cm) from LR or RBSB overhangs RB by 1.5 ft (0.5 m). If minimum bearing is to be used, launch to center hole in BSB.
 - f. Remove front section of LLN before push launch.
 - g. Move counterweight deck units into final position.
 - h. Remove counterweight panels and refit BSB from temporary counterweight position to normal position.
 - i. Put bridge on ground.
- ^ Position LR 9 in (23 cm) from F peg.
- [] Counterweight. (Counterweight BSB connected by shootbolts only).
- () Center of gravity.

**TABLE 2-2 Building and Boom Table - 9 through 12 Bay
Single Story (Normal Site)**

Bridge ft Length m	56 17.1	62 18.9	68 20.7	74 22.6
Bays	9	10	11	12
L/Nose	5N1	5N1	6N1	6N1
Build	Notes a, b, c, d	Notes a, b, c, d	Notes a, b, c, d	Notes a, b, c, d
Boom Add	1p2 Note e, f 4, 1N1* 5, 2N1 6, 3N1, 4N1, 5N1	1p2 Note e, f 4, 1N1* 5, 2N1 6, 3N1 4N1, 5N1	1p2 Note e, f 4, 1N1* 5, 2N1 6, 3N1 4N1, 5N1	1p2 Note e, f 4, 1N1* 5, 2N1 6, 3N1 4N1, 5N1
Boom Add		1p4 7	1p4 7, 6N1	1p4 7, 6N1
Boom Add		2p0 8		1p5 8
Boom Add				2p1 9
Launch Position	(1p5) LRP^	(2p4) LRP^	(1p5) LRP^	(2p7) LRP^
Launch Remove	6p5 Notes g, h	8p5 Notes g, h	7p5 Notes g, h	9p5 Notes g, h
Add	7, 8, 9 BSB	9, 10 BSB	8, 9, 10, 11 BSB	10, 11, 12 BSB
Compl. by	Note i, j	Note i, j	Note i, j	Note i, j

NOTES.

- a. Put BSB on RB.
- b. Add Bay 1 and put BP under 1 p7
- c. Fit nose roller.
- d. Add Bay 2 and put BP under 2p4.
- e. Add Bay 3 (with headless pin) and put BP at 3p7
- f. Add LNCG posts, LNCG. nose roller and LLN
- g. Remove LLN.
- h. Remove LNH sections as they pass LRP.
- i. Launch until far bank end of bridge is 9 in (23 cm) from LRP or BSB overhangs RB by 1.5 ft (0.5 m). If minimum bearing is being used, launch to center hole in BSB.
- j . Put bridge on the ground.
- () Position LRP 9 in (23 cm) from F peg.
- () Center of gravity
- * Add LRP and secure with tie down strap

**TABLE 2-3 Building and Boom Table - 9 through 12 Bay
Single Story (Restricted Site)**

Bridge ft Length m	56 17.1	62 18.9	68 20.7	74 22.6
Bays	9	10	11	12
L/Nose	6N1	6N1	7N1	7N1
Build	Notes a thru d	Notes a thru d	Notes a thru d	Notes a thru d
Add	Notes e, f 4 1N1*, 2N1 3N1 [2TP, 4D] 4N1, 5N1 [BSB] 6N1** LRP^	Notes e, f 4 1N1*, 2N1 3N1 [2TP, 4D] 4N1, 5N1 [BSB] 6N1** LRP^	Notes e, f 4 1N1*, 2N1 3N1 [4TP, 4D] 4N1, 5N1 [BSB], 6N1 7N1** LRP^	Notes e, f 4 1N1*, 2N1 3N1 [4TP, 4D] 4N1, 5N1 [BSB], 6N1 7N1** LRP^
Remove	[2TP, 4D]	[2TP, 4D]	[4TP, 4D]	[4TP, 4D]
Boom Remove	2p7 [BSB] Note g	2p7 [BSB] Note g	2p7 [BSB] Note g	2p7 [BSB] Note g
Boom Remove	4p5 Note h	4p5 Note h	4p5 Note h	4p5 Note h
Add	5, 6, 7, 8	5, 6, 7, 8	5, 6, 7, 8	5, 6, 7, 8
loom Add	8p5 9, BSB	8p5 9, 10, BSB	8p5 9, 10, 11 BSB	8p5 9, 10, 11, 12 BSB
Complete by	Note i, j, k	Note i, j, k	Note i, j, k	Note i, j, k

NOTES:

- a Put BSB on RB.
- b. Add Bay 1 and put BP under 1p7.
- c. Fit nose roller.
- d Add Bay 2 and put BP under 2p6.
- e Add Bay 3 (with headless pin) and put BP at 3p7.
- f. Add LNCG posts, LNCG, nose roller and LLN
- g Place BSB to side of site near rear of bridge
- h Remove nose sections as they pass LRP, observing 5 ft (1.5 m) minimum overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground
- i. Launch until far bank end of bridge is 9 in (23 cm) from LRP or BSB overhangs RB by 1.5 ft (0.5 m) If minimum bearing is being used, launch to center hole in BSB
- j. Lower LRP, remove last 3 LNH
- k. Put Bridge on the ground
- ^ Position LRP 9 in (23 cm) from F peg.
- [] Counterweight. (Counterweight BSB connected by shootbolts only)
- () Center of gravity.
- * Add LRP and secure with tie down strap.
- ** Bridge will tip as nose is boomed

**TABLE 2-4 Delaunch Table. 4 through 8 Bay Single Story
(Normal Site)**

Bridge ft. Length m.	26 7.9	32 9.8	38 11.6	44 13.4	50 15.2
Bays	4	5	6	7	8
L/Nose	LLN	LLN	LLN	LLN	LLN
Build	Notes a, b, c, d, e	Notes a, b, c, d, e	Notes a, b, c, d, e	Note a, b	Note a, b
Remove				BSB	BSB
Add			[5D]	[8, BSB 4D] Notes c, d, e	[9,10 BSB, 5D] Notes c, d, e
Delaunch Recover	(2p7) LR	(3p3) LR	(4p2) LR	(5p2) LR	(6p2) LR
Boom Remove					5p3 [BSB 5D]
Boom Remove					4p7 [10]
Boom Remove				4p3 [BSB 4D]	4p3 [9]
Boom Remove				3p7 [8]	3p7 8
Boom Remove			3p3 BSB [5D]	3p3 7	3p3 7
Bowl Remove		2p7 BSB	2p7 6	2p7 6	2p7 6

Bays	4	5	6	7	8
Boom Remove	2p3 BSB	2p3 5	2p3 5	2p3 5	2p3 5
Boom Remove	1p7 4	1p7 4	1p7 4	1p7 4	1p7 4
Boom Remove	1p2 Note f 3	1p2 Note f 3	1p2 Note f 3	1p2 Note f 3	1p2 Note f 3
Boom Remove	BSB Note g 2	BSB Note g 2	BSB Note g 2	BSB Note g 2	BSB Note g 2
Boom Remove	Note h 1	Note h 1	Note h 1	Note h 1	Note h 1
Complete by:	Notes i, j	Notes i, j	Notes i, j	Notes i, j	Notes i, j

NOTES:

- a. Remove curbs, deck units and ramps.
 - b. Install RB under bridge min 1.5 ft (0.5 m) from tie end. If minimum bearing is being used, position RB under center hole in BSB.
 - c. Add LLN.
 - d. Install LR 9 in (23 an) from BSB.
 - e. Put BP as required to keep bridge off the ground.
 - f. Move BP to 2p7.
 - g. Move BP to 1p7.
 - h. BSB over BP.
 - i. Remove LLN.
 - j. Remove BSB. Clear site.
- [] Counterweight. (Counterweight BSB connected by shootbolts only).
- () Center of gravity

TABLE 2-5 Delaunch Table - 9 through 12 Say Single Story
(Normal Site)

Bridge ft Length m	56 17.1	62 18.9	68 20.7	74 22.6
Bays	9	10	11	12
L/Nose	5N1	5N1	6N1	6N1
Build	Notes a thru e	Notes a thru e	Notes a thru e	Notes a thru e
Delaunch Remove	6p5 BSB, 9, 8, 7	8p5 BSB, 10, 9	7p5 BSB, 11, 10 9, 8	9p5 BSB, 12, 11 10
Add	Note f	Note f	Note g	Note g
Delaunch Recover	(1p5) LRP	(2p4) LRP	(1p5) LRP	(2p7) LRP
Boom Remove		2p0 8		2p1 9
Boom Remove				1p5 8
Boom Remove		1p4 7	1p4 6N1, 7	1p4 6N1, 7
Boom Remove	1p2 5N1, 4N1 3N1, 6 2N1, 5 1N1, LLN, 4 Note h, 3	1p2 5N1, 4N1 3N1, 6 2N1, 5 1N1, LLN, 4 Note h, 3	1p2 5N1, 4N1 3N1, 6 2N1, 5 1N1, LLN, 4 Note h, 3	1p2 5N1, 4N1 3N1, 6 2N1, 5 1N1, LLN, 4 Note h, 3
Boom Remove	BSB Note i 2, 1	BSB Note i 2, 1	BSB Note i 2, 1	BSB Note i 2, 1
Compl. by	Note j	Note j	Note i	Note i

NOTES:

- a. Remove curbs, deck units and ramps.
- b. Install RB under bridge minimum 1.5 ft (0.5m) from and. If minimum bearing is being used, position RB under canter hole of BSB.
- c. Position canter of LR (in LRP) 8 ft (2.4 m) from BSB.
- d. Position BP as required to keep bridge off ground.
- e. Add LNCG posts, LNCG, nose roller and 3 LNH. Reposition LRP [base 9 in (23 cm) from BSB]. Add LNH 4.
- f. Add LNH5 and LLN.
- g. Add LNH5, LNH6 and UN.
- h. Move BP to 2p7. Remove nose roller, LNCG and LNCG posts.
- i. Move BP to 1p7
- j. Remove BSB, Clear site
- () Canter of gravity.

TABLE 2-6 Delaunch Table - 9 through 12 Bay Single Story
(Restricted Site)

Bridge ft Length m	56 17.1	62 18.9	68 20.7	74 22.6
Bays	9	10	11	12
L/Nose	6N1	6N1	7N1	7N1
Build	Notes a thru d	Notes a thru d	Notes a thru d	Notes a thru d
Delaunch Remove	8p5 BSB Note e 9	8p5 BSB Note e 10.9	8p5 BSB Note e 11, 10, 9	8p5 BSB Note e 12, 11, 10, 9
Add	Note f	Note f	Note f	Note f
Delaunch Remove	4p5 8, 7, 6, 5	4p5 6, 7, 6, 5	4p5 8, 7, 6, 5	4p5 8, 7, 6, 3
Add	[BSB]	[BSB]	[BSB]	[BSB]
Delaunch Add	1p0 Note g [2TP, 4D]	1p0 Note g [2TP, 4D]	1p0 Note g [4TP, 4D]	1p0 Note g [4TP, 4D]
Recover	LRP	LRP	LRP	LRP
Remove	6N1, BSB 5N1, 4N1 [2TP, 4D] 3N1, 2N1 1N1 4, LLN 3, 2, 1	6N1, BSB 5N1, 4N1 [2TP, 4D] 3N1, 2N1 1N1 4, LLN 3, 2, 1	7N1, 6N1 BSB 5N1, 4N1 [4TP, 4D] 3N1, 2N1 1N1 4, LLN 3, 2, 1	7N1, 6N1 BSB 5N1, 4N1 [4TP, 4D] 3N1, 2N1 1N1 4, LLN 3, 2, 1
Compl. by	Note h	Note h	Note h	Note h

NOTES:

- a. Remove curbs, deck units and ramps.
- b. Install RB under bridge minimum 1.5 ft (0.5 m) from end. If minimum bearing is being used, position RB under center hole of BSB.
- c. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
- d. Add LNCG posts, LNCG, nose roller and 3 LNH. Reposition LRP [base 9 in (23 cm) from BSB]. Add LNH 4.
- e. Place BSB to side of site near end of bridge.
- f. Add launching nose sections as required, observing minimum 5 ft (1.5 m) overhang.
- g. Position BP as required to keep bridge off ground.
- h. Remove BSB. clear site.
- [] Counterweight. (Counterweight BSB connected by shootbolts only).
- () Center of gravity,

TABLE 2-7 Building and Boom Table - 2E + 1 through
2E + 6 Bay Double Story (Normal Site)

Bridge ft length m	36 11.0	42 12.8	48 14.6	54 16.5	60 18.3	66 20.1
2E + Bays	1	2	3	4	5	6
L/Nose	2N1	3N1	3N1	3N1	4N1	4N1
w/RRB at: Add	1p2 Note a 2N1* E	1p2 Note a 2 3N1*	1p2 Note a 2, 3 3N1*	1p2 Note a 2, 3 3N1* 4	1p2 Note a 2, 3 4N1* 4	1p2 Note a 2, 3 4N1* 4
(CG)	(1p0)	(Bp5)	(Bp0)	(Ap2)	(Ap2)	(Ap2)
Boom Add (CG)		1p6 E (1p2)	2p4 E (1p6)	3p0 E (2p3)	3p0 5, E (2p5,	3p0 5, 6 (1p6)
Boom Add (CG)						4p0 E (3p1)
Launch Position LRP	(1p0) LZ 3 Note b	(1p2) LZ 8 Note b	(1p6) LZ 5 Note b	(2p3) LZ 4 Note b	(2p5) LZ 8 Note b	(3p1) LZ 5 Note b
Launch Remove	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Complete by	Note c, d	Note c, d	Note c, d	Note c, d	Note c, d	Note c, d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
 - b. Check the LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground
 - c. Launch until far bank end of bridge is 9 in (23 cm) from LRP, or end of ETP overhangs FRB by 1.5 ft (0.5 m).
 - d. Put bridge on ground
- * Add entire launching nose with LRP secured with tie down strap
() Center of gravity.

TABLE 2-8 Building and Boom Table - 2E + 7 through
2E + 12 Bay Double Story (Normal Site)

Bridge ft Length m	7 2 21.9	7 8 23.8	8 4 25.6	9 0 27.4	9 6 29.3	1 0 2 31.1
2E + Bays	7	8	9	10	11	12
L/Nose	4N1	5N1	5N1	5N1	6N1	6N1
Build E + 1 w/RRB at: Add (CG)	1p2 Note a 2, 3 4N1* 4 (Ap2)	1p2 Nom a 2, 3 5N1* 4.5 (1p0)	1p2 Note a 2, 3 5N1* 4, 5 (1p0)	1p2 Note a 2, 3 5N1* 4, 5 (1p0)	1p2 Note a 2, 3 6N1* 4, 5 (Ap2)	1p2 Note a 2, 3 6N1* 4, 5 (Ap2)
Boom Add (CG)	3p0 5, 6, 7 (2p2)	3p2 6, 7, 8 (2p5)	3p2 6, 7, 8 (2p5)	3p2 6, 7, 8 (2p5)	2p0 6, 7, 8 (2p3)	3p0 6, 7, 8 (2p3)
Boom Add (CG)	4p4 E (3p6)	4p6 E (3p7)	4p6 9, E (4p3)	4p6 9, 10 (3p5)	4p6 9, 10 11 (3p7)	4p4 9, 10 11 (3p7)
Boom Add (CG)				5p7 E (5p0)	6p1 E (5p2)	6p1 12, E (5p6)
Launch Position LRP	(3p6) LZ 4 Note b	(3p7) LZ 8 Note b	(4p3) LZ 5 Note b	(5p0) LZ 3 Note b	(5p2) LZ 8 Note b	(5p6) LZ 5 Note b
Launch Remove	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Complete by	Note c, d	Note c, d	Note c, d	Note c, d	Note c, d	Note C, d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
 - b. Check the LR is under LZ given or higher. Remove nose sections as they pass LRP. observing minimum 5 ft (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
 - c. Launch until far bank end of bridge is 9 in (23 cm) from LRP, or end of ETP overhangs FRB by 1.5 ft (0.5 m).
 - d. Put bridge on ground.
- * Add entire launching nose with LRP secured with tie down strap.
() Center of gravity.

TABLE 2-9 Building and Boom Table - 2E + 13 through
2E + 17 Bay Double Story (W/O LRS) (Normal Site)

Bridge ft Length m	1 0 8 32.9	1 1 4 34.8	1 2 0 36.6	1 2 6 38.4	1 3 2 40.2
2E + Bays	13	14	15	16	17
L/Nose	6N1	7N1	7N1	7N1	8N1
Build E + 1 W/RRB at: Add	1p2 Note a 2, 3 6N1* 4.5	1p2 Note a 2, 3 7N1* 4, 5, 6	1p2 Note a 2, 3 7N1* 4, 5, 6	1p2 Note a 2, 3 7N1* 4, 5, 6	1p2 Note a 2, 3 7N1* 4, 5 8N1**, 6
(CG)	(Ap2)	(1p0)	(1p0)	(1p0)	(Ap2)
Boom A d d (CG)	3p0 6, 7, 8 (2p3)	3p2 7, 8, 9 (2p5)	3p2 7, 8, 9 (2p5)	3p2 7, 8, 9 (2p5)	3p0 7, 8, 9 (2p3)
Boom Add (CG)	4p4 9, 10, 11 (4p0)	4p7 10, 11, 12 (4p2)	4p7 10, 11, 12 (4p2)	4p7 10, 11, 12 (4p2)	4p5 10, 11, 12 (3p7)
Boom Add (CG)	11p0 12, 13 E (6p2)	11p0 13, 14 E (6p4)	11p0 13, 14 15 E (7p1)	11p0 13 thru 16 E (7p5)	10p7 13 thru 17 E (8p0)
Launch Position LRP	(6p2) LZ 3 Note b	(6p4) LZ 7 Note b	(7p1) LZ 5 Note b	(7p5) LZ 5 Note b	(8p0) LZ 8 Note b
Launch Remove	10p6 FRB RRB	11p6 FRB RRB	12p6 FRB RRB	13p6 FRB RRB	14p6 FRB RRB
Compl. by	Note c, d	Note c, d	Note c, d	Note c, d	Note c, d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
- b. Check that LR is under LZ given or higher Remove nose sections as they pass LRP, observing minimum 5 ft (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
- c. Launch until far bank end of bridge is 9 in (23 cm) from LRP, or end of ETP overhangs CRB by 1.5 ft (0.5 m).
- d. Put bridge on ground
 - * Add given length launching nose with LRP secured with tie down strap.
 - ** Nose completed by adding 8th LNH or 6 LNH required for 3N2 (double-story nose).
- () Center of gravity

TABLE 2-10 Building and Boom Table - 2E + 18 through
2E + 22 bay Double Story (w/o LRS) (Normal Site)

Bridge ft Length m	138 42.1	144 43.9	150 45.7	156 47.6	162 49.4
2E + Bays	18	19	20	21	22
L/Nose	8N1	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
C/weight		[20D + 6C]	[20D + 6C]	[20D + 6C]	[20D + 6C]
Build E + 1 W/RRB at:	1p2	1p2	1p2	1p2	1p2
Add	Note a 2, 3 7N1*	Note a 2, 3 6N1*	Note a 2, 3 6N1*	Note a 2, 3 6N1*	Note a 2, 3 6N1*
(CG)	4, 5 8N1**, 6 (Ap2)	4, 5 3N2**, 6 (Bp2)	4, 5 3N2**, 6 (Bp2)	4, 5 3N2**, 6 (Bp2)	4, 5 3N2**, 6 (Bp2)
A d d (CG)	3p0 7 thr 9 (2p3)	2p4 7 thr 9 (2p0)	2p4 7 thr 9 (2p0)	2p4 7 thr 9 (2p0)	2p4 7 thr 9 (2p0)
Boom Add (CG)	4p5 10, 11, 12 (3p7)	4p2 10 thr 13 (4p0)	4p2 10 thr 13 (4p0)	4p2 10 thr 13 (4p0)	4p2 10 thr 13 (4p0)
Boom Add (CG)	10p7 13 thr 18 E (8p4)	11p0 14 thr 19 E, [20D+ 6C] (9p0)	11p0 14 thr 20 E, [20D + 6C] (9p7)	11p0 14 thr 21 E, [20D + 6C] (10p3)	11p0 14 thr 22 E, [20D + 6C] (10p7)

2E + Bays	18	19	20	21	22
L/Nose	8N1	6N1+ 3N2	6N1 + 3N2	6N1 + 3N2	6N1 + 3N2
Launch Position LRP	(8p4) LZ 5 Note b	(9p0) LZ 2 Note b	(9p7) LZ 4 Note b	(10p3) LZ 5 Note b	(10p7) LZ 6 Note b
Launch Remove	15p5 FRB RRB	16P5 FRB RRB	17P5 FRB RRB	18P5 FRB RRB	19P5 FRB RRB
Compl. by	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
 - b. Check that LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
 - c. Launch until far bank end of bridge is 9 in (23 cm) from LRP, or end of ETP overhangs CRB by 1.5 ft. (0.5 m).
 - d. Put bridge on ground.
- * Add given length of launching nose with LRP secured with tie down strap.
- ** Nose completed by adding 8th LNH or 6 LNH required for 3N2 (double-story nose).
- [] Counterweight.
- () Center of gravity.

**TABLE 2-11 Building and Boom Table-2E +1 through
2E + 3 Bay Double Story (Restricted Site)**

Bridge ft. Length .	36 11.0	42 12.8	48 14.6
2E + Bays	1	2	3
L/Nose	3N1	4N1	4N1
Build E + 1 With RRB at:	1p2	1p2	1p2
Add (CG)	Note a 3N1* (Cp1)	Note a 2 4N1* (Bp7)	Note a 2 4N1* (Bp7)
Launch Position LRP	(Cp1) LZ 3 Note b	(Bp7) LZ 8 Note b	(Bp7) LZ 2 Note b
Launch Remove	Bp1 RRB	1p4 RRB	1p4 RRB
Launch Add	1p4 E	2p4 E	2p4 E
Launch Add			3p4 E
Complete by	Note c.d	Note c.d	Note c.d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
- b. Check LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft. (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
- c. Launch until far bank end of bridge is 9 in. (23 cm) from LRP, or end of ETP overhangs CRB by 1.5 ft (0.5 m).
- d. Put bridge on ground.
- * Add entire launching nose with LRP secured with tie down strap.
- () Center of gravity.

**TABLE 2-12 Building and Boom Table-2E +4 through
2E + 6 Bay Double Story (Restricted Site)**

Bridge ft. Length .	54 16.5		60 18.3		66 20.1	
2E + Bays	4		5		6	
L/Nose	4N1	5N1	5N1	6N1	5N1	6N1
Build E + 1 With RRB at:	1p2	1p2	1p2	1p2	1p2	1p2
Add	Note a 2 4N1*	Note a 2 5N1*	Note a 2 5N1*	Note a 2 6N1*	Note a 2,3 5N1*	Note a 2 6N1*
(CG)	(Bp7)	(Cp1)	(Cp1)	(Cp4)	(Bp4)	(Cp4)
Boom Add (CG)	1p7 3 (Bp2)		1p5 3 (Bp4)		2p2 4 (Bp0)	
Boom Add (CG)	2p4 4 (Ap2)		2p2 4 (Bp0)		2p6 5 (1p0)	
Launch Position LRP	(Ap2) LZ 3 Note b	(Cp1) LZ 6 Note b	(Bp0) LZ 2 Note b	(Cp4) LZ 6 Note b	(1p0) LZ 2 Note b	(Cp4) LZ 1 Note b
Launch Remove	2p4 RRB	1p4 RRB	2p4 RRB	1p4 RRB	3p4 RRB	1p4 RRB
Launch Add	4p4 E	2p4 3	4p4 5	2p4 3	5p4 6	2p4 3

2E + Bays	4		5		6	
L/Nose	4N1	5N1	5N1	6N1	5N1	6N1
Launch Add		3p4 4	5p4 E	3p4 4	6p4 E	3p4 4
Launch Add		4p4 E		4p4 5		4p4 5
Launch Add				5p4 E		5p4 6
Launch Add						6p4 E
Complete by	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
- b. Check LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft (1.5m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
- c. Launch until far bank end of bridge is 9 in (23cm) from LRP, or end of ETP overhangs CRB by 1.5 ft (0.5m).
- d. Put bridge on ground.
- * Add entire launching nose with LRP secured with tie down strap.
- () Center of gravity.

**TABLE 2-13 Building and Boom Table-2E +7 through
2E + 9 Bay Double Story (Restricted Site)**

Bridge ft. Length .	72 21.9		78 23.8		84 25.6	
2E + Bays	7		8		9	
L/Nose	5N1	6N1	6N1	7N1	6N1	7N1
Build E + 1 With RRB at	1p2	1p2	1p2	1p2	1p2	1p2
Add	Note a 2,3 5N1*	Note a 2,3 6N1*	Note a 2,3 6N1*	Note a 2,3 7N1*	Note a 2,3 6N1*	Note a 2,3 7N1*
(CG)	(Bp4)	(Bp7)	(Bp7)	(Bp5)	(Bp7)	(BP5)
Boom Add	2p2 4,5	1p7 4	1p7 4		1p7 4,5	2p1 5
(CG)	(1p0)	(Bp7)	(Bp2)		(Ap2)	(Bp0)
Boom Add	3p2 6		2p4 5		3p0 6	
(CG)	(1p4)		(Ap2)		(1p2)	
Boom Add	3p7 7		3p0 6		3p4 7	
(CG)	(2p0)		(1p2)		(1p6)	
Boom Add					4p0 8	
(CG)					(2p3)	
Launch Position LRP	(2p0) LZ 2 Note b	(Bp2) LZ 2 Note b	(1p2) LZ 2 Note b	(Bp5) LZ 4 Note b	(2p3) LZ 3 Note b	(Bp0) LZ 1 Note b

2E +Bays	7		8		9	
L/Nose	5N1	6N1	6N1	7N1	6N1	7N1
Launch Remove	5p4 RRB	2p4 RRB	4p4 RRB	2p4 RRB	6p4 RRB	3p4 RRB
Launch Add	7p4 E	4p4 5	6p4 7	4p4 5	8p4 9	5p4 6
Launch Add		5p4 6	7p4 8	5p4 6	9p4 E	6p4 7
Launch Add		6p4 7	8p4 E	6p4 7		7p4 9
Launch Add		7p4 E		7p4 8		8p4 9
Launch Add				8p4 E		9p4 E
Complete By	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
 - b. Check LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft (1.5m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
 - c. Launch until far bank end of bridge is 9 in (23cm) from LRP, or end of ETP overhangs CRB by 1.5 ft (0.5m).
 - d. Put bridge on ground.
- * Add entire launching nose with LRP secured with tie down strap.
- () Center of gravity.

**TABLE 2-14 Building and Boom Table-2E +10 through
2E + 12 Bay Double Story (Restricted Site)**

Bridge ft. Length .	90 27.4		96 29.3		102 31.1	
2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
Build E + 1 With RRB at	1p2	1p2	1p2	1p2	1p2	1p2
Add	Note a 2,3 6N1*	Note a 2,3 7N1* 4	Note a 2,3 7N1* 4,5	Note a 2,3 7N1* 4 8N1**	Note a 2,3 7N1* 4,5	Note a 2,3 7N1* 4 8N1**
(CG)	(Bp7)	(Bp5)	(Bp0)	(Cp0)	(Bp0)	(Cp0)
Boom Add (CG)	1p7 4,5 (Ap2)	2p1 5 (Bp0)	2p6 6.7 (1p4)	1p6 5 (Bp3)	2p6 6,7 (1p4)	1p6 5 (Bp3)
Boom Add (CG)	3p0 6.7 (1p6)	2p6 6 (1p0)	3p6 8 (2p1)	2p3 6 (Ap2)	3p6 8.9 (2p5)	2p3 6 (Ap2)
Boom Add (CG)	4p0 8 (2p3)	3p2 7 (1p4)	4p2 9 (2p5)		4p7 10 (3p1)	3p0 7 (1p2)
Boom Add (CG)	4p4 9 (2p7)				5p3 11 (3p5)	3p4 8 (1p6)
Boom Add (CG)	5p1 10 (3p)					
Launch Position LRP	(3p3) LZ 3 Note b	(1p4) LZ 1 Note b	(2p5) LZ 2 Note b	(Ap2) LZ 1 Note b	(3p5) LZ 2 Note b	(1p6) LZ 1 Note b

2E +Bays	10		11			12
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
Launch Remove	8p4 RRB	5p4 RRB	7p4 RRB	4p4 RRB	9p4 RRB	6p4 RRB
Launch Add	10p4 E	7p4 8	9p4 10	6p4 7	11p4 12	8p4 9
Launch Add		8p4 9	10p4 11	7p4 8	12p4 E	9p4 10
Launch Add		9p4 10	11p4 E	8p4 9		10p4 11
Launch Add		10p4 E		9p4 10		11p4 12
Launch Add				10p4 11		12p4 E
Launch Add				11p4 E		
Complete By	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d	Note c,d

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
- b. Check LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft (1.5m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
- c. Launch until far bank end of bridge is 9 in (23cm) from LRP, or end of ETP overhangs CRB by 1.5 ft (0.5m).
- d. Put bridge on ground.
 - Add entire launching nose with LRP secured with tie down strap.
 - ** Nose completed by adding 8th LNH.
 - () Center of gravity.

**TABLE 2-15 Delaunch Table-2E +1 through 2E + 6 Bay
Double Story (Normal Site)**

Bridge Length	ft m	36 11.0	42 12.8	48 14.6	54 16.5	60 18.3	66 20.1
2E + Bays		1	2	3	4	5	6
L/Nose		2N1	3N1	3N1	3N1	4N1	4N1
V Dist	ft m	38 11.6	45 13.7	51 15.5	55.8 17.0	63 19.2	69 21.0
Build		Notes a,b,c	Notes a,b and d	Notes a,b and d	Notes a,b and d	Notes a,b,d and e	Notes a,b,d and e
Delaunch Add		Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Delaunch Recover		(1p0) LRP	(1p2) LRP	(1p6) LRP	(2p3) LRP	(2p5) LRP	(3p1) LRP
Boom Remove (CG)							4p0 E (1p6)
Boom Remove (CG)				2p4 E (Bp0)	3p0 E (Ap2)	3p0 E,5 (Ap2)	3p0 6,5 (Ap2)
Boom Remove (CG)		1p2 E (Bp7)	1p6 E (Bp5)	1p2	1p2 4 (Bp0)	1p2 4 (Bp2)	1p2 4 (Bp2)
Remove		2N1*	3N1* 2	3N1* 3,2	3N1* 3,2	4N1* 3,2	4N1* 3,2

2E + Bays	1	2	3	4	5	6
L/Nose	2N1	3N1	3N1	3N1	4N1	4N1
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note f	Note f	Note f	Note f	Note f	Note f

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB. Add LNCG posts, LNCG and nose roller.
 - c. For 2E + 1 only. Add 2 LNH and LLN.
 - d. For 2E + 2 through 2E + 12, add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - e. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - f. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
 - Center of gravity.

**TABLE 2-16 Delaunch Table-2E + 7 through 2E + 12 Bay
Double Story (Normal Site)**

Bridge ft	72	78	84	90	96	102
Length m	21.9	23.8	25.6	27.4	29.3	31.1
2E + Bays	7	8	9	10	11	12
L/Nose	4N1	5N1	5N1	5N1	6N1	6N1
V Dist ft	74	81	87	92	99	105
m	22.6	24.7	26.5	28.0	30.2	32.0
Build	Notes a,b, d,e	Notes a,b, d,e	Notes a,b, d,e	Notes a,b, d,e	Notes a,b, d,e	Notes a,b, d,e
Delaunch Add	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Delaunch Recover	(3p6) LRP	(3p7) LRP	(4p3) LRP	(5p0) LRP	(5p2) LRP	(5p6) LRP
Boom Remove (CG)				5p7 E (3p5)	6p1 E (3p7)	6p1 E,12 (3p7)
Boom Remove (CG)	4p4 E (2p2)	4p6 E (2p5)	4p6 E,9 (2p5)	4p6 10,9 (2p5)	4p4 11,10 9 (2p3)	4p4 11,10 9 (2p3)
Boom Remove (CG)	3p0 7,6 5 (Ap2)	3p2 8,7 6 (1p0)	3p2 8,7 6 (1p0)	3p2 8,7 6 (1p0)	3p0 8,7 6 (Ap2)	3p0 8,7 6 (Ap2)

2E + Bays	7	8	9	10	11	12
L/Nose	4N1	5N1	5N1	5N1	6N1	6N1
Boom Remove (CG)	1p2 4 (Bp2)	1p2 5,4 (Bp5)	1p2 5,4 (Bp5)	1p2 5,4 (Bp5)	1p2 5,4 (Bp7)	1p2 5,4 (Bp7)
Remove	4N1* 3,2	5N1* 3,2	5N1* 3,2	5N1* 3,2	6N1* 3,2	6N1* 3,2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note f	Note f	Note f	Note f	Note f	Note f

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5 m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB. Add LNCG posts, LNCG and nose roller.
 - c. For 2E + 1 only. Add 2 LNH and LLN.
 - d. For 2E + 2 through 2E + 12, add 3 LNH. Reposition LRP [base 9in (23 cm) from BSB].
 - e. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - f. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-17 Delaunch Table-2E + 13 through 2E + 17 Bay
Double Story (w/o LRS) (Normal Site)**

Bridge ft	108	114	120	126	130
Length m	32.9	34.8	36.6	38.4	40.2
2E + Bays	13	14	15	16	17
L/Nose	6N1	7N1	7N1	7N1	8N1
Counter-Weight	-	-	-	-	-
V Dist ft	110	117	123	128	134.8
m	33.5	35.7	37.5	39	41.1
Build	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c
Delaunch Add	10p6 FRB RRB	11p6 FRB RRB	12p6 FRB RRB	13p6 FRB RRB	14p6 FRB RRB
Delaunch Recover	(6p2) LRP	(6p4) LRP	(7p1) LRP	(7p5) LRP	(8p0) LRP
Boom Remove	11p0 E,13,12	10p0 E,14,13	11p0 E,15 thru 13	11p0 E,16 thru 13	10p7 E,17 thru 13
(CG)	(4p0)	(4p2)	(4p2)	(4p2)	(3p7)
Boom Remove	4p4 11,10,9	4p7 12 thru 10	4p7 12 thru 10	4p7 12 thru 10	4p5 12 thru 10
(CG)	(2p3)	(2p5)	(2p5)	(2p5)	(2p3)
Boom Remove	3p0 8,7,6	3p2 9 thru 7	3p2 9 thru 7	3p2 9 thru 7	3p0 9 thru 7
(CG)	(Ap2)	(1p0)	(1p0)	(1p0)	(Ap2)

2E + Bays	13	14	15	16	17
L/Nose	6N1	7N1	7N1	7N1	8N1
Boom Remove	1p2 5 6N1*,4 3,2	1p2 6,5 7N1*,4 3,2	1p2 6,5 7N1*,4 3,2	1p2 6,5 7N1*,4 3,2	1p2 6,8N1** 7N1*,4 3,2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note d	Note d	Note d	Note d	Note d

NOTES:

- a. Remove all curbs, ramps, and deck units.
 - b. Position CRB under bridge min. 1.5 ft (0.5 m) from end.
 - c. Add LNCG posts, LNCG and nose roller and install launching nose, observing minimum 5 ft (1.5 m) overhang.
 - d. Disassemble FRB and RRB. Clear site.
- ** Remove 8th LNH or all of 3N2 (double-story nose).
- * Remove given length of launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-18 Delaunch Table-2E + 18 through 2E + 22 Bay
Double Story (w/o LRS) (Normal Site)**

Bridge ft	138	144	150	156	162
Length m	42.1	43.9	45.7	47.6	49.4
2E + Bays	18	19	20	21	22
L/Nose	8N1	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Counter-Weight	-	[20D+ 6C]	[20D+ 6C]	[20D+ 6C]	[20D+ 6C]
V Dist ft	141	158.5	161	163	165
m	43.0	48.3	49.1	49.7	50.3
Build	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c
Delaunch Add	15p5 FRB, RRB	16p5 FRB, RRB	17p5 FRB, RRB	18p5 FRB, RRB	19p5 FRB, RRB
Delaunch Recover	(8p4) LRP	(9p0) LRP	(9p7) LRP	(10p3) LRP	(10p7) LRP
Boom Remove	10p7 E,18 thru 13	11p0 [6C+ 20D],E 19 thru 14	11p0 [6C+ 20D],E 20 thru 14	11p0 [6+ 20D],E 21 thru 14	11p0 [6C+ 20D],E 22 thru 14
(CG)	(3p7)	(4p0)	(4p0)	(4p0)	(3p7)
Boom Remove	4p5 12 thru 10	4p2 13 thru 10	4p2 13 thru 10	4p2 13 thru 10	4p2 13 thru 10
(CG)	(2p3)	(2p0)	(2p0)	(2p0)	(2p0)

2E + Bays	18	19	20	21	22
L/Nose	8N1	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Boom Remove (CG)	3p0 9 thru 7 (Ap2)	2p4 9 thru 7 (Bp2)	2p4 9 thru 7 (Bp2)	2p4 9 thru 7 (Bp2)	2p4 9 thru 7 (Bp2)
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note d	Note d	Note d	Note d	Note d

NOTES:

- a. Remove all curbs, ramps, and deck units and add counterweight if required.
 - b. Position CRB under bridge min. 1.5 ft (0.5 m) from end.
 - c. Add LNCG posts, LNCG and nose roller and install launching nose, observing minimum 5 ft (1.5 m) overhang.
 - d. Disassemble FRB and RRB. Clear site.
- ** Remove 8th LNH or all of 3N2 (double-story nose).
- * Remove given length of launching nose, LNCG, LNCG posts and nose roller.
- [] Counterweight.
- () Center of gravity.

**TABLE 2-19 Delaunch Table-2E +1 through 2E + 6 Bay
Double Story (Normal Site – Original Far Bank)**

Bridge Length	ft m	36 11.0	42 12.8	48 14.6	54 16.5	60 18.3	66 20.1
2E + Bays		1	2	3	4	5	6
L/Nose		2N1	3N1	3N1	3N1	4N1	4N1
V Dist	ft m	38 11.6	45 13.7	51 15.5	55.8 17.0	63 19.2	69 21.0
Build		Notes a,b,c	Notes a,b,d	Notes a,b,d	Notes a,b,d	Notes a,b, d,e	Notes a,b, d,e
Delaunch Add		Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Delaunch Recover		(1p0) LRP	(1p2) LRP	(1p6) LRP	(2p3) LRP	(2p5) LRP	(3p1) LRP
Boom Remove (CG)		1p3 E (Bp7)	1p6 E (Bp5)	2p4 E (Bp0)	3p0 E (Bp1)	3p0 E (Bp2)	4p0 E (1p6)
Boom Remove (CG)							3p0 6,Bp5 (1p0)
Boom Remove (CG)		2N1* (Bp3)	3N1* Pin at A BP2 (Bp1)	1p7 3N1* Pin at A BP3 (Ap2)	1p7 BP4 3N1* (1p3)	1p7 TP5 BP4 4N1* (1p3)	1p7 TP5 BP4 4N1* (1p3)

2E + Bays	1	2	3	4	5	6
L/Nose	2N1	3N1	3N1	3N1	4N1	4N1
Boom Remove				2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove			1p4 TP3 BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2
Boom Remove	Bp0 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note f	Note f	Note f	Note f	Note f	Note f

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB. Add LNCG posts, LNCG and nose roller.
 - c. For 2E + 1 only. Add 2 LNH and LLN.
 - d. For 2E + 2 through 2E + 12, add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - e. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - f. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
-
- () Center of gravity.

**TABLE 2-20 Delaunch Table-2E +7 through 2E + 12 Bay
Double Story (Normal Site – Original Far Bank)**

Bridge ft	72	78	84	90	96	102
Length m	21.9	23.8	25.6	27.4	29.3	31.1
2E + Bays	7	8	9	10	11	12
L/Nose	4N1	5N1	5N1	5N1	6N1	6N1
V Dist ft	74	81	87	92	99	105
m	22.6	24.7	26.5	28.0	30.2	32.0
Build	Notes a,b,c,d	Notes a,b,c,d	Notes a,b,c,d	Notes a,b,c,d	Notes a,b,c,d	Notes a,b,c,d
Delaunch Add	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB	Dp2 RRB
Delaunch Recover	(3p6) LRP	(3p7) LRP	(4p3) LRP	(5p0) LRP	(5p2) LRP	(5p6) LRP
Boom Remove (CG)	4p4 E (2p2)	4p6 E (2p5)	4p6 E (2p7)	5p7 E (3p3)	6p1 E (3p7)	6p1 E (4p3)
Boom Remove (CG)				4p6 BP10 (3p3)	4p6 11 BP10 (3p1)	4p6 12, 11 BP10 (3p1)
Boom Remove (CG)		3p6 BP8 (2p0)	3p6 9, BP8 (2p0)	3p6 TP10 9 BP8 (2p0)	3p6 TP10 9 BP8 (2p0)	3p6 TP10 9 BP8 (2p0)
Boom Remove (CG)	3p0 7, 6 BP5 (1p0)	3p0 TP8, 7 BP6 (1p0)	3p0 TP8, 7 BP6 (1p0)	3p0 TP8, 7 BP6 (1p0)	3p0 TP8, 7 BP6 (1p0)	3p0 TP8, 7 BP6 (1p0)

2E + Bays	7	8	9	10	11	12
L/Nose	4N1	5N1	5N1	5N1	6N1	6N1
Boom Remove (CG)	1p7 TP5 BP4 4N1* (1p3)	1p7 TP6, 5 BP4 5N1* (1p3)	1p7 TP6, 5 BP4 5N1* (1p3)	1p7 TP6,5 BP4 5N1* (1p3)	1p7 TP6, 5 BP4 6N1* (1p3)	1p7 TP6, 5 BP4 6N1* (1p3)
Boom Remove	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove	1p4 TP4 3, BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2	1p4 TP4 3, BP2
Boom Remove	Bp0 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - c. Add LNCG posts, LNCG and nose roller. Add 3LNH. Re-position LRP [base 9 in (23 cm) from BSB].
 - d. For 2E + 1 only. Add 2 LNH and LLN.
 - e. Add remaining nose sections, as required observing the minimum 5 ft (1.5 m) overhang.
 - f. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-21 Delaunch Table-2E +13 through 2E + 17 Bay
Double Story (w/o LRS) (Normal Site – Original Far Bank)**

Bridge ft	108	114	120	126	132
Length m	32.9	34.8	36.6	38.4	40.2
2E + Bays	13	14	15	16	17
L/Nose	6N1	7N1	7N1	7N1	8N1
V Dist ft	110	117	123	128	134.8
m	33.5	35.7	37.5	39	41.1
Build	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c	Notes a thru c
Delaunch Add	10p6 FRB RRB	11p6 FRB RRB	12p6 FRB RRB	13p6 FRB RRB	14p6 FRB RRB
Delaunch Recover	(6p2) LRP	(6p4) LRP	(7p1) LRP	(7p5) LRP	(8p0) LRP
Boom Remove (CG)	6p4 E thru BP12 (4p1)	6p6 E thru BP13 (4p4)	7p3 E thru BP13 (4p4)	7p7 E thru BP13 (4p4)	8p2 E thru BP13 (4p1)
Boom Remove (CG)	4p4 TP12 thru BP9 (2p4)	4p6 TP13 thru BP10 (2p7)	4p6 TP13 thru BP10 (2p7)	4p6 TP13 thru BP10 (2p7)	4p4 TP13 thru BP10 (2p4)
Boom Remove (CG)	2p6 TP9thru BP6 (1p0)	1p6 TP10 thru BP7 (1p2)	3p1 TP10 thru BP7 (1p2)	3p1 TP10 thru BP7 (1p2)	2p6 TP10 thru BP7 (1p0)

2E + Bays	13	14	15	16	17
L/Nose	6N1	7N1	7N1	7N1	8N1
Boom Remove	1p7 TP7 thru BP4 6N1*	1p7 TP7 thru BP4 7N1*	1p7 TP7 thru BP4 7N1*	1p7 TP7 thru Bp4 7N1*	1p7 TP7 thru Bp5 8N1** BP4 7N1*
(CG)	(1p0)	(1p3)	(1p3)	(1p3)	(1p3)
Boom Remove	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A
Boom Remove	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2
Boom Remove	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note d	Note d	Note d	Note d	Note d

NOTES:

- a. Remove all curbs, ramps, and deck units.
 - b. Position CRB under bridge min. 1.5 ft (0.5 m) from end.
 - c. Add LNCG posts, LNCG and nose roller and install launching nose, observing minimum 5 ft (1.5 m) overhang.
 - d. Disassemble FRB and RRB. Clear site.
- ** Remove 8th LNH (after BP5) or all of 3N2 (after BP6).
- * Remove given length of launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-22 Delaunch Table-2E +18 through 2E + 22 Bay
Double Story (w/o LRS) (Normal Site – Original Far Bank)**

Bridge ft	138	144	150	156	162
Length m	42.1	43.9	45.7	47.6	49.4
2E + Bays	18	19	20	21	22
L/Nose	8N1	6N1,3N1	6N1,3N2	6N1,3N2	6N1,3N2
V Dist ft	141	158.5	161	163	165
m	43.0	48.3	49.1	49.7	50.3
Build	notes a thru c	notes a thru c	notes a thru c	notes a thru c	notes a thru c
Delaunch Add	10p6 FRB RRB	11p6 FRB RRB	12p6 FRB RRB	13p6 FRB RRB	14p6 FRB RRB
Delaunch Recover	(8p4) LRP	(9p0) LRP	(9p7) LRP	(10p3) LRP	(10p7) LRP
Boom Remove	8p6 E thru BP13	9p2 [6C+ 20D] E thru BP13	7p3 6C+ 20D] E thru BP13	7p7 6C+ 20D] E thru BP13	8p2 6C+ 20D] E thru BP13
(CG)	(4p1)	(3p6)	(3p6)	(3p6)	(3p6)
Boom Remove	4p4 TP12 thru BP9	4p0 TP13 thru BP10	4p0 TP13 thru BP10	4p0 TP13 thru BP10	4p0 TP13 thru BP10
(CG)	(2p4)	(2p2)	(2p2)	(2p2)	(2p2)
Boom Remove	2p6 TP10 thru BP7	2p4 TP10 thru BP7	2p4 TP10 thru BP7	2p4 TP10 thru BP7	2p6 TP10 thru BP7
(CG)	(1p0)	(Bp0)	(Bp0)	(Bp0)	(Bp0)

2E + Bays	18	19	20	21	22
L/Nose	6N1	7N1	7N1	7N1	8N1
Boom Remove (CG)	1p7 TP7 thru BP5 8N1** BP4 7N1* (1p3)	1p7 TP7 BP6 3N2** TP6 thru BP4 6N1* (1p3)	1p7 TP7 BP6 3N2** TP6 thru BP4 6N1* (1p3)	1p7 TP7 Bp6 3N2** TP6 thru BP4 6N1* (1p3)	1p7 TP7 Bp6 3N2** TP6 thru BP4 6N1* (1p3)
Boom Remove	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A	2p0 PIN at A
Boom Remove	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2	1p4 TP4 thru BP2
Boom Remove	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1	Bp0 TP2, 1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note d	Note d	Note d	Note d	Note d

NOTES:

- Remove all curbs, ramps, and deck units and add counterweight if required.
 - Position CRB under bridge min. 1.5 ft (0.5 m) from end.
 - Add LNCG posts, LNCG and nose roller and install launching nose, observing minimum 5 ft (1.5 m) overhang.
 - Disassemble FRB and RRB. Clear site.
- ** Remove 8th LNH (after BP5) or all of 3N2 (after BP6).
- Remove given length of launching nose, LNCG, LNCG posts and nose roller.
- [] Counterweight
() Center of gravity.

**TABLE 2-23 Building and Boom Table-2E +1 through2E + 4 Bay
Double Story (Restricted Site)**

Bridge ft.	36	42	48	54	
Length .	11.0	12.8	14.6	16.5	
2E + Bays	1	2	3	4	
L/Nose	6N1			7N1	7N1
V Dist ft	39	45	51	57	63
m	11.9	13.7	15.5	17.4	19.2
Build	Notes a,b, c,d	Notes a,b, c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove	1p4 E	2p4 E	3p4 E	4p4 E	4p4 E
Delaunch Remove			2p4 3		3p4 4
Delaunch Remove					2p4 3
Delaunch Add	Bp1 RRB	1p4 RRB	1p4 RRB	2p4 RRB	1p4 RRB
Delaunch Recover	(Cp1) LRP	(Bp7) LRP	(Bp7) LRP	(Ap2) LRP	(Cp1) LRP
Boom Remove (CG)				2p4 4 (Bp7)	
Boom Remove (CG)				1p7 3 (Bp7)	

2E + Bays	1	2	3	4	
L/Nose	2N1	3N1	3N1	4N1	5N1
Boom Remove	1p3 3N1*	1p6 4N1* 2	1p2 4N1* 2	1p2 4N1* 2	1p2 5N1* 2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note e	Note e	Note e	Note e	Note e

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - c. Add LNCG posts, LNCG and nose roller. Add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - d. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - e. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-24 Building and Boom Table-2E +5 through 2E + 6 Bay
Double Story (Restricted Site)**

Bridge Length .	60 18.3		66 20.1	
2E + Bays	5		6	
L/Nose	5N1	6N1	7N1	7N1
V Dist ft m	63 19.2	63 19.2	69 21.0	69 21.0
Build	Notes a,b, c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove	5p4 E	5p4 E	6p4 E	6p4 E
Delaunch Remove	4p4 5	4p4 5	5p4 6	5p4 6
Delaunch Remove		3p4 4		4p4 5
Delaunch Remove		2p4 3		3p4 4
Delaunch Remove				2p4 3
Delaunch Add	2p4 RRB	1p4 RRB	3p4 RRB	1p4 RRB
Delaunch Recover	(Bp0) LRP	(Cp4) LRP	(1p0) LRP	(Cp4) LRP

**TABLE 2-24 Building and Boom Table-2E +5 through 2E + 6 Bay
Double Story (Restricted Site)**

2E + Bays	5		6	
L/Nose	5N1	6N1	5N1	6N1
Boom Remove (CG)	2p2 4		2p6 5 (Bp0)	
Boom Remove (CG)	1p5 3 (Cp1)		2p4 4 (Bp4)	
Boom Remove (CG)	1p2 5N1* 2	1p2 6N1* 2	1p2 5N1* 3,2	1p2 6N1* 2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note e	Note e	Note e	Note e

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min 1.5 ft (0.5 m) from the end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - c. Add LNCG posts, LNCG and nose roller. Add 3 LNH. Reposition LRP [base 9 in (23 cm) from BSB.]
 - d. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - e. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-25 Delaunch Table-2E +7 through 2E + 9 Bay
Double Story (Restricted Site)**

Bridge ft. Length .	72 21.9		78 23.8		84 25.6	
2E + Bays	7		8		9	
L/Nose	5N1	6N1	6N1	7N1	6N1	7N1
V Dist ft m	75 22.9	75 22.9	81 24.7	81 24.7	87 26.5	87 26.5
Build	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove	7p4 E	7p4 E	8p4 E	8p4 E	9p4 E	9p4 E
Delaunch Remove		6p4 7	7p4 8	7p4 8	8p4 9	8p4 9
Delaunch Remove		5p4 6	6p4 7	6p4 7		7p4 8
Delaunch Remove		4p4 5		5p4 6		6p4 7
Delaunch Remove				4p4 5		5p4 6
Delaunch Add	5p4 RRB	2p4 RRB	4p4 RRB	2p4 RRB	6p4 RRB	3p4 RRB
Delaunch Recover	(2p0) LRP	(Bp2) LRP	(1p2) LRP	(Bp5) LRP	(2p3) LRP	(Bp0) LRP
Boom Remove (CG)	3p7 7 (1p4)	1p7 4 (Bp7)	3p0 6 (Ap2)		4p0 8 (1p6)	2p1 5 (Bp5)

2E + Bays	7		8		9	
L/Nose	5N1	6N1	6N1	7N1	6N1	7N1
Boom Remove (CG)	3p2 6 (1p0)		2p4 5 (Bp2)		3p4 7 (1p2)	
Boom Remove (CG)	2p2 5,4 (Bp4)		1p7 4 (Bp7)		3p0 6 (Ap2)	
Boom Remove (CG)					1p7 5,4 (Bp7)	
Boom Remove	1p2 5N1* 3,2	1p2 6N1* 3,2	1p2 6N1* 3,2	1p2 4 7N1* 3,2	1p2 6N1* 3,2	1p2 4 7N1* 3,2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - Add LNCG posts, LNCG and nose roller. Add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
-
- () Center of gravity.

**TABLE 2-26 Delaunch Table-2E +10 through 2E + 12 Bay
Double Story (Restricted Site)**

Bridge ft. Length .	90 27.4		96 29.3		102 31.1	
2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
V Dist ft m	93 28.3	93 28.3	99 30.2	99 30.2	105 32.0	105 32.0
Build	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove	10p4 E	10p4 E	11p4 E	11p4 E	12p4 E	12p4 E
Delaunch Remove		9p4 10	10p4 11	10p4 11	11p4 12	11p4 12
Delaunch Remove		8p4 9	9p4 10	9p4 10		10p4 11
Delaunch Remove		7p4 8		8p4 9		9p4 10
Delaunch Remove				7p4 8		8p4 9
Delaunch Remove				6p4 7		
Delaunch Add	8p4 RRB	5p4 RRB	7p4 RRB	4p4 RRB	9p4 RRB	6p4 RRB
Delaunch Recover	(3p3) LRP	(1p4) LRP	(2p5) LRP	(Ap2) LRP	(3p5) LRP	(1p6) LRP
Boom Remove (CG)	5p1 10 (2p7)	3p2 7 (1p0)	4p2 9 (2p1)	2p3 6 (Bp3)	5p3 11 (3p1)	3p4 8 (1p2)

2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
Boom Remove (CG)	4p4 9 (2p3)	2p6 6 (Bp0)	3p6 8 (1p4)	1p6 5 (Cp0)	4p7 10 (2p5)	3p0 7 (Ap2)
Boom Remove (CG)	4p0 8 (1p6)	2p1 5 (Bp5)	2p6 7,6 (Bp0)		3p6 9,8 (1p4)	2p3 6 (Bp3)
Boom Remove (CG)	3p0 7,6 (Ap2)				2p6 7,6 (Cp2)	1p6 5 (Cp0)
Boom Remove (CG) Remove	1p2 6N1* 3,2	1p2 4 (Cp2) 7N1* 3,2	1p2 5,4 (Cp2) 7N1* 3,2	1p2 8N1,4 (Cp2) 7N1* 3,2	1p2 5,4 (Cp2) 7N1* 3,2	1p2 8N1,4 (Cp2) 7N1* 3,2
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Complete by:	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - Add LNCG posts, LNCG and nose roller. Add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-27 Delaunch Table-2E +1 through 2E + 5 Bay
Double Story (Restricted Site – Original Far Bank)**

Bridge ft. Length .	36 11.0	42 12.8	48 14.6	54 16.5		60 18.3	
2E + Bays	1	2	3	4		5	
L/Nose	3N1	4N1	4N1	4N1	5N1	5N1	6N1
V Dist ft m	39 11.9	45 13.7	51 15.5	57 17.4	57 17.4	63 19.2	63 19.2
Build	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove		2p4 BSB ETP F,E	3p4 BSB ETP F,E	4p4 BSB ETP F,E	4p4 BSB ETP F,E	5p4 BSB ETP F,E	5p4 BSB ETP F,E
Delaunch Remove			2p4 D BP3	3p4 D BP4	3p4 D BP4	4p4 D BP5	4p4 D BP5
Delaunch Remove					Ap1 TP4 BP3		1p7 TP5 BP4
Delaunch Remove							Ap1 TP4 BP3
Delaunch Add	RRB	Ap3 RRB	Ap3 RRB	1p6 RRB	RRB	1p4 RRB	RRB
Delaunch Recover	(Ap2) LRP	(Bp4) LRP	(Bp5) LRP	(Bp0) LRP	(Bp7) LRP	(Ap2) LRP	(Cp2) LRP
Boom Remove	Dp1 BSB ETP F,E					2p2 TP5 BP4	

2E + Bays	1	2	3	4		5	
L/Nose	3N1	4N1	4N1	4N1	5N1	5N1	6N1
Boom Remove (CG)	1p4 3N1* (Bp1)	1p7 4N1* (Ap1)	1p7 4N1* (Ap2)	1p7 4N1* (1p3)	1p4 5N1* (Ap2)	1p5 5N1* (1p3)	1p4 6N1* (1p3)
Boom Remove	Dp2 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove	1p2 D	1p4 D BP2	1p4 TP3 BP2	1p4 TP4 3 BP2	1p4 TP3 BP2	1p4 TP4 3 BP2	1p4 TP3 BP2
Boom Remove	Bp0 1	Bp0 TP2 1	Bp0 TP2 1	Bp0 TP2 1	Bp0 TP2 1	Bp0 TP2 1	Bp0 TP2 1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note e	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - Add LNCG posts, LNCG and nose roller. Add 3 LHN. Re-Position LRP [base 9in (23cm) from BSB].
 - Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-28 Delaunch Table-2E +6 through 2E + 9 Bay
Double Story (Restricted Site – Original Far Bank)**

Br. Ft Len. M	66 20.1		72 24.9		78 23.8		84 25.6	
2E + B	6		7		8		9	
L/Nose	5N1	6N1	5N1	6N1	6N1	7N1	6N1	7N1
V Dist ft m	69 21.0	69 21.0	75 22.9	75 22.9	81 24.7	81 24.7	87 26.5	87 26.5
Build	Note a,b c,d	Note a,b c,d	Note a,b c,d	Note a,b c,d	Note a,b c,d	Note a,b c,d	Note a,b c,d	Note a,b c,d
Delau Re- move	6p4 BSB ETP F,E	6p4 BSB ETP F,E	7p4 BSB ETP F,E	7p4 BSB ETP F,E	8p4 BSB ETP F,E	8p4 BSB ETP F,E	9p4 BSB ETP F,E	9p4 BSB ETP F,E
Delau Re- move	5p4 D BP6	5p4 D BP6	6p4 D BP7	6p4 D BP7	7p4 D BP8	7p4 D BP8	8p4 D BP9	8p4 D BP9
Delau Re- move		2p7 TP6 BP5		3p7 TP7 BP6	4p7 TP8 BP7	4p7 TP8 BP7		5p7 TP9 BP8
Delau Re- move		1p7 TP5 BP4				2p7 TP6 BP5		3p7 TP7 BP6
Delau Add	2p0 RRB	RRB	3p0 RRB	RRB	2p2 RRB	RRB	3p3 RRB	RRB
Delaunch Recover	(1p2) LRP	(Cp2) LRP	(1p6) LRP	(Bp0) LRP	(1p4) LRP	(Bp3) LRP	(2p5) LRP	(Ap2) LRP

2E + B	6		7		8		9	
L/N	5N1	6N1	5N1	6N1	6N1	7N1	6N1	7N1
Boom Re- move (CG)	2p6 TP6 BP5 (Ap2)				3p0 TP7 BP6 (1p6)		4p0 TP9 BP8 (1p6)	2p1 TP6 BP5 (Bp3)
Boom Re- move (CG)	2p2 TP5 BP4 (Bp3)		3p2 TP7 BP6 (1p2)		2p4 TP6 BP5 (Bp0)		3p4 TP8 BP7 (1p2)	
Boom Re- move (CG)			2p2 TP6 BP5 (Ap2)				3p0 TP8 BP7 (Ap2)	
Boom Re- Move (CG)	1p7 5N1* (1p3)	1p4 6N1* (Ap2)	1p7 TP5 BP4 5N1* (1p3)	1p7 TP5, BP4 6N1* (1p3)	1p7 TP5 BP4 6N1* (1p3)	1p7 TP5 BP4 7N1* (1p3)	1p7 TP6 BP5 TP5 BP4 6N1* (1p3)	1p7 TP5 BP4 7N1* (1p3)
Boom Re- move	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Re- move	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2	1p4 TP4 3 BP2
Boom Re- move	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1	Pp0 TP2 1

2E + B	6		7		8		9	
L/Nose	5N1	6N1	5N1	6N1	6N1	7N1	6N1	7N1
Boom Rem	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Comp by	Note e	Note e	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - c. Add LNCG posts, LNCG and nose roller. Add 3 LHN. Reposition LRP [base 9in (23cm) from BSB].
 - d. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - e. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-29 Delaunch Table-2E +10 through 2E + 12 Bay
Double Story (Restricted Site – Original Far Bank)**

Bridge ft. Length .	90 27.4		96 29.3		102 31.1	
2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
V Dist ft m	93 28.3	93 28.3	99 30.2	99 30.2	105 32.0	105 32.0
Build	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d	Notes a,b c,d
Delaunch Remove	10p4 BSB ETP F,E	10p4 BSB ETP F,E	11p4 BSB ETP F,E	11p4 BSB ETP F,E	12p4 BSB ETP F,E	12p4 BSB ETP F,E
Delaunch Remove	9p4 D BP10	9p4 D BP10	10p4 D BP11	10p4 D BP11	11p4 D BP12	11p4 D BP12
Delaunch Remove		8p4 9	9p4 10	9p4 10		10p4 11
Delaunch Remove		6p7 TP10 BP9	7p7 TP11 BP10	7p7 TP11 BP10		8p7 TP12 BP11
Delaunch Remove		5p7 TP9 BP8		6p7 TP10 BP9		7p7 TP11 BP10
Delaunch Remove				5p7 TP9 BP8		6p7 TP10 BP9
Delaunch Remove				4p7 TP8 BP7		
Delaunch Add	4p3 RRB	RRB	3p5 RRB	RRB	4p5 RRB	RRB

2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
De launch Recover	(3p1) LRP	(1p6) LRP	(2p7) LRP	(1p0) LRP	(3p7) LRP	(2p0) LRP
Boom Remove (CG)		3p2 TP8 BP7 (1p2)	4p2 TP10 BP9 (2p3)	2p3 TP7 BP6 (Bp1)	5p3 TP12 BP11 (3p3)	3p4 TP9 BP8 (1p4)
Boom Remove (CG)	4p4 TP10 BP9 (2p5)	2p6 TP7 BP6 (Ap2)	3p6 TP9 BP8 (1p6)		4p7 TP11 BP9 (2p7)	3p0 TP8 BP7 (1p0)
Boom Remove (CG)	4p0 TP9 BP8 (2p0)	2p1 TP6 BP5 (Bp3)	2p6 TP8 BP7 (1p2)		3p6 TP10 BP9 (2p3)	2p3 TP7 BP6 (Bp1)
Boom Remove (CG)	3p0 TP8 BP7 TP7 BP6 (1p0)				2p6 TP8 BP7 (1p2)	
Boom Remove (CG)	1p7 TP6 BP5 TP5 BP4 6N1*	1p7 TP5 BP4 7N1*	1p7 TP7 BP6 TP6 BP5 TP5 BP4 7N1*	1p7 TP6 BP5 8N1 TP5 BP4 7N1*	1p7 TP7 BP6 TP6 BP5 TP5 BP4 7N1*	1p7 TP6 BP5 8N1 TP5 BP4 7N1*
	(1p3)	(1p3)	(1p3)	(1p3)	(1p3)	(1p3)

2E + Bays	10		11		12	
L/Nose	6N1	7N1	7N1	8N1	7N1	8N1
Boom Remove	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove	1p4 TP4 3,BP2	1p4 TP4 3,BP2	1p4 TP4 3,BP2	1p4 TP4 3,BP2	1p4 TP4 3,BP2	1p4 TP4 3,BP2
Boom Remove	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Complete by:	Note e	Note e	Note e	Note e	Note e	Note e

NOTES:

- a. Remove curbs, decks and ramps and position FRB under bridge min. 1.5 ft (0.5m) from end.
 - b. Position center of LR (in LRP) 8 ft (2.4 m) from BSB.
 - c. Add LNCG posts, LNCG and nose roller. Add 3 LHN. Re-position LRP [base 9in (23cm) from BSB].
 - d. Add remaining nose sections, observing minimum 5 ft (1.5 m) overhang.
 - e. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

**TABLE 2-30 Building and Boom Table-2E +13 through 2E +
17 Bay Link Reinforced (Normal Site)**

Bridge ft. Length .	108 32.9	114 34.8	120 36.6	126 38.4	132 40.2
2E + Bays	13	14	15	16	17
L/Nose	7N1	7N1	7N1	8N1	8N1
Build E + 1 W/ RRB at:	1p2 Note a	1p2 Note a	1p2 Note a	1p2 Note a	1p2 Note a
Add (CG)	2,3 5N1* 4,5 7N1**,6 (Ap1)	2,3 5N1* 4,5 7N1**,6 (Ap1)	2,3 5N1* 4,5 7N1**,6 (Ap1)	2,3 5N1* 4,5 7N1**,6 (Ap1)	2,3 5N1* 4,5 7N1**,6 (Ap1)
Boom Add (CG)	3p0 7,8,9 (2p5)	3p0 7,8,9 (2p5)	3p0 7,8,9 (2p5)	1p7 7,8,9 (2p3)	2p7 7,8,9 (2p3)
Boom Add (CG)	4p7 10,11,12 (4p2)	4p7 10,11,12 (4p2)	4p7 10,11,12 (4p2)	4p7 10,11,12 (4p0)	4p7 10,11,12 (4p0)
Boom Add (CG)	10p0 AA(L) Note b (4p2)	10p0 AA(L) Note b (4p2)	10p0 AA(L) Note b (4p2)	10p0 AA(L) Note b (4p2)	10p0 AA(L) Note b (4p2)
Boom Add (CG)	11p0 AA(S) 13,E (6p0)	11p0 AA(S) 13,14,E (6p4)	11p0 AA(S) 13 thr E (7p0)	11p0 AA(S) 13thr E (7p2)	11p0 AA(S) 13 thr E (7p7)
Boom Add			13p7 PT	13p7 PT	13p7 PT

2E + Bays	13	14	15	16	17
L/Nose	7N1	7N1	7N1	8N1	8N1
Launch Position LRP	(6p0) LZ 7 Note c	(6p4) LZ 4 Note c	(7p0) LZ 3 Note c	(7p0) LZ 7 Note c	(7p6) LZ 5 Note c
Launch Add	6p2 PT	PT			
Launch Add	10p6 PT	11p6 PT	12p6 PT	13p6 PT	14p6 PT
Remove	RRB FRB	RRB FRB	RRB FRB	RRB FRB	RRB FRB
Launch Add	13p2 AA(S)	14p2 AA(S)	15p2 AA(S)	16p2 AA(S)	17p2 AA(S)
Launch Add	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)
Complete by:	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
 - b. Stop boom/launch to add long or short links, light tackle and anti-flutter as required.
 - c. Check the LR is under the LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft. (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
 - d. Boom to 6 ft. (1.8 m) from A peg or ETP overhangs CRB by min. 1.5 ft. (0.5 m).
 - e. Install ex FRB in front of CRB and then reposition LRP 12 ft. (3.6 m) from A peg.
 - f. Launch to required far bank bearing or until end of ETP overhangs Ex FRB by 1.5 ft. (0.5 m).
 - g. Put bridge on ground.
- * Add given length of launching nose with LRP secured with tie-down strap.
- ** Nose completed by adding further LNH's.
- () Center of gravity.

**TABLE 2-31 Building and Boom Table-2E +18 through 2E
22 Bay Link Reinforced (Normal Site)**

Bridge ft. Length .	138 42.1	144 43.9	150 45.7	156 47.6	162 49.2
2E + Bays	18	19	20	21	22
L/Nose	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Counter- weight		[8D]	[20D+ 6C]	[30D+ 6C]	[40D+ 6C]
Build E + 1 with RRB at:	1p2 Note a	1p2 Note a	1p2 Note a	1p2 Note a	1p2 Note a
Add	2,3 6N1* 4,5 3N2** 6.7 (Ap2)	2,3 6N1* 4,5 3N2** 6.7 (Ap2)	2,3 6N1* 4,5 3N2** 6.7 (Ap2)	2,3 6N1* 4,5 3N2** 6.7 (Ap2)	2,3 6N1* 4,5 3N2** 6.7 (Ap2)
Boom Add (CG)	2p7 8,9,10 2p3	2p7 8,9,10 2p3	2p7 8,9,10 2p3	2p7 8,9,10 2p3	2p7 8,9,10 2p3
Boom Add (CG)	4p5 11,12,13 (4p0)	4p5 11,12,13 (4p0)	4p5 11,12,13 (4p0)	4p5 11,12,13 (4p0)	4p5 11,12,13 (4p0)
Boom Add (CG)	10p0 AA(L) Note b (4p0)	10p0 AA(L) Note b (4p0)	10p0 AA(L) Note b (4p0)	10p0 AA(L) Note b (4p0)	10p0 AA(L) Note b (4p0)
Boom Add (CG)	11p0 AA(S) 14 thru 17 6p0	11p0 AA(S) 14 thru 17 6p0	11p0 AA(S) 14 thru 17 6p0	11p0 AA(S) 14 thru 17 6p0	11p0 AA(S) 14 thru 17 6p0

2E + Bays	18	19	20	21	22
L/Nose	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Boom Add	13p0 18,E	13p0 18,19	13p0 18 thr 20	13p0 18 thr 21	13p0 18 thr 22
(CG	7P7	7P7	7P7	7P7	7P7
Boom Add	13p7 PT	13p7 PT E,[8D]	13p7 PT E,[20D +6C]	13p7 PT	13p7 PT
(CG	(7p6)	(8p5)	(9p6)	(8p0)	(8p4)
Boom Add (CG				15p0 E,[3D] (9p4)	15p4 E,[3D] (10p0)
Launch Position LRP	(8p0) LZ 9 Note c	(8p5) LZ 7 Note c	(9p6) LZ 7 Note c	(9p4) LZ 2 Note c	(10p0) LZ 2 Note c
Launch Add				15p0 [27D +6C]	15p0 [37D +6C]
Launch Add	15p5 PT	16p5 PT	17p5 PT	18p5 PT	19p5 PT
Remove	RRB	RRB	RRB	RRB	RRB
Launch Add	18p2 AA(S)	19p2 AA(S)	20p2 AA(S)	21p2 AA(S)	22p2 AA(S)
Remove	FRB	FRB	FRB	FRB	FRB
Launch Add	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)
Complete by:	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g	Note d, e, f, g

NOTES:

- a. Add LNCG posts, LNCG and nose roller.
- b. Stop boom/launch to add long or short links, light tackle and anti-flutter as required.
- c. Check that LR is under LZ given or higher. Remove nose sections as they pass LRP, observing minimum 5 ft. (1.5 m) overhang. Leave last three nose sections in place until far bank end of bridge has been lowered to ground.
- d. Boom to 6 ft. (1.8 m) from A peg or ETP overhangs CRB by min. 1.5 ft. (0.5 m).
- e. Install ex FRB in front of CRB and then reposition LRP 12 ft. (3.6 m) from A peg.
- f. Launch to required far bank bearing or until end of ETP overhangs ex FRB bt 1.5 ft (0-.5 m).
- g. Reposition counterweight deck units to final position and put bridge on ground.
- * Add given length of launching nose with LRP secured with tie-down strap.
- ** Nose completed by adding further LNH's.
- [] Counterweight.
- () Center of gravity.

TABLE 2-32 Delaunch Table – 2E + 13 through 2E + 17 Bay
Link Reinforced

Bridge Length	ft m	108 32.9	114 34.8	120 36.6	126 38.4	132 40.2
2E + Bays		13	14	15	16	17
L/Nose		7N1	7N1	7N1	8N1	8N1
V Dist	ft M	118.6 36.16	124.9 38.06	129.1 39.36	136.7 41.66	142.6 43.46
Build		Notes a thru f	Notes a thru f	Notes a thru f	Notes a thru f	Notes a thru f
Delaunch Add		Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)
Delaunch Remove		13p2 AA(S)	14p2 AA(S)	15p2 AA(S)	16p2 AA(S)	17p2 AA(S)
Delaunch Remove		10p6 PT	11p6 PT	12p6 PT	13p6 PT	14p6 PT
Add		RRB FRB	RRB FRB	RRB FRB	RRB FRB	RRB FRB
Boom Remove		6p2 PT				
Delaunch Recover		(6p0) LRP	(6p4) LRP	(7p0) LRP	(7p2) LRP	(7p6) LRP
Boom Remove			PT	13p7 PT	13p7 PT	13p7 PT
Boom Remove		11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)
Boom Remove		10p0 AA(L) E,13	10p0 AA(L) E,14,13	10p0 AA(L) E thr 13	10p0 AA(L) E thr 13	10p0 AA(L) E thr 13

2E + Bays	13	14	15	16	17
L/Nose	7N1	7N1	7N1	8N1	8N1
Boom	4p7	(4p7)	4p7	4p7	4p7
Remove	12,11	12,11	12,11	12,11	12,11
	10	10	10	10	10
(CG)	(2p5)	(2p5)	(2p5)	(2p3)	(2p3)
Boom	3p0	3p0	3p0	3p0	3p0
Remove	9,8,7	9,8,7	9,8,7	9,8,7	9,8,7
(CG)	(Ap1)	(Ap1)	(Ap1)	(Ap3)	(Ap3)
Boom	1p2	1p2	1p2	1p2	1p2
Remove	6,7N1	6,7N1	6,7N1	6,8N1	6,8N1
	6N1	6N1	6N1	7N1	7N1
	5,4	5,4	5,4	6N1	6N1
	5N1*	5N1*	5N1*	5,4	5,4
	3,2	3,2	3,2	5N1*	5N1*
				3,2	3,2
(CG)	(Bp3)	(Bp3)	(Bp3)	(Bp3)	(Bp3)
Boom	Bp2	Bp2	Bp2	Bp2	Bp2
Remove	1,E	1,E	1,E	1,E	1,E)
Compl. By:	Note g	Note g	Note g	Note g	Note g

NOTES:

- a. Remove curbs, ramps and deck units.
 - b. Position ex. FRB under bridge min. 1.5 ft. (0.5 m) from end.
 - c. Add LNCG posts, LNCG, nose roller and install launching nose, then reposition LRP 12 ft from A peg.
 - d. Delaunch bridge until far BSB is 6 ft. (1.8 m) from A peg or end of
 - e. Reposition LRP against A peg and then remove ex. FRB.
 - f. Stop boom/delaunch to remove long or short links, light tackle, anti-flutter and add launching noses as required, observing minimum 5ft. (1.5 m) overhang.
 - g. Disassemble FRB and RRB. Clear site.
- * Remove remainder of launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

TABLE 2-33 Delaunch Table – 2E + 18 through 2E + 22 Bay
Link Reinforced

Bridge Length	ft m	138 42.1	144 43.9	150 45.7	156 47.6	162 49.4
2E + Bays		18	19	20	21	22
L/Nose		6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Counter-weight			[8D]	[20D +6C]	[30D +6C]	[40D +6C]
V Dist	ft m	148.8 45.36	154.7 47.16	160.6 48.96	165.2 50.36	168.8 51.45
Build		Notes a thru f	Notes a thru f	Notes a thru f	Notes a thru f	Notes a thru f
Delaunch Remove		Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)	Dp2 AA(L)
Delaunch Remove		18p2 AA(S)	19p2 AA(S)	20p2 AA(S)	21p2 AA(S)	22p2 AA(S)
Add		FRB	FRB	FRB	FRB	FRB
Delaunch Remove		15p5 PT	15p5 PT	15p5 PT	15p5 PT	15p5 PT
Add		RRB	RRB	RRB	RRB	RRB
Delaunch Remove					15p0) [27D +6C]	(15p0) [37D +6C]
Delaunch Recover		(8p0) LRP	(8p5) LRP	(9p6) LRP	(9p4) LRP	(10p0) LRP
Boom Remove (CG)					15p0 E,[3D] (8p0)	15p4 E,[3D] (8p4)

2E + Bays	18	19	20	21	22
L/Nose	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Boom Remove	13p7 PT	13p7 E,[8D] PT	13p7 E,[20D] +6C] PT	13p7 PT	13p7 PT
(CG)	(7p7)	(7p0)	(7p4)	(8p0)	(6p0)
Boom Remove	13p0 E,18 (6p0)	13p0 19,18 (6p0)	13p0 20,19 18 (6p0)	13p0 21 thru 18 (6p0)	13p0 22 thru 18 (6p0)
(CG)					
Boom Remove	11p0 AA(S) 17 thru 14	11p0 AA(S) 17 thru 14	11p0 AA(S) 17 thru 14	11p0 AA(S) 17 thru 14	11p0 AA(S) 17 thru 14
Boom Remove (CG)	10p0 AA(S) (4p0)	10p0 AA(S) (4p0)	10p0 AA(S) (4p0)	10p0 AA(S) (4p0)	10p0 AA(S) (4p0)
Boom Remove (CG)	4p5 13,12 11 (2p3)	4p5 13,12 11 (2p3)	4p5 13,12 11 (2p3)	4p5 13,12 11 (2p3)	4p5 13,12 11 (2p3)
Boom Remove (CG)	2p7 10,9,8 (Ap2)	2p7 10,9,8 (Ap2)	2p7 10,9,8 (Ap2)	2p7 10,9,8 (Ap2)	2p7 10,9,8 (Ap2)

2E + Bays	18	19	20	21	22
L/Nose	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2	6N1+ 3N2
Boom Remove	1p2 7,6 3N2** 5,4 6N1* 3,2 (CG)	1p2 7,6 3N2** 5,4 6N1* 3,2 (Bp3)	1p2 7,6 3N2** 5,4 6N1* 3,2 (Bp3)	1p2 7,6 3N2** 5,4 6N1* 3,2 (Bp3)	1p2 7,6 3N2** 5,4 6N1* 3,2 (Bp3)
Boom Remove	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E	Bp2 1,E
Compl. By:	Note g	Note g	Note g	Note g	Note g

NOTES:

- a. Remove curbs, ramps and deck units and add counterweight if required.
 - b. Position ex. FRB under bridge min. 1.5 ft. (0.5 m) from end.
 - c. Add LNCG posts, LNCG, nose roller and install launching nose, then reposition LRP 12 ft from A peg.
 - d. Delaunch bridge until far BSB is 6 ft. (1.8 m) from A peg or end of ETP overhangs CRB by min. 1.5 ft (0.5 m).
 - e. Reposition LRP against A peg and then remove ex. FRB.
 - f. Stop boom/delaunch to remove long or short links, light tackle, anti-flutter and add launching noses as required, observing minimum 5ft. (1.5 m) overhang.
 - g. Disassemble FRB and RRB. Clear site.
- ** Remove double story launching nose.
- * Remove remainder of launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

TABLE 2-34 Delaunch Table – 2E + 13 through 2E + 17 Bay
Link Reinforced (Normal Site – Original Far Bank)

Bridge Length	ft m	108 32.9	114 34.8	120 36.6	126 38.4	132 40.2
2E + Bays		13	14	15	16	17
L/Nose		7N1	7N1	7N1	8N1	8N1
V Dist	ft m	118.6 36.16	124.9 38.06	129.1 39.36	136.7 41.66	142.6 43.46
Build		Notes a thru g	Notes a thru g	Notes a thru g	Notes a thru g	Notes a thru g
Delaunch Add		Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)
Delaunch Remove		13p2 AA(S)	14p2 AA(S)	15p2 AA(S)	16p2 AA(S)	17p2 AA(S)
Delaunch Add		12p2 FRB	13p2 FRB	14p2 FRB	15p2 FRB	16p2 FRB
Delaunch Remove		10p6 PT	11p6 PT	12p6 PT	13p6 PT	14p6 PT
Add		RRB	RRB	RRB	RRB	RRB
Delaunch Remove		6p2 PT				
Delaunch Recover		(6p0) LRP	(6p4) LRP	(7p0) LRP	(7p2) LRP	(7p6) LRP
Boom Remove			PT	13p7 PT	13p7 PT	13p7 PT
Boom Remove		11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)

2E+Bays	13	14	15	16	17
L/Nose	7N1	7N1	7N1	8N1	8N1
Boom Remove (GG)	10p0 AA(L) E thru 12 BP11 (3p4)	10p0 AA(L) E thru 12 BP11 (3P4)	10p0 AA(L) E thru 12 BP11 (3p4)	10p0 AA(L) E thru 13 BE12 (3p6)	10p0 AA(L) E thru 13 BP12 (3p6)
Boom Remove (CG)	4p0 TP11,10 BP9 (2p3)	4p0 TP11,10 BP9 (2p3)	4p0 TP11,10 BP9 (2p3)	4p5 TP12,11 BP10 (2p5)	4p5 TP12,11 BP10 (2p5)
Boom Remove (CG)	3p0 TP9,8 BP7 (1p2)	3p0 TP9,8 BP7 (1p2)	3p0 TP9,8 BP7 (1p2)	3p0 TP10,9 BP8 (1p4)	3p0 TP10,9 BP8 (1p4)
Boom Remove	1p7 TP7 BP6 7N1 TP6 BP5 TP5 BP4 6N1*	1p7 TP7 BP6 7N1 TP6 BP5 TP5 BP4 6N1*	1p7 TP7 BP6 7N1 TP6 BP5 TP5 BP4 6N1*	1p7 TP8 BP7 8N1 TP7 BP6 7N1 TP6 BP4 6N1*	1p7 TP8 BP7 8N1 TP7 BP6 7N1 TP6 BP4 6N1*
Boom Remove	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove	1p4 TP4 BP3 TP3 BP2	1p4 TP4 BP3 TP3 BP2	1p4 TP4 BP3 TP3 BP2	1p4 TP4 BP3 TP3 BP2	1p4 TP4 BP3 TP3 BP2

2E+Bays	13	14	15	16	17
L/Nose	7N1	7N1	7N1	8N1	8N1
Boom Remove	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Compl. by:	Note i	Note i	Note i	Note i	Note i

NOTES:

- a. Remove curbs, ramps and deck units.
 - b. Skid bridge to correct bearing.
 - c. Position ex FRB under bridge 3 ft (0.9 m) from new A' peg. Bridge should overhang ex FRB min.1.5 ft (0.5 m)
 - d. Position CRB next to ex FRB.
 - e. Add LNCG posts, LNCG, nose roller and install launching nose, then reposition LRP 12 ft from A peg.
 - f. Delaunch bridge until far BSB is 6 ft (1.8 m) from A peg or end of ETP overhangs CRB by minimum 1.5 ft (0.5 m)
 - g. Reposition LRP against new A peg and then remove ex. FRB.
 - h. Stop boom/delaunch to remove long or short links, light tackle, anti-flutter and add launching noses as required, observing minimum 5ft (1.5 m) overhang.
 - i. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG Posts and nose roller.
- () Center of gravity.

**TABLE 2-35 Delaunch Table-2E + 18 through 2E + 22 Bay
Link Reinforced (Normal Site. - Original Far Bank)**

Bridge ft	138	144	150	156	162
Length m	42.1	43.9	45.7	47.6	49.4
2E+Bays	18	19	20	21	22
L/Nose	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2
C/weight		[8D]	[20D,6C]	[30D,6C]	[40D,6C]
V Dist ft	148.8	154.7	160.6	165.2	168.8
m	45.36	47.16	48.96	50.36	51.45
Build	Notes a thru g	Notes a thru g	Notes a thru g	Notes a thru g	Notes a thru g
Delaunch Remove	Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)	Dp2 Note h AA(L)
Delaunch Remove	18p2 AA(S)	19p2 AA(S)	20p2 AA(S)	21p2 AA(S)	22p2 AA(S)
Add	FRB	FRB	FRB	FRB	FRB
Delaunch Remove	15p5 PT	16p5 PT	17p5 PT	18p5 PT	19p5 PT
Add	RRB	RRB	RRB	RRB	RRB
Delaunch Remove				15p0 [27D,6C]	15p0 [37D,6C]
Delaunch Recover	(8p0) LRP	(8p7) LRP	(9p5) LRP	(9p4) LRP	(10p0) LRP
Boom Remove (CG)					15p4 [3D],E (8p4)

2E+Bays	18	19	20	21	22
L/Nose	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2
Boom Remove (CG)	13p7 PT (7p7)	13p7 [8D],E PT (8P1)	13p7 [20D,6C] E,PT (7p5)	13p7 [3D],E PT (8p2)	13p7 PT (6p0)
Boom Remove (CG)	13p0 E,BP18 (6p3)	13p0 19 BP18 (6p2)	13p0 20,19 BP18 (6p2)	13p0 21 thru 19 BP18 (6p2)	13p0 22 thr 19 BP18 (6p0)
Boom Remove	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)	11p0 AA(S)
Boom Remove (CG)	10p0 AA(L) TP18 17 thr 14 BP13 (3p6)	10p0 AA(L) TP18 17 thr 14 BP13 (3p6)	10p0 AA(L) TP18 17 thr 14 BP13 (3p6)	10p0 AA(L) Tp18 17 thr 14 BP13 (3p6)	10p0 AA(L) TP18 17 thr 14 BP13 (3p6)
Boom Remove (CG)	4p3 TP13 12 BP11 (2p6)	4p3 TP13 12 BP11 (2p6)	4p3 TP13 12 BP11 (2p6)	4p3 TP13 12 BP11 (2p6)	4p3 TP13 12 BP11 (2p6)
Boom Remove (CG)	3p0 T11,10 BP9 (1p4)	3p0 TP11,10 BP9 (1p4)	3p0 TP11,10 BP9 (1p4)	3p0 TP11,10 BP9 (1p4)	3p0 TP11,10 BP9 (1p4)
Boom Remove	1p7 TP9 8,BP7 3N2 TP7,6 5,BP4 6N1*	1p7 TP9 8,BP7 3N2 TP7,6 5,BP4 6N1*	1p7 TP9 8,BP7 3N2 TP7,6 5,BP4 6N1*	1P7 TP9 8,BP7 3N2 TP7,6 5,BP4 6N1*	1p7 TP9 8,BP7 3N2 TP7,6 5,BP4 6N1*

2E+Bays	18	19	20	21	22
L/Nose	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2	6N1,3N2
Boom Remove	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A	2p0 Pin at A
Boom Remove	1p4 TP4,3 BP2	1p4 TP4,3 BP2	1p4 TP4,3 BP2	1p4 TP4,3 BP2	1p4 TP4,3 BP2
Boom Remove	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1	Bp0 TP2,1
Boom Remove	Bp2 E	Bp2 E	Bp2 E	Bp2 E	Bp2 E
Compl. by:	Note i	Note i	Note i	Note i	Note i

NOTES.

- a. Remove curbs, ramps and deck units and add counterweight if required.
 - b. Skid bridge to correct bearing.
 - c. Position ex. FRB under bridge 3 ft (0.9 m) from new A peg. Bridge should overhang ex FRB min.1.5 ft (0.5 m).
 - d. Position CRB next to ex FRB.
 - e. Add LNCG posts. LNCG, nose roller and install launching nose, then position LRP 12 ft from A peg.
 - f. Delaunch bridge until far BSB is 6 ft (1.8 m) from A peg or end of ETP overhangs CRB by min. 1.5 ft (0.5 m)
 - g. Reposition LRP against new A peg and then remove ex. FRB.
 - h. Stop boom/delaunch to remove long or short links, light tackle, anti-flutter and add launching noses as required, observing minimum 5 ft (1.5 m) overhang.
 - i. Disassemble FRB and RRB. Clear site.
- * Remove entire launching nose, LNCG, LNCG posts and nose roller.
- () Center of gravity.

Table 2-36 V Distance For 2E + 1 through 2E + 6 Bay
Double story Bridges - Normal and Restricted Sites.

	Length of Bridge 2E + Number of Bays					
	1	2	3	4	5	6
Brg Lgth (m)	11.0	12.8	14.6	16.5	18.3	20.1
Normal Site						
Nose Conf.	2N1	3N1		4N1		
V Distance	11.6	13.7	15.5	17.0	19.2	21.0
Restricted Site						
Nose Conf.	3N1	4N1		4N1 5N1	5N1 or 6N1	
V Distance	11.9	13.7	15.5	17.4	19.2	21.0

Table 2-37 V Distance For 2E + 7 through 2E + 12 Bay
Double Story Bridges - Normal and Restricted Sites.

	Length of Bridge 2E + Number of Bays					
	7	8	9	10	11	12
Brg Lgth (m)	21.9	23.8	25.6	27.4	29.3	31.1
Normal Site						
Nose Conf.	4N1	5N1		6N1		
V Distance	22.6	24.7	26.5	28.0	30.2	32.0
Restricted Site						
Nose Conf.	5N1 6N1	6N1 or 7N1		7N1 or 8N1		
V Distance	22.9	24.7	26.5	28.3	30.2	32.0

Table 2-38 Distance For 2E + 13 through 2E + 17 Bay
Double Story Bridges (w/o LRS) - Normal and Restricted Sites.

	Length of Bridge 2E + Number of Bays Without LRS.				
	13	14	15	16	17
Brig Lgth (m)	32.9	34.8	36.6	38.4	40.2
Normal Site					
Nose Conf.	6N1	7N1			8N1
V Distance	33.5	35.7	37.5	39.0	41.1
Restricted Site					
Nose Conf.	8N1				
V Distance	33.4	35.2	37.0	38.9	40.7

Table 2-39 V Distance For 2E + 18 through 2E + 22 Bay
Double Story Bridges (w/o LRS) - Normal and Restricted Sites.

	Length of Bridge 2E + Number of Bays Without LRS.				
	18	19	20	21	22
Brig Lgth (m)	42.1	43.9	45.7	47.6	49.4
Normal Site					
Nose Conf.	8N1		6N1 + 3N2		
V Distance	43.0	48.3	49.1	49.7	50.3
Restricted Site					
Nose Conf.	8N1			6N1 + 3N2	
V Distance	42.5	44.3	46.2	48.0	49.8

Table 2-40 V Distance For 2E + 13 through 2E + 17 Bay
Double Story Bridges (w/LRS) - Normal Site.

	Length of Bridge 2E + Number of Bays With LRS.				
	13	14	15	16	17
Brg Lgth (m)	33.2	35.1	36.9	38.7	40.5
Normal Site					
Nose Conf.	7N1			8N1	
V Distance	36.16	38.06	39.36	41.66	43.46

Table 2-41 V Distance For 2E + 18 through 2E + 22 Bay
Double Story Bridges (w/LRS) -Normal Site.

	Length of Bridge 2E + Number of Bays With LRS.				
	18	19	20	21	22
Brg Lgth (m)	42.4	44.2	46.0	47.9	49.7
Normal Site					
Nose Conf.	6N1 + 3N2				
V Distance	45.36	47.16	48.96	50.36	51.45

Index

A

- Abbreviations
 - glossary: 10-1 1-6
 - list. 10-1 1-4
- Add. Auth. List: 10-1 C-1
- Adjustable Support
 - description: 10-1 1-28
 - maint.: 10-1 8-18,8-22, 8-28
- Anchor Assembly
 - description: 10-1 1-46
 - general drills: 10-1 4-52
- Anchorage, Single Story: 10-1 5-48
- Anchorage Pin, description: 10-1 1-44
- Anti Flutter Tackle, general drills: 10-1 4-62
- Anti-flutter Tackle, description- 10-1 1-48
- Anti-Skid. maint.: 10-1 8-38

B

- Bankseat Beam
 - description: 10-1 1-15
 - resilient mount, main.: 10-1 8-8
 - shoot bolt, maint.: 10-1 8-10
- Baseplate Double Story, description: 10-1 1-27
- Baseplate Single Story, description: 10-1 1-26
- Basket Loads: 10-1 E-12
- Bottom Panel
 - description: 10-1 1-21
 - general drills: 10-1 4-18
 - resilient mount, main.: 10-1 8-8
 - shoot bolt, maint.: 10-1 8-12
- Bracing Pin, description. 10-1 1-26
- Bridge Marker Guide, description 10-1 1-19
- Build and Boom Table
 - Double Story
 - 1 thru 3 bay (res.): 10-2 2-23
 - 1 thru 6 bay: 10-1 6-3; 10-22-15
 - 1 thru 6 bay (res.): 10-1 6-7

10 thru 12 bay (res.): 10-1
6-9; 10-2 2-28
13 thru 17 bay w/LRS: 10-1
7-2; 10-2 2-81
13 thru 17 bay w/o LRS:
10-1 6-5; 10-2 2-19
13 thru 17 bay w/o LRS
(res.): 10-1 6-11; 10-2
2-31
18 thru 22 bay w/LRS: 10-1
7-4; 10-2 2-84
18 thru 22 bay w/o LRS:
10-1 6-6; 10-2 2-21
18 thru 22 bay w/o LRS
(res.): 10-1 6-12; 10-2
2-33
4 thru 6 bay (res.): 10-2
2-24
7 thru 12 bay: 10-1 6-4;
10-2 2-17
7 thru 9 bay (res.): 10-1
6-8; 10-2 2-26
Single Story
4 thru 6 bay: 10-1 5-3;
10-2 2-2
9 thru 12 bay: 10-1 5-4;
10-2 2-4
9 thru 12 bay (res.): 10-1
5-5; 10-2 2-6
Building Pedestal, description:
10-1 1-42

C

C of G: 10-1 4-2

Index-2

C.O.I.E. & Basic Issue: 10-1
B-1
Capsill, description: 10-1 1-51
Capsill Pin, description: 10-1
1-54
Carrying Bar, description: 10-1
1-45
Carrying Handle. description:
10-1 1-46
Components/Bridge Length:
10-1 E-1
Counterweights
Double Story 10-1 6-71
Single Story: 10-1 5-41
Curb, description: 10-1 1-18

D

Davit Post Assembly, description:
10-1 1-52
De-Launch Table
Double Story
1 thru 4 bay (res.): 10-1
6-21; 10-2 2-52
1 thru 5 bay (res. far bank):
10-1 6-28; 10-2 2-65
1 thru 6 bay: 10-1 6-13;
10-2 2-36
1 thru 6 bay (far bank):
10-1 6-17; 10-2 2-44
10 thru 12 bay (res. far
bank): 10-1 6-31; 10-2
2-71

10 thru 12 bay (res.): 10-1
 6-24; 10-2 2-58
 13 thru 17 bay w/LRS: 10-1
 7-7; 10-2 2-88
 13 thru 17 bay w/o LRS:
 10-1 6-15; 10-2 2-40
 13 thru 17 bay w/o LRS (far
 bank): 10-1 6-19; 10-2
 2-48
 13 thru 17 bay w/o LRS
 (res. far bank): 10-1 6-33;
 10-2 2-74
 13 thru 17 bay w/o LRS
 (res.): 10-1 6-26; 10-2
 2-60
 18 thru 22 bay w/LRS: 10-1
 7-9; 10-2 2-91
 18 thru 22 bay w/o LRS:
 10-1 6-16; 10-2 2-42
 18 thru 22 bay w/o LRS (far
 bank): 10-1 6-20; 10-2
 2-50
 18 thru 22 bay w/o LRS
 (res. far bank): 10-1 6-35;
 10-2 2-77
 18 thru 22 bay w/o LRS
 (res.): 10-1 6-27; 10-2
 2-62
 5 thru 6 bay (res.): 10-1
 6-22; 10-2 2-54
 6 thru 9 bay (res. far bank).
 10-1 6-29; 10-2 2-68

7 thru 12 bay: 10-1 6-14;
 10-2 2-38
 7 thru 12 bay (far bank):
 10-1 6-18; 10-2 2-46
 7 thru 9 bay (res.): 10-1
 6-23; 10-2 2-56
 Single Story
 4 thru 8 bay: 10-1 5-6;
 10-2 2-8
 9 thru 12 bay: 10-1 5-7;
 10-2 2-11
 9 thru 12 bay (res.): 10-1
 5-8; 10-2 2-13

Deck Unit, description: 10-1
 1-18

Double Story
 12 bay assembly: 10-1 6-37
 12 bay disassembly: 10-1
 6-42
 12 bay disassembly (far bank):
 10-1 6-48
 12 bay disassembly (res. far
 bank): 10-1 6-68
 12 bay disassembly (res.):
 10-1 6-66
 22 bay assembly (w/o LRS):
 10-1 6-53
 22 bay disassembly (w/o LRS):
 10-1 6-58

Index-3

E

End Taper Panel
description: 10-1 1-23
resilient mount, maint: 10-1
8-8

Equip Data: 10-21-2

Equipment Bag. description
10-1 1-68

Equipment Basket. description
10-1 1-69

Erection and Launching Compo-
nents. description: 10-1 1-26

Expend./Durable: 10-1 D-1

Extractor Cable, description
10-1 1-65

F

First Link. general drills: 10-1
4-52

Fixed Support
description: 10-1 1-27
maim: 10-1 8-30

Footwalk
description: 10-1 1-52
general drills: 10-1 4-56

Footwalk Bearer. description
10-1 1-50

Footwalk Post, description: 10-1
1-57

Frame Cross Girder, description:
10-1 1-29

Front End of Bridge, general
drills: 10-1 4-20

G

Guard Rope. description: 10-1
1-61

H

Headless Panel Pin: 10-1 1-25

Hydraulic Jack 15 Ton, descrip-
tion: 10-1 1-31

Hydraulic Jack 15T, maint.: 10-1
8-24

Hydraulic Jack 20 Ton, descrip-
tion: 10-1 1-31

Hydraulic Jack 20T, maint.: 10-1
8-34

I

Introduction: 10-2 1-1

J

Jack Post
description: 10-1 1-33
maint.: 10-1 8-26

Index-4

Jack Seat, description: 10-1
1-32

Jack Support, description: 10-1
1-34

Jacking Bracket
description: 10-1 1-50
maint.: 10-1 8-32

Junction Panel
description: 10-1 1-22
resilient mount, maint.: 10-1
8-8
shoot bolt, maint.: 10-1 8-10

L

L Z No.: 10-1 4-3

Landing Roller, description 10-1
1-40

Landing Poller Pedestal
general drills: 10-1 4-49
MK.I., description: 10-1 1-41
MK.II., description: 10-1 1-56

Launching Nose, general drills
assemble for launch: 10-1
4-35
assembling for de-launch:
10-1 4-46
stripping for de-launch: 10-1
4-45

Launching Nose Code: 10-1
4-3

Launching Nose Cross Girder,
description: 10-1 1-39

Launching Nose cross Girder
Post, description: 10-1 1-38

Launching Nose Heavy
description: 10-1 1-36
resilient mount, maint.: 10-1
8-8
shoot bolt, maim: 10-1 8-10

Launching Nose Link, descrip-
tion: 10-1 1-54

Launching Nose Pin, description:
10-1 1-44

Launching Nose Roller
description: 10-1 1-37
general drills: 10-1 4-32

Lifting Sling, description 10-1
1-66

Light Launching Nose
Front Section, description:
10-1 1-34
Pear Section, description:
10-1 1-35

Light Tackle
description: 10-1 1-62
general drills: 10-1 4-61

Link Components. general drills:
10-1 4-52

Link Reinforced, 22 bay assem-
bly 10-1 7-11

Link Reinforcement Components,
description, 10-1 1-46

Index-5

LNCG
 general drills: 10-1 4-33
 maint.: 10-1 8-16,8-20

LNCG Post, general drills: 10-1
4-33

Long Reinforcing Link, descrip-
tin: 10-1 1-55

Longitudinal Girder, description:
10-1 1-31

M

Medium Girder Bridge, principles
of operation: 10-1 1-84

MGB
 date: 10-1 1-71
 description: 10-1 1-8
 interface of components: 10-1
1-84

N

Nylon Faced Hammer, descrip-
tion: 10-1 1-52

O

Operator
 lubrication: 10-1 8-2

Index-6

 maint.: 10-1 8-1
 troubleshooting: 10-1 8-2

Overbridges, Single Story: 10-1
5-43

P

Packing, description: 10-1 1-70
Pallet, description: 10-1 1-63
Pallet Adapter, description: 10-1
1-65

Pallet Loads: 10-1 30

Palletization
 double story: 10-1 3-74
 link reinf.: 10-1 3-98
 loading on vehicles: 10-1
3-111
 off loading from vehicles:
 10-1 3-121
 single story: 10-1 3-46
 spares: 10-1 3-111

Panel Erection Aid. description:
10-1 1-45

Panel Pin, description: 10-1
1-25

Panel Point Coda: 10-1 4-2

PMCS: 10-1 2-1
 daily: 10-1 2-2
 monthly: 10-1 2-3

Post Tensioning Assembly, de-
scription: 10-1 1-58

Post Tensioning Assy, general
drills: 10-1 4-56

Preparation for Use

choice of bridge: 10-1 3-14
design: 10-1 3-17
prelim. planning: 10-1 3-1
prelim. studies: 10-1 3-7
recon. report: 10-1 3-14
site selection: 10-1 3-7
times: 10-1 3-17
work party: 10-1 3-17

Puller

description: 10-1 1-59
general drills: 10-1 4-63
maint.: 10-1 8-36

Push Bar Adapter, description:
10-1 1-43

Push Bar Cross Girder, descrip-
tion: 10-1 1-42

Push Bar Long, description:
10-1 1-49

Push Bar Short, description:
10-1 1-42

R

Ramp Unit Short and Long, De-
scription: 10-1 1-16

Ratchet Wrench 3/4 in, descrip-
tion: 10-1 1-61

Rear End of Bridge, general
drills: 10-1 4-25

References: 10-1 A-1

Retainer Clip, description: 10-1
1-26

Rocking Roller, description:
10-1 1-60

Roller Beam
description: 10-1 1-30
maint.: 10-1 8-14

Roller Beams, general drills:
10-1 4-4

Rubber Bumper, description:
10-1 1-66

S

Second Link, general drills: 10-1
4-56

Short Reinforcing Link. descrip-
tion: 10-1 1-55

Single Story

12 bay assembly: 10-1 5-20

12 bay assembly (res.): 10-1
5-32

12 bay disassembly: 10-1
5-27

12 bay disassembly (res.):
10-1 5-37

5 bay assembly: 10-1 5-9

5 bay disassembly: 10-1 5-14

Strap

10,000lb, description: 10-1
1-68

Index-7

5,000lb, description: 10-1
1-67

Support Equipment, descriptions
10-1 1-63

Sway Brace, description: 10-1
1-24

T

Tensioning, general drills: 10-1
4-63

Tie Down Lug, description: 10-1
1-69

Tie Down, Cargo, Aircraft,MB-1,
description: 10-1 1-69

Top Panel

description: 10-1 1-14
general drills: 10-1 4-16
resilient mount, maint.: 10-1
8-8
shoot bolt, maint.: 10-1 8-10

Trailer, 4 Ton, description: 10-1
1-64

Truck, 5 Ton Dump, description:
10-1 1-64

U

Unusual Conditions

high winds: 10-1 2-4
operation: 10-1 2-4
steep slopes: 10-1 2-6

V


V Distance Table, Double Story

1 thru 6 bay: 10-2 2-95
13 thru 17 bay w/LRS: 10-2
2-99
13 thru 17 bay w/o LRS: 10-2
2-97
18 thru 22 bay w/LRS: 10-2
2-99
18 thru 22 bay w/o LRS: 10-2
2-98
7 thru 12 bay: 10-2 2-96

**By order of the Secretary of the Army and Navy
(Including the Marine Corps):**

GORDON R. SULLIVAN
General, United States Army
Chief of Staff

Official:



MILTON H. HAMILTON
Administrative Assistant to the
Secretary of the Army
03504

DAVID E. BOTTORFF
Rear Admiral, CEC, US Navy
Commander
Navy Facilities Engineering
Command

RONALD D. ELLIOT
Executive Director
Marine Corps Systems Command

DISTRIBUTION:

To be distributed in accordance with DA Form
12-25-E, block no. 6020, requirements for
TM 5-5420-212-10-2.

RECOMMENDED CHANGES TO EQUIPMENT TECHNICAL PUBLICATIONS

SOMETHING WRONG

WITH THIS PUBLICATION?



THEN . . . JOT DOWN THE DOPE ABOUT IT ON THIS FORM, FOLD IT, AND DROP IT IN THE MAIL!

FROM: (PRINT YOUR UNIT'S COMPLETE ADDRESS)

DATE SENT

PUBLICATION NUMBER

PUBLICATION DATE

PUBLICATION TITLE

BE EXACT . . . PIN-POINT WHERE IT IS

PAGE NO.

PARA-GRAPH

FIGURE NO.

TABLE NO.

IN THIS SPACE TELL WHAT IS WRONG AND WHAT SHOULD BE DONE ABOUT IT:

PRINTED NAME, GRADE OR TITLE, AND TELEPHONE NUMBER

SIGN HERE

The Metric System and Equivalents

Linear Measure

- 1 centimeter = 10 millimeters = .39 inch
- 1 decimeter = 10 centimeters = 3.94 inches
- 1 meter = 10 decimeters = 39.37 inches
- 1 dekameter = 10 meters = 32.8 feet
- 1 hectometer = 10 dekameters = 328.08 feet
- 1 kilometer = 10 hectometers = 3,280.8 feet

Weights

- 1 centigram = 10 milligrams = .15 grain
- 1 decigram = 10 centigrams = 1.54 grains
- 1 gram = 10 decigrams = .035 ounce
- 1 dekagram = 10 grams = .35 ounce
- 1 hectogram = 10 dekagrams = 3.52 ounces
- 1 kilogram = 10 hectograms = 2.2 pounds
- 1 quintal = 100 kilograms = 220.46 pounds
- 1 metric ton = 10 quintals = 1.1 short tons

Liquid Measure

- 1 centiliter = 10 milliliters = .34 fl. ounce
- 1 deciliter = 10 centiliters = 3.38 fl. ounces
- 1 liter = 10 deciliters = 33.81 fl. ounces
- 1 dekaliter = 10 liters = 2.64 gallons
- 1 hectoliter = 10 dekaliters = 26.42 gallons
- 1 kiloliter = 10 hectoliters = 264.18 gallons

PIN: 070970-000